Appendix Table of Contents

2-1	Abbreviations	1
2-2	Plan Notes - Sample Format	11
2-3	Engineers & Drainage Certifications	12
2-4	Sample Legend Format	14
3-1	Site Development Concept Plan Flow Chart	15
3-2	Site Development Plan Flow Chart	16
3-3	Permits Flow Chart	17
3-4	Sample Construction Permits	18
3-5	Special Drain Permit Application	27
4-1	Floodplain Review And Request Flow Chart	29
4-2	Floodplain Approval Block	30
5-1	Site Development Concept Plan Application	31
5-2	ESD Matrix	35
5-3	BMP Summary Table	38
5-4	Sample Stream Inventory Checklist	40
5-5	Sample Notification Letter	42
5-6	Sample Affidavit	43
5-7	Sample Approval Letter & Block	44
6-1	Sample Approval Memo	48
7-1	Plan Approval Blocks	51
7-2	General Storm Drain And Plan General Notes	59
8-1	Marlboro Clay Geotechnical Investigation	67
8-2	Overland Sheet Flow (MSHA-61.1-402.1)	69
8-3	Grass Swale Flow Velocity (MSHA-61.1-402.3)	70
8-4	Concrete Swale Flow Velocity (MSHA-61.1-402.4)	71
8-5	Grass Ditch Flow Velocity (MSHA-61.1-402.5)	72
8-6	Concrete Ditch Flow Velocity (MSHA-61.1-402.6)	73
8-7	Gutter Flow Velocity (MSHA-61.1-402.7)	74
8-8	Rational Method Rainfall Intensity Table	
8-9	Pipe Material Specification Table	76
8-10	Sample Pipe Computation Form	77
8-11	Sample Structure Schedule	79
8-12	Pipe Loading Chart (C-76)	80

8-13	Sample Pipe Schedule	82
8-14	Headloss Coefficient Msha 61.1 – 408.1(K _b)	83
	Sample Headloss Calculation	
8-16	Sample Headloss Form	85
	Curb And Gutter Spread Graph	
8-18	Inlet Capacity	88
8-19	MSHA Inlet Interception And Efficiency Capacity Curve	94
	Structure Width Sample Computation	
	Determining "N" For Riprap Lined Channel Using Depth Of Flow	
	Limiting Velocities For Rip-Rap Lining (Msha-61.1-405.1)	
8-23	M-NCPPC Head/Endwall Stone Veneer Detail	98
9-1	SWM Landscape Criteria	99
9-2	SWM Facility Vegetation Guidelines	100
9-3	Warning Sign	
9-4	Storm Drain Discharge Options Into Swm Facility	108
9-5	M-NCPPC Guidelines For Stormwater Management Facilities	
9-6	Riser Weir And Orifice Flow Scenarios	
9-7	Riser Location Sketch	117
9-8	Low Flow Pipe Examples	118
9-9	Typical Barrel & Riser Profile	119
9-10	Typical Embankment Cross Section	120
9-11	Emergency Spillway Cross Section & Profiles	121
9-12	Geotechnical Testing Requirement For Infiltration Systems	122
	Infiltration Trench Specifications & Notes	
10-1	BMP Summary Table	125
10-2	Sample BMP Calculations	126
10-3	BMP Specification	127
11-1	Easement Processing Flow Chart	142
11-2	Easement Width For Multiple Pipes	143
11-3	Channel/Swale Easement Width	144
11-4	Block Easement Sketch Along Public R/W	145
11-5	County Boiler Plate Easement Language	146
11-6	Right-Of-Way Survey Transmittal	147
	Sample Security Forms	
	Sample Construction Cost Estimate	
12-3	Office Of Law Bond Review Checklist	168
12-4	Sample Acceptance Memorandum	169

13-1	Shop Drawing Submittal Form	.170
14-1	Sample Construction Inspection Form	.173
14-2	Construction Inspection Flow Chart	.198
	Sample Punchlist	
	Construction Inspection Checklists	

ABBREVIATIONS on DRAWINGS

Abbreviations used on drawings shall be "Abbreviations for Use of Drawings and Text"; published by the American National Standards Institute, Inc. (ANSI). Abbreviations should be used only where their meaning is unquestionably clear and when necessary in call-outs. When in doubt—spell out. Do not use abbreviations in general notes except for agency names. Use periods after abbreviations only if the abbreviation itself spells a word. For example, sewer can be abbreviated by "sew", since this is a word; a period is required after the "w". Do not use periods after each letter of an agency. For example, Maryland National Capital Park & Planning Commission shall be abbreviated M-NCPPC not M.N.C.P. & P.C.

Α

American Society for Testing Material	
American Water Works Association	
Amount	
Approve	
Approximate	
Architect	
Architectural	
Architecture	
Area Drain	
As Soon As Possible	
Asbestos-Cement Pipe	
Asphalt	
At	@
Avenue	AVE
Average	AVG
В	
	DOE
Baltimore Gas and Electric Company	
Baltimore Gas and Electric Company	BL
Baltimore Gas and Electric Company	BL BSMT
Baltimore Gas and Electric Company	BL BSMT BRG
Baltimore Gas and Electric Company Base Line Basement Bearing Bench Mark	BL BSMT BRG BM
Baltimore Gas and Electric Company Base Line Basement Bearing Bench Mark Best Management Practice	BL BSMT BRG BM BMP
Baltimore Gas and Electric Company Base Line Basement Bearing Bench Mark Best Management Practice Bituminous	BL BSMT BRG BM BMP BITUM
Baltimore Gas and Electric Company Base Line Basement Bearing Bench Mark Best Management Practice Bituminous Bituminous Coated Corrugated Metal Pipe	BL BSMT BRG BM BMP BITUM BCCMP
Baltimore Gas and Electric Company Base Line Basement Bearing Bench Mark Best Management Practice Bituminous Bituminous Coated Corrugated Metal Pipe Blocking	BL BSMT BRG BM BMP BITUM BCCMP BLKG
Baltimore Gas and Electric Company Base Line Basement Bearing Bench Mark Best Management Practice Bituminous Bituminous Coated Corrugated Metal Pipe Blocking Bottom of Wall	BL BSMT BRG BM BMP BITUM BCCMP BLKG BW
Baltimore Gas and Electric Company Base Line Basement Bearing Bench Mark Best Management Practice Bituminous Bituminous Coated Corrugated Metal Pipe Blocking Bottom of Wall Boundary	BL BSMT BRG BM BMP BITUM BCCMP BLKG BW BDY
Baltimore Gas and Electric Company Base Line Basement Bearing Bench Mark Best Management Practice Bituminous Bituminous Coated Corrugated Metal Pipe Blocking Bottom of Wall	BL BSMT BRG BM BMP BITUM BCCMP BLKG BW BDY BR

Bridge...... BRDG

Abbreviations

Building	BLDG
By (Between Dimensions)	
С	
Cable	CA
Cable Duct	
Cast In Place Concrete	CIPC
Cast Iron Pipe	CIP
Catch Basin	CB
Cellar	C
Cement	CEM
Center	CTR
Center-Line	CL
Center To Center	C TO C
Channel	CHAN
Chesapeake Bay Critical Area	CBCA
Class	CL
Clay Pipe	
Cleanout	
Clear	
Clearance	
Collar	
Concrete	
Concrete Masonry Unit	
Concrete Sewer Pipe-Extra Strength	
Conduit	
Construction	
Construction Joint	
Continuous or Continue	-
Contractor	
Corporation	
Corps of Engineers	
Corrugated Metal Pipe	
Company	
Council of Governments	
Cross Section	
Cubic Foot	
Cubic Foot per Minute	
Cubic Foot per Second	
Cubic Yard	
D	
D	
Degree	° or DEG
Degree Fahrenheit	
Delete	

Abbreviations Issue Date: July 26, 2014

Demolish or Demolition	DEM
Department	
Depressed	
Design	
Development	
Diameter	
Dimension	
Distance.	
Distance	
Division	
Double Yellow	
Downspout	
Drainage Area Map	
Drain Tile	
Drawing	
Dry Well	
Duplicate	DUP
T.	
E	
East	E
Elbow	
Electric	
Elliptical Reinforced Concrete Pipe	
Elevation	
Emergency	
Energy Grade Line	
Engineer	
Entrance	
Equal	
Equipment	
Equivalent	
Existing	
Excavation	
Extended Detention	
Extended Detention	LD
F	
Far Side	
Federal	
Federal Emergency Management Administration	
Field Inspection Report	
Feet or Foot	
Feet per Second	
Fence	FN
Field	EI D

Finish	FIN.
Fire Hydrant	FH
First Floor	FF
Floodplain	FP
Footing	FTG
Foundation	FDN
Future	FUT
G	
Gage, Gauge	GA
Gallon	GAL.
Gallons per Minute	GPM
Galvanize	
Galvanized Iron	
Galvanized Steel	
Gas Line (Natural)	
Gate Valve	
Geographic Information System	
Grade	
Grating	
Gravel	
Ground	
Grout	
Guardrail	
Н	
Hand hole	НН
Head	
Heavy Duty	
Height	
Highway	
High Point	
Horizontal	
Horizontal Elliptical Reinforced Concrete Pipe	
House	
Hydraulic Engineering Center	
Hydraulic Grade Line	
I	
Identification	IDFNT
Inch	
Include (D), (Ing)	
Increase	
Inlet	

Tours	INID
Inner	
Inside Diameter Installation	
Internal	
Invert	
Iron Pipe	
non ripe	11
J	
, and the second se	
Joint	JT
Junction Box	JB
K	
Keyway	KWY
L	
T 1 1	I DI
Label	
Lateral	
Left	
Length	
LongitudeLow Point	
LOW 1 OHIC	LI
M	
Main	MN
Major	MAJ
Manhole	
Manhole Cover	
Maryland National Capital Park and Planning Commission	
Maryland Department of the Environment	
Maryland State Highway Administration	
Masonry	
Mastic Joint	•
Maximum	
Maximum Capacity	
Mechanical	
Median	
Membrane	
Metal	
Mezzanine	
Minimum	
Minute	
Miscellaneous	MISC

Abbreviations

Modify	
Multiple	MUL1
N	
IN	
Nail	N
Narrow	
National	
National Bureau of Standards	
National Pollutant Discharge Elimination System	
Natural Resources Conservation Service	
Natural	
Neutral	NEUT
Nomenclature	NOMEN
Nominal	NOM
Normal	NORM
North	N
Not Applicable or Not Available	NA
Not In Contract	
Not To Scale	NTS
Number	NO. or #
O	
Office	OFF
On Center	OC
Opening	OP
Organization	ORG
Original	ORIG
Outlet	OUT.
Outside	OUT.
Outside Diameter	OD
Outside Face	OF
Over	OV
Overflow	OVFL
P	
Pair	PR
Parallel	PRL
Parking	
Parkway	
Part	
Part of	•
Partial	
Pavement	
Percent	PCT or %

Perforated	PERF
Perimeter	PERI
Permanent	PERM.
Perpendicular	PERP
Pipeline	
Plan View	
Point	PT
Point on Curve.	POC
Point of Intersection	PI
Point of Reverse Curve	
Point of Tangent	PT
Point of Curve	
Point of Vertical Intersection	PVI
Point of Vertical Reverse Curve	PVRC
Point of Vertical Tangent	PVT
Point of Vertical Curve	PVC
Polyvinyl Chloride Pipe	PVC
Position	
Potomac Electric Power Company	PEPCO
Pound	LB
Pounds per Cubic Foot	PCF
Pounds per Square Foot	PSF
Precast	
Precast Concrete	PCC
Preliminary	PRELIM
Pressure Reducing Valve	PRV
Prestressed Concrete Cylinder Pipe	PCCP
Primary	PRI
Prince George's County Department of Environment	PGDOE
Prince George's County Department of Housing And Community Development	PGHCD
Prince George's County Department of Permitting, Inspections and Enforcement	
Prince George's County Department of Public Works and Transportation	
Prince George's Soil Conservation District	PGSCD
Property	PROP
Property Line	PL
Proposed	
Q	
Quality	OUAL
Quantity	
Ouarter	OTR

Radius	RAD or R
Railroad	RR
Reducer	RED.
Remove	REM
Recreation	RCN
Reference	REF
Reference Line	REFL
Reinforced Concrete	RC
Reinforced Concrete Culvert Pipe	RCCP
Reinforced Concrete Pipe	
Relocated	
Remove	REM
Replace	REPL
Require	
Required	
Requirement	
Reservoir	
Return	
Revise (D)	
Right	
Right-Of-Way	
Riser	•
Road	RD
Roof Drain	RD
Round	RND
Runoff Curve Number	RCN
S	
Sanitary	
Scale	
Schedule	
Second	
Section	
Service	
Sewer	
Shoulder	
Shutoff Valve	
Single	
Site Development Concept Plan	
Site Development Plan	
Sketch	
Sleeve	SLV
Slope	SLP
Slotted	SLTD

Small	SM
Solid	
South	
Space	
Specification	
Splash Block	
Spring	
Square	
Square Foot.	
Square Inch	-
Stairway	
Standard	
Steel	
Stone	
Storm Drain	
Storage	
Stormwater Management	
Stormwater Management Facility	
Street	
Structural	
Sump Pit	
Symbol	
T	
Tangent	TAN.
Tank	TK
Tee	T
Temperature	ТЕМР
Temporary	ТЕМР
Terra Cotta Pipe	ТСР
Thick (Ness)	THK
Through	THRU
Time of Concentration	TC
Top, Bottom & Sides	TB&S
Top of Slab	TSL
Top of Wall	TW
Total	ТОТ
Transportation	TRANSP
Treated	TRTD
Tunnel	TNL
Typical	
NRCS Technical Release 20 (Project Formulation Hydrology)	
NRCS Technical Release 55 (Urban Hydrology for Small Watersheds)	TR55

Ultimate	ULT
United States Geological Survey	USGS
Unknown	
Utility	
V	
Valve	V
Valve Box	VB
Velocity	V
Versus	VS
Vertical	VERT
Vertical Elliptical Reinforced Concrete Pipe	VERCP
Vitrified Clay Pipe	VCP
Vitrified Clay Pipe-Extra Strength	VCPES
Volume	VOL
W	
Washington Gas Light Company	
Water	
Water Line	WL
Water Meter	WM
Waterstop	WS
Watertight	WTRTT
Weep hole	WH
Welded	
Welded Wire Fabric	
West	
Width	WD
Wire Mesh	
With (Combine from)	
Without	•
Work	
Working	
Wrought Iron Pipe	WIP
Y	
Year	YR
Yellow	

PLAN NOTES - SAMPLE FORMAT

GENERAL STORM DRAIN NOTES

- 1) ALL STORM DRAINS SHALL BE CONSTRUCTED IN ACCORDANCE WITH THE LATEST EDITION OF THE STORMWATER STANDARDS AND SPECIFICATIONS OF PRINCE GEORGE'S COUNTY DEPARTMENT OF ENVIRONMENTAL RESOURCES, UNLESS OTHERWISE NOTED.
- 2) FOR TYPES OF STRUCTURES REFER TO THE LATEST STORMWATER MANAGEMENT STANDARD DETAILS, DER (SWMSD), UNLESS OTHERWISE NOTED.
- 3) INFORMATION CONCERNING UNDERGROUND UTILITIES WAS OBTAINED FROM AVAILIABLE RECORDS. THE CONTRACTOR MUST DETERMINE THE EXACT LOCATIONS AND ELEVATIONS OF THE UTILITIES BY DIGGING TEST PITS AT ALL UTILITY CROSSINGS WELL IN ADVANCE OF TRENCHING. IF CLEARANCES ARE LESS THAN SPECIFIED, CONTACT THE ENGINEER, AND THE OWNER OF OTHER INVOLVED UTILITY BEFORE PROCEEDING WITH CONSTRUCTION.
- 4) ALL STORM DRAIN PIPES MUST HAVE A MINIMUM OF 1 FOOT COVER.
- 5) ALL INLETS TOP SLAB FRONT FACES SHALL BE PAINTED WITH THE FOLLOWING CHESAPEAKE BAY DRAINAGE, "DON'T DUMP" (STANDARD 82.0).
- 6) CONTRACTORS SHALL ADJUST ALL EXISTING UTILITIES AS NEEDED TO CONSTRUCT PROPOSED ROAD IMPROVEMENTS. ADJUSTMENTS MAY INCLUDE BUT NOT LIMITED TO MANHOLE COVERS, VALVES, FIRE HYDRANTS, STORM DRAIN INLETS, STREET LIGHTS, TRAFFIC SIGNALS STRUCTURES, UTILITY POLES, SIDEWALKS, BURIED UTILITY CONDUIT AND PIPES.

GENERAL INSTRUCTIONS TO CREATE PLAN NOTES

- 1. Maximum width of the note shall be 6.5".
- 2. Separate each item with a space.
- 3. Separate text from item number and maintain text in an even line on at least the right side down the page.
- 4. All text shall be CAPITALIZED.
- 5. Height of text is at least 0.1" or 10 font.

ENGINEERS & DRAINAGE CERTIFICATIONS

I HEREBY CERTIFY THAT THIS PLAN CONFORMS TO THE REQUIREMENTS OF SUBTITLE 32. DIVISION 2 OF THE CODE OF PRINCE GEORGE'S COUNTY WATER RESOURCES PROTECTION AND GRADING CODE; AND THAT I OR MY STAFF HAVE INSPECTED THIS SITE AND THAT DRAINAGE FLOWS FROM UPHILL PROPERTIES ONTO THIS SITE, AND FROM THIS SITE ONTO DOWNHILL PROPERTIES, HAVE BEEN ADDRESSED IN SUBSTANTIALACCORDANCE WITH APPLICABLE CODES.

SIGNATURE:

NAME:	DATE:
MD. REG. NO.:	
STORM DRAIN AS-BUILT CERTIFICA	ATION
"I HEREBY CERTIFY TO THE BEST OF MELIEF THAT THIS AS-BUILT TRULY REFIELD CONDITIONS INCLUDING BUT SIZES, DIAMETERS, LINE AND GRADE	EPRESENTS EXISTING NOT LIMITED TO , AND ELEVATIONS."
SIGNATURE: NAME:	
MD. REG. NO.: BMP AND ESD DEVICE AS-BUILT CE	
"I HEREBY CERTIFY TO THE BEST OF MELIEF THAT THE STORMWATER MAIN FACILITIES (BOTH BMP AND ESD) SHOW HAVE BEEN CONSTRUCTED IN ACCOPLANS AND SPECIFICATIONS APPROGEORGE'S COUNTY DEPARTMENT OF INSPECTION AND ENFORCMENT."	NAGEMENT OWN ON THE PLANS RDANCE WITH THE VED BY PRINCE
SIGNATURE:	
NAME:	DATE:
MD. REG. NO.:	

SMALL POND AS-BUILT CERTIFICATIONS

Certifications Issue Date: July 26, 2014 "I HEREBY CERTIFY THAT THE FACILITY WAS CONSTRUCTED AS SHOWN ON THIS "AS-BUILT" PLAN AND MEETS OR EXCEEDS THE REQUIREMENTS OF THE NATURAL RESOURCES CONSERVATION SERVICE- MARYLAND CONSERVATION PRACTICE STANDARD FOR PONDS (MD-378) AND THE APPROVED POND PLANS AND SPECIFICATIONS".

SIGNATURE ENGINEER-IN-CHARGE DATE MD SEAL/DATE

CERTIFY MEANS TO STATE OR DECLARE A PROFESSIONAL OPINION BASED UPON ONSITE INSPECTIONS AND MATERIAL TESTS, WHICH ARE CONDUCTED DURING CONSTRUCTION. THE ONSITE INSPECTIONS AND MATERIAL TESTS ARE THOSE INSPECTIONS AND TESTS DEEMED SUFFICIENT AND APPROPRIATE BY COMMONLY ACCEPTED ENGINEERING STANDARDS. CERTIFY DOES NOT MEAN OR IMPLY A GUARANTEE BY THE ENGINEER NOR DOES AN ENGINEER'S CERTIFICATION RELIEVE ANY OTHER PARTY FROM MEETING REQUIREMENTS IMPOSED BY CONTRACT, EMPLOYMENT, OR OTHER MEANS, INCLUDING MEETING COMMONLY ACCEPTED INDUSTRY PRACTICES.

Certifications 13


Issue Date: January 26, 2014

SAMPLE LEGEND FORMAT


	EXISTING	PROPOSED
100-YEAR FLOODPLAIN LIMIT	FP	FP
50' FLOODPLAIN BUFFER	FPB	FPB
	(SEC. NO.) =	(SEC. NO.) =
CROSS SECTION	(FP ELEVATION) =	(FP ELEVATION) =
NO FREEBOARD	ELEV = 123.24	ELEV = 123.24
ONE FOOT FREEBOARD	ELEV = 123,24*	ELEV = 123.24*
TWO FOOT FREEBOARD	ELEV = 123.24**	ELEV = 123.24**

100-YEAR FLOODPLAIN LIMIT	FP
50' FLOODPLAIN BUFFER	——— FPB ————
CROSS SECTION	(SEC. NO.) = (FP ELEVATION) =
NO FREEBOARD	ELEV = 123.24
ONE FOOT FREEBOARD	ELEV = 123.24*
TWO FOOT FREEBOARD	ELEV = 123.24**


SITE DEVELOPMENT CONCEPT PLAN FLOW CHART



SITE DEVELOPMENT PLAN FLOW CHART



PERMITS FLOW CHART



SAMPLE CONSTRUCTION PERMITS

- 1. Site Development Rough Grading Permit
- 2. Site Development Fine Grading Permit
- 3. Street Construction Permit
- 4. Special Drain Permit



DEPARTMENT OF PERMITTING, INSPECTIONS AND ENFORCEMENT SITE/ROAD PERMIT PROCESSING UNIT

PERMIT FOR CONSTRUCTION AND RELATED ACTIVITIES WITHIN THE PUBLIC RIGHT-OF-WAY AND PRIVATE PROPERTY SITE WORK



CASE NAME:	SUITLAND STRAY	ER UNIVERSITY	CASE NUMBER:	38497-2012-01
CASE TYPE:	SITE DEVELOPMI	ENT ROUGH GRADING PERI	MIT DISTRICT:	SOUTH
Officer Name : Officer Title : Telephone No:	TIFY THAT THE PERMITT CAMPUS PROPER 16501 NORTH CRO HUNTERS VILLE 1 HANKINS, STEVEN MANAGER (704) 650-3964	TIES, LLC DSS	Owner of Prope CAMPUS PROF 16501 NORTH (HUNTERSVILI	PERTIES, LLC CROSS
Contact Person:	ADRIANWIECHERT,			
HAS PERMISSIO	ON TO PERFORM WITHIN	THE PUBLIC RIGHT-OF-WAY or/and	ON_SITE:	
COMMUNI CROSSWAI CURB & GI EVELOPE END SECTI FEE - IN - I FENCE GATEHOUS X GRADING THE PROPOSED AS APPROVED I ACCORDANCE ' AND STANDARIE	CIAL ENTRANCE CATIONS LK UTTER ER CONTRIBUTION LEU SE CONSTRUCTION SHALL BY THE DEPARTMENT OF WITH SUBTITLE 23 AND S DS FOR HIGHWAY AND SI DS FOR HIGHWAY AND SI	GRAVEL HAUL ROAD HEADWALLS INTERNAL STREETS LANDSCAPING MILL OVERLAY MODIFIED PAVING PAVEMENT STRIPING PLANTER BOX RESTORATION RETAINING WALLS BE PERFORMED AND COMPLETED PERMITTING, INSPECTIONS AND E UBTITLE 32 OF THE PRINCE GEOR REET CONSTRUCTION, AND SUBJI	ENFORCEMENT OF PRINCE GE GE'S COUNTY CODE AND THI ECT TO THE INSPECTION AND	APRON DOUBLE SINGLE DRIVEWAY SWALE PIPE TOTHER: TOTHE
		S MUST BE SATISFIED, INCLUDING BT LIGHTING WORK TO THE LOCAL		BET LIGHTING PLAN AND THE
SEDIMENT CON RELATED SITE/I	TROL#: 101-13 ROAD PERMIT#:		RELATED BUILDING PERMIT STORMWATER PERMIT# :	#:
LOCATION O	F PROPOSED WORK			
STREET NAM AUTH (5110)	e : Way, Britania wa	ζ,		
LOT(S):	BLOCK(S):	PARCEL(S): 482	DPW&T MA 5650C8	AP PAGE & GRID:
		Y SHOULD BE MONITORED BY A C A STABILIZED SUBGRADE.	QUALIFIED GEOTECHNICAL	REPRESENTATIVE OR
THE APPLICANT ALL THE REQUI ENVIRONMENT	FROM OBTAINING A STA RED WORK, OR OBTAINI AL RESOURCES THAT NO	ED THAT THE PERMIT ISSUED BY T TTE DEPARTMENT OF NATURAL RE NG ANY NECESSARY SIGN-OFF FRO REGULATED WETLANDS ARE PRE TLED TO ANY AUTOMATIC EXEMP	SOURCES NON-TIDAL WETLA OM THE PRINCE GEORGE'S CO SENT OR SIGNIFICANTLY AFI	ANDS PERMIT COVERING OUNTY DEPARTMENT OF FECTED BY THE SAID



DEPARTMENT OF PERMITTING, INSPECTIONS AND ENFORCEMENT SITE/ROAD PERMIT PROCESSING UNIT

PERMIT FOR CONSTRUCTION AND RELATED ACTIVITIES WITHIN THE





FEE:

\$30.00 PAID:

STREET SIGN(S) FEE:

\$0.00 PAID:

BOND:

PAID:

BOND #:

BOND CO:

BOND TYPE:

PERMIT ISSUANCE DATE:

July 17, 2013

PERMIT EXPIRATION DATE:

July 17, 2015

HAITHAM A. HIJAZI, DPIE DIRECTOR

IT SHALL BE THE RESPONSIBILITY OF THE APPLICANT TO APPLY FOR AN EXTENSION IN WRITING NOT LESS THAN THIRTY (30) DAYS PRIOR TO THE EXPIRATION DATE. THE APPLICANT SHALL NOTIFY THE DEPARTMENT AT LEAST 48 HOURS PRIOR TO STARTING CONSTRUCTION OR RESTARTING CONSTRUCTION BY CONTACTING DPIE'S INSPECTIONS DIVISION AT 301-883-3820. SELECT THE PROMPT FOR SITE DEVELOPMENT INSPECTION.



DEPARTMENT OF PERMITTING, INSPECTIONS AND ENFORCEMENT

SITE/ROAD PERMIT PROCESSING UNIT





CASE NAME: C	COLLEGE PARK		CASE	NUMBER:	23502-2013-00
CASE TYPE: S	ITE DEVELOPMEN	T FINE GRADING PERMI	T DIST	RICT:	NORTH
	YTHAT THE PERMITTE R & J 7501 LLC 8 NOVA BAYVILLE NY 1170		R&J 8 NO	er of Proper COMPANY OVA VILLE NY	(MD) LLC
Officer Title :	MITTLEMANN, JOSEF MANAGING MEMBER (516) 922-1704				
Contact Person:	WALTZAWISLAK,				
HAS PERMISSION T	O PERFORM WITHIN TI	HE PUBLIC RIGHT-OF-WAY or/and	ON_SITE:		
END SECTION FEE - IN - LIEU FENCE GATEHOUSE X GRADING THE PROPOSED CO AS APPROVED BY TACCORDANCE WIT AND STANDARDS I	TIONS TER CONTRIBUTION INSTRUCTION SHALL B THE DEPARTMENT OF P TH SUBTITLE 23 AND ST FOR HIGHWAY AND STR	GRAVEL HAUL ROAD HEADWALLS INTERNAL STREETS X LANDSCAPING MILL OVERLAY MODIFIED X PAVING PAVEMENT STRIPING PLANTER BOX X RESTORATION RETAINING WALLS E PERFORMED AND COMPLETEI ERMITTING, INSPECTIONS AND BITTLE 32 OF THE PRINCE GEOL EET CONSTRUCTION, AND SUB INS AND ENFORCEMENT OF PRI	SIGN X STOR STREI STREI STREI TEMP TRAF UNDE X UTILI REST D IN ACCORDANC ENFORCEMENT (C RGE'S COUNTY CU JECT TO THE INSI	WALK RAMPS M DRAIN ET LIGHTS* ET TREES ET NAME SIG ENTRANCE FIC SIGNALS REDRAIN TY WORK AN DRATION TE WITH THE I FOR PRINCE GE DDE AND THE DECTION AND	X OTHER: ON-SITE D.A. = 2.98 A ON-SITE SD CMP DESCRIPTION: PLANS AND SPECIFICATIONS ORGE'S COUNTY AND IN E GENERAL SPECIFICATIONS
	The part of the pa	MUST BE SATISFIED, INCLUDIN			ET LIGHTING PLAN AND THE
SEDIMENT CONTRO RELATED SITE/ROA	OL#: 149-13		RELATED BUILD	DING PERMIT	#:
STREET NAME :	ROPOSED WORK /E, COLLEGE AVE,	YALE AVE,			
LOT(S): THRU 0	BLOCK(S): 29	PARCEL(S): 0000 214		PW&T MA 409K3	P PAGE & GRID:
		I SHOULD BE MONITORED BY A STABILIZED SUBGRADE.		409k3 TECHNICAL	REPRESENTATIVE OR
THE APPLICANT FR	ROM OBTAINING A STAT	D THAT THE PERMIT ISSUED BY E DEPARTMENT OF NATURAL R G ANY NECESSARY SIGN-OFF FF	ESOURCES NON-	TIDAL WETLA	ANDS PERMIT COVERING



DEPARTMENT OF PERMITTING, INSPECTIONS AND ENFORCEMENT

SITE/ROAD PERMIT PROCESSING UNIT

PERMIT FOR CONSTRUCTION AND RELATED ACTIVITIES WITHIN THE PUBLIC RIGHT-OF-WAY AND PRIVATE PROPERTY SITE WORK



FEE:

\$2,857.30 PAID: October 28, 2013

STREET SIGN(S) FEE:

\$0.00 PAID:

BOND:

\$102,450.00 PAID: November 01, 2013

41275038

BOND CO: PLATTE RIVER INSURANCE COMPANY

BOND TYPE: S

PERMIT ISSUANCE DATE:

November 05, 2013

PERMIT EXPIRATION DATE:

November 05, 2015


HAITHAM A. HIJAZI, DPIE DIRECTOR

IT SHALL BE THE RESPONSIBILITY OF THE APPLICANT TO APPLY FOR AN EXTENSION IN WRITING NOT LESS THAN THIRTY (30) DAYS PRIOR TO THE EXPIRATION DATE. THE APPLICANT SHALL NOTIFY THE DEPARTMENT AT LEAST 48 HOURS PRIOR TO STARTING CONSTRUCTION OR RESTARTING CONSTRUCTION BY CONTACTING DPIE'S INSPECTIONS DIVISION AT 301-883-3820, SELECT THE PROMPT FOR SITE DEVELOPMENT INSPECTION.



DEPARTMENT OF PERMITTING, INSPECTIONS AND ENFORCEMENT

SITE/ROAD PERMIT PROCESSING UNIT





CASE NAME:	OSBORNE SHOPPING	CENTER		CASE NUMBER:	22113-2013-00
CASE TYPE:	STREET CONSTRUCT	ION PERMIT		DISTRICT:	CENTRAL
Officer Name : Officer Title : Telephone No:	TIFY THAT THE PERMITTEE: PROPERTY DEVELOP: 5918 STONERIDGE M/ PLEASANTON CA 945 KINN, JOE CONSTRUCTION MANAGE (925) 738-1209	MENT CENTERS ALL 88		Owner of Propert	<u>v</u>
Contact Person:	MATTHEWJONES,				
BRIDGE CIP PROJE X COMMUN X COMMUN X CROSSWA Y CURB & G DEVELOP END SECT FEE - IN - I FENCE GATEHOU X GRADING THE PROPOSEE AS APPROVED ACCORDANCE AND STANDAR DEPARTMENT O * ALL STREET I	CIAL ENTRANCE ICATIONS LK UTTER ER CONTRIBUTION ION X LIEU X SE CONSTRUCTION SHALL BE P BY THE DEPARTMENT OF PERI WITH SUBTITLE 23 AND SUBT DOS FOR HIGHWAY AND STREE OF PERMITTING, INSPECTIONS LIGHTING REQUIREMENTS M	GRAVEL HAUL ROAD HEADWALLS INTERNAL STREETS LANDSCAPING MILL OVERLAY MODIFIED PAVING PAVENENT STRIPING PLANTER BOX RESTORATION RETAINING WALLS ERFORMED AND COMPLETED MITTING, INSPECTIONS AND E ITILE 32 OF THE PRINCE GEORM T CONSTRUCTION, AND SUBJI AND ENFORCEMENT OF PRIN IST BE SATISFIED, INCLUDING	X X X X X X X X X X X X X X X X X X X	SIDEWALK SIDEWALK RAMPS SIGN STORM DRAIN STREET LIGHTS* STREET TREES STREET HAME SIGN TEMP ENTRANCE TRAFFIC SIGNALS UNDERDRAIN UTILITY WORK ANE RESTORATION RDANCE WITH THE PI MENT OF PRINCE GEC INTY CODE AND THE HE INSPECTION AND G	X OTHER: R/W SD CMP DESCRIPTION: LANS AND SPECIFICATIONS ORGE'S COUNTY AND IN GENERAL SPECIFICATIONS CONTROL OF THE
-	AND PAYMENT FOR STREET LI				
SEDIMENT CON RELATED SITE/				D BUILDING PERMIT# /ATER PERMIT# :	*
LOCATION O STREET NAM SOUTH OSB					
LOT(S):	BLOCK(S):	PARCEL(S):		DPW&T MAI 5768C5	PPAGE & GRID:
	T USED IN THE ROADWAY SHO PERSONNEL TO ENSURE A ST.		UALIFII	ED GEOTECHNICAL F	REPRESENTATIVE OR
THE APPLICAN ALL THE REQU ENVIRONMENT	PLICANT SHALL BE ADVISED T T FROM OBTAINING A STATE I IRED WORK, OR OBTAINING A FAL RESOURCES THAT NO REG I THE SAID WORK IS ENTITLE!	DEPARTMENT OF NATURAL RE NY NECESSARY SIGN-OFF FRO ULATED WETLANDS ARE PRE	SOURCE: OM THE I SENT OR	S NON-TIDAL WETLA RINCE GEORGE'S CO SIGNIFICANTLY AFFE	NDS PERMIT COVERING UNTY DEPARTMENT OF ECTED BY THE SAID



DEPARTMENT OF PERMITTING, INSPECTIONS AND ENFORCEMENT

SITE/ROAD PERMIT PROCESSING UNIT

PERMIT FOR CONSTRUCTION AND RELATED ACTIVITIES WITHIN THE PUBLIC RIGHT-OF-WAY AND PRIVATE PROPERTY SITE WORK



FEE:

\$12,247.50 PAID: September 19, 2013

STREET SIGN(S) FEE:

\$0.00 PAID:

BOND:

\$146,350.00 PAID: August 29, 2013

BOND #: 070014857

BOND CO:

LIBERTY MUTUAL INSURANCE CO

BOND TYPE: S

PERMIT ISSUANCE DATE:

September 25, 2013

PERMIT EXPIRATION DATE:

September 25, 2015

HAITHAM A. HIJAZI, DPIE DIRECTOR

IT SHALL BE THE RESPONSIBILITY OF THE APPLICANT TO APPLY FOR AN EXTENSION IN WRITING NOT LESS THAN THIRTY (30) DAYS PRIOR TO THE EXPIRATION DATE. THE APPLICANT SHALL NOTIFY THE DEPARTMENT AT LEAST 48 HOURS PRIOR TO STARTING CONSTRUCTION OR RESTARTING CONSTRUCTION BY CONTACTING DPIE'S INSPECTIONS DIVISION AT 301-883-3820. SELECT THE PROMPT FOR SITE DEVELOPMENT INSPECTION.



DEPARTMENT OF PERMITTING, INSPECTIONS AND ENFORCEMENT

SITE/ROAD PERMIT PROCESSING UNIT





CASE NAME:	NORTHERN ESTA	TES SPECIAL STORM DRAIN	CASE NUMBER:	28183-2013-00
CASE TYPE:	SPECIAL DRAIN I	PERMIT	DISTRICT:	NORTH
	Caruso Homes Inc 1655 Crofton Blvd Crofton MD 21114		Owner of Propey Caruso Homes In 1655 Crofton Blv Crofton MD 2111	c d 200
Officer Name : Officer Title : Telephone No:	N/A (301) 261-0277			
Contact Person:	MARK SOMERVILLI	3,		
HAS PERMISSI	ON TO PERFORM WITHIN	THE PUBLIC RIGHT-OF-WAY or/and O	N_SITE:	
COMMUNICROSSW/ CURB & C DEVELOP END SECT FEE - IN- FENCE GATEHOL GRADINC THE PROPOSEI AS APPROVED ACCORDANCE AND STANDAE DEPARTMENT	CIAL ENTRANCE SICATIONS ALK SUTTER FOR CONTRIBUTION FIND FOR CONSTRUCTION SHALL BY THE DEPARTMENT O WITH SUBTITLE 23 AND ROS FOR HIGHWAY AND S OF PERMITTING, INSPEC	GRAVEL HAUL ROAD HEADWALLS INTERNAL STREETS LANDSCAPING MILL OVERLAY MODIFIED PAVING PAVEMENT STRIPING PLANTER BOX RESTORATION RETAINING WALLS BE PERFORMED AND COMPLETED IN FPERMITTING, INSPECTIONS AND EN SUBTITLE 32 OF THE PRINCE GEORGI STREET CONSTRUCTION, AND SUBJECTIONS AND EN SUBTITLE 32 OF THE PRINCE GEORGI STREET CONSTRUCTION, AND SUBJECTIONS AND EN SUBTITLE 32 OF THE PRINCE GEORGI STREET CONSTRUCTION, AND SUBJECTIONS AND EN SUBTITLE 32 OF THE PRINCE GEORGI STREET CONSTRUCTION, AND SUBJECTIONS AND ENFORCEMENT OF PRINCIPLE STREET CONSTRUCTION AND ENFORCEMENT OF PRINCI	FORCEMENT OF PRINCE GE E'S COUNTY CODE AND THE IT TO THE INSPECTION AND E GEORGE'S COUNTY.	X OTHER: SPECIAL DRAIN PERMIT D CMP DESCRIPTION: PLANS AND SPECIFICATIONS ORGE'S COUNTY AND IN GENERAL SPECIFICATIONS CONTROL OF THE
		EET LIGHTING WORK TO THE LOCAL I		
SEDIMENT CO RELATED SITE	NTROL# : 000-00 /ROAD PERMIT# :		ELATED BUILDING PERMIT# ORMWATER PERMIT# :	* 1
LOCATION O	OF PROPOSED WORK			
LOT(S):	BLOCK(S	PARCEL(S):	DPW&T MA	P PAGE & GRID:
		NY SHOULD BE MONITORED BY A QU E A STABILIZED SUBGRADE.	ALIFIED GEOTECHNICAL	REPRESENTATIVE OR
THE APPLICAN ALL THE REQUENVIRONMEN	IT FROM OBTAINING A ST JIRED WORK, OR OBTAIN TAL RESOURCES THAT N	SED THAT THE PERMIT ISSUED BY TH TATE DEPARTMENT OF NATURAL RESC ING ANY NECESSARY SIGN-OFF FROM O REGULATED WE'TLANDS ARE PRESE TITLED TO ANY AUTOMATIC EXEMPTI	DURCES NON-TIDAL WETLA I THE PRINCE GEORGE'S CO ENT OR SIGNIFICANTLY AFF	ANDS PERMIT COVERING DUNTY DEPARTMENT OF JECTED BY THE SAID



DEPARTMENT OF PERMITTING, INSPECTIONS AND ENFORCEMENT

SITE/ROAD PERMIT PROCESSING UNIT





FEE:

\$100.00 PAID:

PAID:

STREET SIGN(S) FEE:

\$0.00

PAID:

BOND:

BOND #:

BOND CO:

BOND TYPE:

PERMIT ISSUANCE DATE:

PERMIT EXPIRATION DATE:

HAITHAM A. HIJAZI, DPIE DIRECTOR

IT SHALL BE THE RESPONSIBILITY OF THE APPLICANT TO APPLY FOR AN EXTENSION IN WRITING NOT LESS THAN THIRTY (30) DAYS PRIOR TO THE EXPIRATION DATE. THE APPLICANT SHALL NOTIFY THE DEPARTMENT AT LEAST 48 HOURS PRIOR TO STARTING CONSTRUCTION OR RESTARTING CONSTRUCTION BY CONTACTING DPIE'S INSPECTIONS DIVISION AT 301-883-3820. SELECT THE PROMPT FOR SITE DEVELOPMENT INSPECTION.

SPECIAL DRAIN PERMIT APPLICATION



Prince George's County

Department of Permitting, Inspections and Enforcement

SITE/ROAD PLAN REVIEW DIVISION

9400 Peppercorn Place
Largo, Maryland 20774
301.636.2060 • FAX: 301.925.8510




SPECIAL DRAIN PERMIT APPLICATION

Date	of Issue:	DPIE Permit No:
Subdivision:		Lot/Block:
Owne	ers Name:	Telephone:
Buildi	ing Address:	
City:	State:	Zip:
Owne	ers/Agents Signature:	
1.	In public space use only cast iron, steel, PVC or held connections but may be used for connection	reinforced concrete pipe. PVC is not acceptable for on to an inlet or manhole.
2.	All construction and future maintenance will be a owner.	at the expense and sole responsibility of the property
3.	For location of underground utilities, call Miss U construction.	tility at 800-257-7777, at least 48 hours prior to starting
4.	Contact Prince George's County Inspection and request information system for inspection at (30	Code Compliance Section automatic inspection 1) 883-5390.
5.		nd Enforcement at (301) 499-8500 at least 24 hours
6. 7.	This permit expires 12 months from date of issu Use SD 50.0 for field connection.	ance.
FEDE	PERMIT DOES NOT RELIEVE THE APPLICANT ERAL, STATE, AND/OR MUNICIPAL PERMIT AUT STRUCTION PURSUANT TO ISSUANCE OF THIS	HORITY HAVING JURISDICTION OVER ANY
Perm	it Charge \$	
	Prince George's County	
1	Draw the property dimensions to scale	

- 1. Draw the property dimensions to scale.
- 2. Show property lines and existing storm drains and easements.
- 3. Show north arrow.
- 4. Show street names and rights-of-way.
- 5. Show proposed storm drain connection invert elevation, pipe size, and type of material.
- 6. Show lot and block numbers on sketch.

FLOODPLAIN REVIEW AND REQUEST FLOW CHART



FLOODPLAIN APPROVAL BLOCK

DEPARTMENT OF PERMITTING, INSPECTIONS AND ENFORCEMENT (DPIE) UTILITY AND TECHNICAL SUPPORT SECTION PRINCE GEORGE'S COUNTY, MARYLAND	
PERMIT NAME: CASE NUMBER: FLOODPLAIN STUDY NUMBER: EXISTING FLOODPLAIN DELINEATION REQUIRED: YES NO PROPOSED FLOODPLAIN DELINEATION REQUIRED: YES NO PAPROVED BY: For Existing Floodplain Delineation Only	

SITE DEVELOPMENT CONCEPT PLAN APPLICATION



Prince George's County

Department of Permitting, Inspections and Enforcement

SITE/ROAD PLAN REVIEW DIVISION

DIVISION9400 Peppercorn Place
Largo, Maryland 20774
301.636.2060 ◆ FAX: 301.925.8510



STANDARD PLAN APPLICATION

_					
Last Name	First Name	MI Phone	E-mail addre	ess	
Present Address (No. & Street)	City/Town	State	Zip	
Project Address (No. & Street)		City/Town	State	Zip	
Tax Map Liber		Folio	Parcel Block		
Builder			Phone		
Lot Size:		square feet.			
Total area of distu	ırbance:	square feet.			
Total Impervious	Area:	square feet.			

The requirements for stormwater management found in Prince George's County Code Subtitle 32and the Code of Maryland Regulations (COMAR) will be satisfied if environmental site design (ESD) practices are used to the maximum extent practicable (MEP) to treat runoff according to Chapter 5 of the **2000** Maryland Stormwater Design Manual (Manual).

Limitations

- 1. The project is a single lot residential construction, not within a developing subdivision, and there is no contiguous land undergoing development by the same owner, builder, or developer;
- 2. Total site impervious cover shall not exceed 15% of the lot size;
- 3. Total land area disturbed during construction shall be less than 30,000 square feet;
- 4. Land area that is disturbed for septic system construction may be subtracted from the total disturbed area provided it is re-vegetated;
- 5. This Standard Plan shall not be used in areas of special concern (e.g., karst geology, sinkhole activity, surface water supply reservoirs, wellhead protection areas, sensitive stream systems, etc.) or if soil or site conditions such as slope, soil type, high groundwater, etc. present a challenge; and
- 6. Documentation must be submitted to show that ESD has been implemented to the MEP before structural practices found in the (Manual) that address these characteristics and specified by the Prince George's County is/are used.

Conditions

Standard Plan Application Issue Date: July 26, 2014

The following conditions for design and construction shall be met and maintained. All stormwater management systems shall be designed by integrating site design, natural hydrology, and smaller controls to capture and treat runoff onsite. The standard for characterizing predevelopment runoff characteristics for new development projects shall be woods in good hydrologic condition. If the following design conditions are met, all stormwater management obligations will be satisfied.

<u>Design</u>

- All ESD practices shall be designed and located to prevent basement seepage, flooding, soil erosion, increases in nonpoint pollution and minimize pollutants in stormwater runoff from both new and redevelopment.
- 2. All rooftop downspouts shall discharge to and drain continuously through at least 75 feet of vegetation (e.g., vegetated channel, swale, or filter strip) in a non-erosive manner to the property line.
- 3. To the extent practical, all other site impervious areas shall drain and discharge continuously through vegetation in a non-erosive manner. The length shall be equal to that of contributing impervious area.
- 4. All access roads and/or driveways constructed for this project shall use open sections in lieu of curb and gutter.
- 5. ESD practices may be used in lieu of providing the required rooftop and other impervious area vegetation lengths.
- 6. Design constraints specific to each ESD practice as specified in the Manual must be addressed.
- 7. The total impervious area draining to any ESD practice shall conform to the design criteria in the Manual.
- 8. The drainage area to each rooftop downspout shall be 500 square feet or less. Drainage areas to individual downspouts greater than 500 square feet shall be treated using rain gardens, rain barrels, or other similar practices as approved by the [MDE/WMA or Prince George's County].

B. The following information must be attached to this application for coverage under the Standard Plan:

- 1. Plat showing the dimensions of property lines and road frontage;
- 2. Location and dimensions of all proposed structures (e.g., house, garage, driveway, well, septic system);
- 3. If present, the location of the Critical Area buffer, nontidal and tidal wetlands, and perennial streams and their associated floodplain;
- 4. Limits of disturbance; and
- 5. The location of all disconnected impervious areas and ESD practices.

Construction

- 1. Prince George's County shall be contacted at least 48 hours prior to the start of construction.
- 2. All stormwater practices and/or runoff controls shall be installed and maintained according to this Standard Plan and the criteria contained in Chapter 5 of the Manual. Subsequent alteration or modification of these practices requires the approval from the Prince George's County.
- 3. Access to the site will be made available at all reasonable times during construction and with reasonable notification after construction for inspection by the [the local approval authority].
- 4. The applicant/homeowners shall promptly repair and/or restore all stormwater practices found in noncompliance by Prince George's County.
- 5. Prince George's County reserves the right to deny approval under this Standard Plan and require that a design be prepared according to County Code Subtitle 32 and the Manual.
- 6. Nothing in this Standard Plan relieves the applicant from complying with any and all federal, State, and local laws and regulations.

Standard Plan Application Issue Date: July 26, 2014

- 7. At a minimum, inspections shall be made by county or municipal staff or by a professional engineer licensed in the State and documented for each ESD planning technique and practice upon completion of final grading, establishment of permanent stabilization, and before issuance of use and occupancy approval.
- 8. Coverage under this Standard Plan shall remain valid for [two] years from the date of approval.

I hereby certify that I have the authority to make application to this Standard Plan; that the information contained herein is correct and accurate; and that all clearing, grading, construction, and development will be conducted according to the above Requirements, Conditions and Project Information.

Signature of Applicant	Date
Printed Name of Applicant	
Approved by	Date

ESD MATRIX

Environmental Site Design Maximum Extent Practicable Determination

		A-1 Green Roof	A-2 Permeable Concrete	A-3 Reinforced Turf (interlocking Structural Units)	N-1 Disconnection of Rooftop Runoff	N-2 Disconnection of Non-Rooftop Runoff	N-3 Sheet flow to Conservation Area
Slope Limitation		None	< 5 %	< 5 %	< 5 % unless terraces or berms	< 5 % unless terraces or berms	< 5 % or with level spreaders
	A	Yes	Yes	Yes	Yes	Yes	Yes
	В	Yes	Yes	Yes	Yes	Yes	Yes
	C	Yes	Yes	Yes	Yes	Yes	Yes
Soils	D	Yes	No 6	No 6	Yes	Yes	Yes
	Marlbo ro	Yes	No	No	Yes	Yes	Yes
	Compac ted Fill	Yes	No 6	No 6	Yes	Yes	Yes
High Gro	undwater	Yes	Yes 2	Yes	Yes	Yes	Yes
Maint.	DPWT	No	No	No	No	No	No
Resp.	Private	Yes	Yes	Yes	Yes	Yes	Yes
Road	R/W	No	No	No	No	Yes	Yes
Resid ential	> 1 ac	Not desirable	Yes 1	Yes 1	Yes	Yes	Yes
	>0.5 ac lot	Not desirable	Yes 1	Yes 1	Yes	Yes	Yes
	<0.5 ac lot	Not desirable	Yes 1	Yes 1	Yes	Yes	Yes
	Multi	Not desirable	Yes 1	Yes 1	Yes	Yes	Yes
Comn	nercial	Yes	Yes	Yes	Yes	Yes	Yes
	nwater spot	Yes	No	No	No 7	No 7	No
Drain age Ar	<500 sf	Yes	Yes	Yes	Yes	Yes	Yes
e a	<1,00 0 sf	Yes	Yes	Yes	No	Yes	Yes
	<10,0 00 sf	Yes	Yes	Yes	No	No	Yes
	Other		Yes 3				
No	otes		Permeable asphalt not permitted.				Conservation area min 20,000 sf., min. width 50 ft.

1 Acceptable for pedestrian walkways, parking lots, driveways, plazas and access roads. 2 Facility sub-base must be a minimum 4' above high water table. 3 Facilities shall be designed as infiltration practices, as outlined in Appendix D.13 in the MD Design Manual. 4 Special design required. Standard rain barrel not acceptable. 5 Not acceptable on soils that have low shear strength, or identified as "slough prone" or "landslide prone." 6 If designed per County detail, then Yes. 7 If discharge is beyond hotspot use, the Yes. 8 Pretreatment and soil testing to verify infiltration rates are required for drainage areas larger than 10,000 sf. Footnotes:

		M-1 Rainwater Harvesting (Rain Barrell)	M-2 Submerged Gravel Wetlands	M-3 Landscape Infiltration	M-4 Infiltration Berms	M-5 Dry Wells
Slope Li	imitations	None	<2%	sheet flow or level spreader	up to 10 %	up to 20 %
	Α	Yes	If lined	Yes	Yes ⁵	Yes
	В	Yes	If lined	Yes	Yes ⁵	Yes
S o	С	Yes	Yes	No	Yes ⁵	No
1	D	Yes	Yes	No	Yes ⁵	No
S	Marlboro	No	If lined	No	No	No
l	Compacted Fill	Yes	No	No	No	No
High Gro	oundwater	Yes	Yes	Yes ²	Yes	Yes ²
Maint.	DPWT	No	No	No	No	No
Resp.	Private	Yes	Yes	Yes	Yes	Yes
Roa	d R/W	No	No	No	No	No
R	> 1 ac lot	Yes	Common areas only	Common areas only	Common areas only	Yes
e s i	>0.5 ac lot	Yes	Common areas only	Common areas only	Common areas only	Yes
d a	<0.5 ac lot	Yes	Common areas only	Common areas only	Common areas only	Yes
e n	Multi	Yes	Common areas only	Common areas only	Common areas only	Yes
Com	mercial	Yes	Yes	Yes	Yes	Yes ³
Stormwater Hotspot		Rooftop runoff only	Yes with Liner	No	No	No
D r	<500 sf	Yes	No	Yes	Yes	Yes
a A i r	<1,000 sf	Yes ⁴	No	Yes	Must sheet flow into berm	Yes
n e a a	<10,000 sf	Yes ⁴	No	Yes	Must sheet flow into berm	Yes ³
g e	Other		1 Ac Minimum	Yes ⁸		Yes ³
N-	otes				Used to augment other devices, or for pretreatment	Setback 100' from 15% fill slopes, 200' from 25% fill slopes

Footnotes:

- 1 Acceptable for pedestrian walkways, parking lots, driveways, plazas and access roads.
- 2 Facility subbase must be a minimum 4' above high water table.
- 3 Facilities shall be designed as infiltration practices, as outlined in Appendix D.13 in the MD Design Manual.
- 4 Special design required. Standard rain barrel not acceptable.
- 5 Not acceptable on soils that have low shear strength, or identified as "slough prone" or "landslide prone."
- 6 If designed per County detail, then Yes.
- 7 If discharge is beyond hotspot use, the Yes.
- 8 Pretreatment and soil testing to verify infiltration rates are required for drainage areas larger than 10,000 sf.

		M-6 Micro- Bioretention	M-7 Rain Gardens	M-8 Grass Swales	M-8 Bio Swales	M-8 Wet Swales
Slope L	imitations	< 5 % or with level spreaders	< 5 % unless terraces or berms	1 % min, 4 % max	1 % min, 4 % max	1 % min, 4 % max
	Α	Yes	Yes	Yes	Yes	No
	В	Yes	Yes	Yes	Yes	No
S o	С	Yes, with underdrain	Yes	Yes	Yes, with underdrain	Yes
i I	D	Yes, with underdrain	No	Yes	Yes, with underdrain	Yes
S	Marlboro	Yes, with underdrain	No	Yes, if flow is < 3 cfs	Yes, with underdrain	No
	Compacted Fill	Yes, with underdrain	No	Yes	Yes, with underdrain	No
High Gro	oundwater	Yes, above	Yes, 2' above	Yes	Yes, with underdrain	Yes
Maint.	DPWT	No	No	Yes	No	No
Resp.	Private	Yes	Yes	Yes	Yes	Yes
Roa	d R/W	No	No	Rural - open section only	No	No
R	> 1 ac lot	Common areas only	Common areas only	Yes	Common areas only	Common areas only
e s i	>0.5 ac lot	Common areas only	Common areas only	Yes	Common areas only	Common areas only
d a	<0.5 ac lot	Common areas only	Common areas only	No	Common areas only	Common areas only
e n	Multi	Common areas only	Common areas only	No	Common areas only	Common areas only
Com	mercial	Yes	Yes	Yes	Yes	Yes
Stormwa	ter Hotspot	No	No	No	No	No
D r	<500 sf	Yes	Yes	Yes	Yes	Yes
a A i r	<1,000 sf	Yes	Yes	Yes	Yes	Yes
n e a a	<10,000 sf	Yes	Commercial max 10,000 sf	Yes	Yes	Yes
g e	Other	Max 0.5 ac	Residential max 2,000 sf			
N	otes	4' above groundwater if inflitrating.				

Footnotes:

- 1 Acceptable for pedestrian walkways, parking lots, driveways, plazas and access roads.
- $2\,$ Facility subbase must be a minimum $4^{\rm l}$ above high water table.
- 3 Facilities shall be designed as infiltration practices, as outlined in Appendix D.13 in the MD Design Manual.
- 4 Special design required. Standard rain barrel not acceptable.
- 5 Not acceptable on soils that have low shear strength, or identified as "slough prone" or "landslide prone."
- 6 If designed per County detail, then Yes.
- $7\,$ If discharge is beyond hotspot use, the Yes.
- $8 \ \ Pretreatment\ and\ soil\ testing\ to\ verify\ infiltration\ rates\ are\ required\ for\ drainage\ areas\ larger\ than\ 10,000\ sf.$

BMP SUMMARY TABLE

	是我是我的人的国家工作。	The same of the same of	1																				
Application of the control	Ashion whichold it then taking beauting	electric bases and													13.24年	悪							
kaledkjentes	kakalapai kappain fopulai, ilomoka ja kind Saperia ja	sonski je krijal	Shippi	183	h							Н	H										
									63	3		-											
DINE ON BUILD	1 N N 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	10	in a m	NO IS	CIP SEE	3			88	OH()	DE DEC	Н	EEE 1833	3 12	田山	DATA LIBIE		细胞		0 AIS	H 40		
					I STATE BUILD DI LANTE	na .		CA LANGE	CEC	88	B	無	150	Silver Cort	21.0 21.0 21.0	1666 1867 1867	1	tto	ь		N N		
	新館								520		1 15	553	=	ï		traceres)	Seat read	-	1 11	_			
图画	Dill Dille	-18		100 EM	图 图	出	1=1	133						28		E E		+		rwi	200	=======================================	
														J			\dashv	\dashv		\dashv			
					H																		
																		+		+			+
BUE	Urbajet telf mennetale	Metale		888																			
	Cétin Esmelapentági ka	HEI BE		귴	a british b																		
SUE!	Elite Pilot			102																			
部語	Secretary of the second			Set																			
	pockaji žipastadija serbdij	tarifferent	7500	24																			
A13546	Glasts Wohnlich	45			.ao	-	:107										\exists	\dashv		\dashv			\dashv
	Bibaze et futoria	785		-11	jij	-	di																
				Elit	1896		100																

SAMPLE STREAM INVENTORY CHECKLIST



Prince George's County

Department of Permitting, Inspections and Enforcement

SITE/ROAD PLAN REVIEW DIVISION

DPIE

DEPARTMENT OF PERMITTING, INSPECTIONS AND ENFORCEMENT

9400 Peppercorn Place Largo, Maryland 20774 301.636.2060 ◆ FAX: 301.925.8510

SAMPLE STREAM INVENTORY CHECKLIST

STREAM SURVEY FOR DESIGN OF BIO-SENSITIVE STREAM CROSSINGS

Project Name:				Site Inspe	ector:		
Project Number:				Site Inspe	ector:		
Visit Date:		DPIE Rev	iewer:				
Crossing # or Station:							
Stream Order							
STATE USE CLASS							
USE I & I-P							
USE III &III-P							-
USE IV & IV-P							
Specially Designated							
STREAM QUALITY							
Biotic Community Quality							
(As determined by DPIE Staff or Equivalent 1							
STREAM FLOW TYPE							
Ephemeral Ephemeral							
Intermittent							
Perennial (Constant Flow)							
NORMAL (BASEFLOW) CHARACTERIST							
< 3 Months > 3 Months							
WATERSHED CHARACTERISTICS							
Fully Developed							
Partially Developed (Including Agriculture)							
Undeveloped							
FUTURE OR PROPOSED DEVELOPMENT							
< 8% Impervious							
> 8% Impervious							
STREAM BED CHARACTERISTICS							
Bed Materials							
Cobble, Gravel, Sand , Silts							
Solid Rock, Hard Clay, etc.							
Gradient							
Shallow (<0.5%)							
Moderate ((0.5% to 2%)							
Steep (>2%)							
Platform							
Meandeering (Sinuosity <1.5%)							
Sinuous (Sinuosity 1.2% to 1.5%)							
Straight (Sinuosity >1.2%)							
Valley Confinement							
High (Steep Valley Walls, Relatively Narrow FP)							
Moderate (Slight to moderate sloped walls; re	elatively wide	FP)					
Low (No definable valley walls, Broad FP)							
SITE CONSIDERATIONS							
Wetland Impact (Y or N)							
Forested							
Scrubs/shrub	-					-	
Emergent							
Specimen Trees Present (Y or N)			İ				
Species	Size	Species	İ	Size	Species		Size
			İ		-		
			İ				

SAMPLE NOTIFICATION LETTER

	[Date]
[Recipient]	
Dear:	
Re:	[Site Development Concept Plan Number and Name of Project]

A Site Development Concept Plan application for the above-referenced project was filed on [Date] (The date that a Site Development Concept number is issued by DPIE) for review to the Department of Permitting, Inspections and Enforcement ("DPIE").

The subject property consists of approximately [___] acres with an address of [address, if applicable], which is located [Give nearest point of reference by road frontage or distance from nearest intersection]. The nature of the review includes a conceptual stormwater management plan for proposed development of the subject property as [give general description of development for example residential, commercial, mixed use]

If you wish to obtain more information about the proposed Site Development Concept Plan you should contact (Design Consultant) at (Consultants Phone number), visit the Department of Permitting, Inspections and Enforcement noted here where the plan and application may be reviewed, or you may contact the applicant's engineer of record at [provide engineer's contact info].

IMPORTANT: This notice is your opportunity to interact with the applicant. Contacting the applicant as soon as possible after receiving this notice will help facilitate your ability to receive information and/or establish a time when the applicant may meet with you or your civic group to provide information and answer questions about the development proposed.

Sincerely,

SAMPLE AFFIDAVIT

<u>AFFIDAVIT</u>

Mailing letters regarding the application for Site Development Concept Plan approval [Plan
No.]; [Project Name], were mailed to all adjoining property owners, registered associations,
municipalities within a mile, and previous parties of record on [Date].
I, (), solemnly affirm under the penalties of perjury and upon personal
knowledge that the contents of the foregoing paper are true.
Name
Ivanie
Date
STATE OF MARYLAND
COUNTY OF PRINCE GEORGE'S, ss:
I HEREBY CERTIFY that on this day of, 20, before me, the
subscriber, a Notary Public, for the State and County aforesaid, personally appeared (
), being authorized to execute this Affidavit in accordance with the requirements of the
Prince George's County Zoning Ordinance for the purposes therein contained.
IN WITNESS WHEREOF, I hereunto set my hand and official seal.
IN WITNESS WHEREOF, I hereunto set my hand and official seal.
Notary Public
Notary Public
IN WITNESS WHEREOF, I hereunto set my hand and official seal. Notary Public My Commission Expires:

SAMPLE APPROVAL LETTER & BLOCK

- 1. Approval Letter
- 2. Approval Block

DPIE STAMP THREE

Prince George's County Maryland
Department of Permitting, Inspections and Enforcement
APPROVED PLAN SET

The Department of Permitting, Inspections and Enforcement has completed a review of this document for code compliance. As required by State Code, the design professional(s) responsible for the preparation and content of this document must provide a record copy of these documents with their original seal, signature and date.

Case Name

Case Number (Plan Approval #):

Case Type:

Issuance Date:

Address:

Lot(s) and Block(s):



THE PRINCE GEORGE'S COUNTY GOVERNMENT



Department of Permitting, Inspections and Enforcement

Site/Road Plan Review Division

9400 Peppercorn Place, Suite 420 Largo, Maryland 20774 (301) 883-5710



STORMWATER MANAGEMENT CONCEPT APPROVAL

PG.CO.BOE_SUITLAND HIGH SCHOOL AND ANNEX

CASE #:

10906-2014-00

APPLICANT'S NAME:

PG.CO. BOARD OF EDUCATION

ENGINEER:

LANDESIGN

REQUIREMENTS:

Technical Review is required for PUBLIC/PRIVATE Storm Drain/SWM Construction.

Type of Storm Drainage/SWM Construction is PRIVATE.

These additional approvals are required: None.

These fees apply: None.

These bonds apply: None.

Required water quality controls: MICRO-BIORETENTION.

Required water quantity controls: None.

A maintenance agreement is required.

No special conditions apply.

Required easements: None.

Storm Water Management fee payment of none in lieu of providing on-site attenuation/quality control measures. (Fee-In-Lieu subject to change during technical review.)

CONDITIONS OF APPROVAL:

Please see second page.

APPROVED BY:

Rey De Guzman

APPROVAL DATE: EXPIRATION DATE:

May 12, 2014

May 12, 2017

ADC MAP:

5650 D-4

200' SHEET:

204SE05

STREET NAME:

SILVER HILL RD

FOR OFFICE USE ONLY

WATERSHED:

40-Oxon Run

NUMBER OF DU'S:

0

COST PER DWELLING:

0

CC: APPLICANT, SCD, PERMITS P.G.C. FORM #3693 (REV 04/93)

THE PRINCE GEORGE'S COUNTY GOVERNMENT



Department of Permitting, Inspections and Enforcement

Site/Road Plan Review Division

9400 Peppercorn Place, Suite 420 Largo, Maryland 20774 (301) 883-5710



STORMWATER MANAGEMENT CONCEPT APPROVAL

CASE NAME:

PG.CO.BOE SUITLAND HIGH SCHOOL AND ANNEX

CASE #:

10906-2014-00

CONDITIONS OF APPROVAL:

- 1. THIS PROJECT INVOLVES REDEVELOPMENT OF AN EXISTING DEVELOPED SITE. SITE SHALL BE DESIGNED TO TREAT FOR 50% WQv OF THE IMPERVIOUS AREA WITHIN THE PROPOSED DISTURBED AREA AND 100% WQv AND CPV FOR NEW IMPERVIOUS AREA USING ESD PRACTICES AND TECHNIQUES.
- 2. THE PROPOSED DEVELOPMENT IS FOR THE REMOVAL AND REPLACEMENT OF THE EXISTING 8 INCH

WATERLINE. NO ADDITIONAL IMPERVIOUS COVER IS PROPOSED WITH THE REPLACEMENT.
3. ESD TO THE MEP IS PROVIDED IN MICRO-BIO RETENTION. 4. SITE DEVELOPMENT FINE GRADING PERMIT FROM DPIE FOR THE PROPOSED IMPROVEMENTS WILL BE
REQUIRED. 5. A LETTER OF RESPONSIBILITY BY THE BOARD OF EDUCATION SHOULD BE FURNISHED AT THE TIME OF THE
PERMIT ISSUANCE.
REVIEWED BY MS.

SAMPLE APPROVAL MEMO

THE PRINCE GEORGE'S COUNTY GOVERNMENT

Department of Permitting, Inspections and Enforcement IJI 11

Site/Road Plan Review Division **SAMPLE**DPIE Referral

MEMORANDUM

2014

TO: Meika Fields, Urban Design Section

Development Review Division, M-NCPPC

FROM: Mary C. Giles, P.E. Associate Director

Site/Road Plan Review Division, DPIE

RE: (Site Name)

Detailed Site Plan No. DSP-

In response to the Detailed Site Plan No. DSP-referral, the Department of Permitting, Inspections and Enforcement (DPIE) offer the following:

The property is located on the east side of

Avenue, west of Street.

Avenue and Street are State of Maryland

maintained roadways; therefore, coordination with the Maryland State Highway Administration (SHA) is required.

Street and Street are Town

of Brentwood maintained roadways; therefore, coordination with the Town of Brentwood is required.

A soils investigation report which includes subsurface exploration and geotechnical engineering evaluation for the proposed buildings and ESD is required.

All storm drainage systems and facilities are to be in accordance with DPW&T's Specifications and Standards.

The proposed Detailed Site Plan is consistent with the approved stormwater management Concept Plan No. .

The stormwater management pond east of the intersection of

Avenue and Street is a SHA

facility. Modification of this stormwater management pond to add an ESD device must be coordinated with SHA, or modification of project to incorporate ESD onsite.

9400 Peppercorn Place, 4[^] Floor, Largo, Maryland 20774 Phone: 301.636.2060 • http://dpie.mypgc.us • FAX: 301.636.2069

Meika Fields , 2014 Page 2

- This memorandum incorporates the Site Development Plan Review pertaining to Stormwater Management (County Code 32-182(b)). The following comments are provided pertaining to this approval phase:
 - a) Final site layout, exact impervious area locations are shown on plans.
 - b) Exact acreage of impervious areas has not been provided.
 - c) Proposed grading is shown on plans.
 - d) Delineated drainage areas at all points of discharge from the site have been provided.
 - e) Stormwater volume computations have not been provided. Provide BMP summary table to define ESD target volumes and ESD provided volumes for entire LOD.
 - f) Erosion/sediment control plans that contain the construction sequence, and any phasing necessary to limit earth disturbances and impacts to natural resources, and an overlay plan showing the types and locations of ESD devices and erosion and sediment control practices are not included in the submittal.
 - g) A narrative in accordance with the code has not been provided. Please submit any additional information described above for further review.

If you have any questions or need additional information, please contact Mr. Steve Snyder, District Engineer for the area, at 301.636.2060.

MCG:SS:dab

(Engineer, address)

PLAN APPROVAL BLOCKS

Stamp 1 Signature Set

Stamp 2 Approved Permit Set

Stamp 3 Approved Plan Set

Stamp 4 Approved Not Permitted Set

Stamp 5 Approved Permit SD-SWM Only

Stamp 6 Approved As-Built Set

PGSCD Small Pond Approval

DPIE STAMP ONE

Prince George's County Maryland Department of Permitting, Inspections and Enforcement SIGNATURE READY SET

The Department of Permitting, Inspections and Enforcement has completed a review of this document for code compliance. As required by State Code, the design professional(s) responsible for the preparation and content of this document must provide a record copy of these documents with their original seal, signature and date.

THIS DOCUMENT MAY NOT BE MODIFIED IN ANY WAY, OTHER THAN TO AFFIX A SEAL, SIGNATURE AND DATE IN THE SPACE PROVIDED.

The signed "Signature Ready Set" will give the electronic document from which it was created the same force and impact as if the electronic document were signed and sealed.

Case Name:

Case Number (Permit or Approval #):

Case Type:

Signature Ready Date:

Address:

Lot(s) and Block(s):

By signing this set, I am confirming that the "Signature Ready Set" has not been modified in any way that would make it different from the electronic document from which it was created.



DPIE STAMP TWO

STAMP TWO

Prince George's County Maryland
Department of Permitting, Inspections and Enforcement
APPROVED PERMIT SET

The Department of Permitting, Inspections and Enforcement has completed a review of this document for code compliance. As required by State Code, the design professional(s) responsible for the preparation and content of this document must provide a record copy of these documents with their original seal, signature and date.

Case Name:

Case Number (Permit #):

Case Type:

Issuance Date:

Address:

Lot(s) and Block(s) and Parcel(s):



DPIE STAMP THREE

Prince George's County Maryland Department of Permitting, Inspections and Enforcement APPROVED PLAN SET

The Department of Permitting, Inspections and Enforcement has completed a review of this document for code compliance. As required by State Code, the design professional(s) responsible for the preparation and content of this document must provide a record copy of these documents with their original seal, signature and date.

Case Name:

Case Number (Plan Approval #):

Case Type:

Issuance Date:

Address:

Lot(s) and Block(s):



STAMP FOUR

Prince George's County Maryland Department of Permitting, Inspections and Enforcement APPROVED NOT PERMITTED SET (CONDITIONAL APPROVAL)

The Department of Permitting, Inspections and Enforcement has completed a review of this document for code compliance. As required by State Code, the design professional(s) responsible for the preparation and content of this document must provide a record copy of these documents with their original seal, signature and date.

Case Name:

Case Number (Permit #):

Case Type:

Issuance Date:

Address:

Lot(s) and Block(s):



Conditions of Approval

The above approval is conditioned upon the following:

- This DOES NOT REPRESENT A PERMIT TO CONSTRUCT.
- This represents complete plan approval by DPIE for roadway and drainage systems included in the plan (storm drain, stormwater management, paving, sidewalk, curb/gutter, pavement marking, signage, signals and other roadway appurtenances, grading).
- Additional outstanding permit requirements, including payment of fees and posting of bonds must be satisfied prior to final permit issuance.
- If a permit for this work is not secured within 6 months of this approval, this approval expires and all previously paid permit fees are forfeited. In this instance, the permittee shall file for permit extension and pay the required filing fees.

STAMP FIVE

Prince George's County Maryland Department of Permitting, Inspections and Enforcement APPROVED PLAN SET SD-SWM ONLY

The Department of Permitting, Inspections and Enforcement has completed a review of this document for code compliance. As required by State Code, the design professional(s) responsible for the preparation and content of this document must provide a record copy of these documents with their original seal, signature and date.

Case Name:

Case Number (Plan Approval #):

Case Type:

Issuance Date:

Address:

Lot(s) and Block(s):



Conditions of Approval

The above approval is conditioned upon the following:

- This approval includes plan approval by DPIE for storm drain and stormwater management systems ONLY.
- Roadway systems (paving, sidewalk, curb/gutter, pavement marking, signage, signals and other roadway appurtenances), grading and permitting require further review.
- This approval does NOT represent a permit to construct.

STAMP SIX

Prince George's County Maryland Department of Permitting, Inspections and Enforcement APPROVED AS BUILT PLAN SET

The Department of Permitting, Inspections and Enforcement has completed a review of this document for code compliance. As required by State Code, the design professional(s) responsible for the preparation and content of this document must provide a record copy of these documents with their original seal, signature and date.

Case Name:

Case Number (Permit Approval #):

Case Type:

Issuance Date:

Address:

Lot(s) and Block(s):



DELEGATED PROFESSIONAL ENGINEER CERTIFICATION

	I D		ON DISTRICT APPROVAL
()	Certifies Water C Structure Exemp MD-378 Approv	t From
		Signature	Date
()	Certifies Pond M MD-378 & Reco PGSCD Approv	ommend al
		Signature	Date
()	Certifies Pond MD-378 & For Final PGSCD Approval	rward For
		Signature	Date
()	As Built Meet Requirements	
		Signature	Date

GENERAL STORM DRAIN and PLAN GENERAL NOTES

- 1. General Storm Drain and Paving Notes
- 2. Paving Notes

GENERAL STORM DRAIN AND PAVING NOTES

- 1) INFORMATION CONCERNING UNDERGROUND UTILITIES WAS OBTAINED FROM AVAILABLE RECORDS, BUT THE CONTRACTOR MUST DETERMINE THE EXACT LOCATION AND ELEVATION OF THE MAINS BY DIGGING TEST PITS, BY HAND OR VACUUM, AT UTILITY CROSSINGS WELL IN ADVANCE OF TRENCHING. IF CLEARANCES TO WATER AND SEWER LINES ARE LESS THAN SHOWN ON THIS PLAN, OR LESS THAN TWELVE (12) INCHES, CONTACT THE DEPARTMENT OF PERMITTING INSPECTION AND ENFORCEMENT (DPIE) INSPECTOR BEFORE PROCEEDING WITH CONSTRUCTION.
- 2) ALL STORM DRAINS SHALL BE CONSTRUCTED IN ACCORDANCE WITH THE LATEST EDITION OF THE STORMWATER MANAGEMENT STANDARDS AND SPECIFICATIONS OF PRINCE GEORGE'S COUNTY DEPARTMENT OF PUBLIC WORKS AND TRANSPORTATION.
- 3) FOR TYPES OF STORM DRAIN STRUCTURES, REFER TO THE LATEST STANDARD DETAILS OF PRINCE GEORGE'S COUNTY DEPARTMENT OF PUBLIC WORKS AND TRANSPORTATION, UNLESS OTHERWISE NOTED.
- 4) ALL ROADWAY CONSTRUCTION SHALL BE PERFORMED IN ACCORDANCE WITH THE FOLLOWING: THE DPW&T SPECIFICATIONS AND STANDARDS FOR ROADWAYS AND BRIDGES; THE PRINCE GEORGE'S COUNTY CODE, SUBTITLE 23, ROAD ORDINANCE; AND THE PRINCE GEORGE'S COUNTY POLICY AND SPECIFICATION FOR UTILITY INSTALLATION AND MAINTENANCE.
- 5) PRIOR TO DIGGING WITHIN THE PUBLIC RIGHT-OF-WAY, CALL "MISS UTILITY" TOLL FREE AT (800) 257-7777 FOR UTILITY LOCATION AT LEAST 48 HOURS BEFORE BEGINNING CONSTRUCTION.
- 6) PRIOR TO PERMIT ISSUANCE AND STARTING ANY WORK SHOWN ON THIS PLAN, THE PERMITTEE SHALL ARRANGE A PRE-CONSTRUCTION MEETING WITH THE DPIE INSPECTOR BY CALLING (301) 883-5730. AN INITIAL INSPECTION IS REQUIRED PRIOR TO FULL MASS GRADING OF THE SITE.
- 7) IN ACCORDANCE WITH SECTION 23-128, THE COUNTY'S ROAD ORDINANCE, A PROJECT SIGN SHALL BE POSTED PROMINENTLY DESCRIBING THE FOLLOWING:
- SUBDIVISION NAME (AS SHOWN ON PERMIT APPLICATION)
- OWNER/PERMITTEE NAME
- OWNER/PERMITTEE ADDRESS AND PHONE
- DPW&T PERMIT NUMBER
- 8) ALL ELEVATIONS SHOWN ON THIS PLAN ARE IN ACCORDANCE WITH THE FOLLOWING: HORIZONTAL—MARYLAND COORDINATE SYSTEM (STATE PLANE GRID) BASED ON NORTH AMERICAN DATUM OF 1983 (NAD 83); NATIONAL GEODOTIC VERTICAL DATUM OF 1929 (NG VD 29).
- 9) TEMPORARY TRAFFIC CONTROL AND PERMANENT TRAFFIC SIGNS SHALL CONFORM TO THE LATEST EDITION OF THE FEDERAL HIGHWAY ADMINISTRATION'S MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES (MUTCD).
- 10) IT SHALL BE THE RESPONSIBILITY OF THE PERMITTEE TO ARRANGE FOR THE ADJUSTMENT OR RELOCATION OF ALL UTILITIES.

- 11) ALL UNSUITABLE MATERIAL MUST BE REMOVED AND REPLACED WITH SUITABLE MATERIAL TO A DEPTH AS DIRECTED BY THE GEOTECHNICAL ENGINEER, THE DPW&T INSPECTOR, AND/OR THE DEPARTMENT'S ENGINEER.
- 12) EXCAVATION AND PLACEMENT OF FILL MATERIAL SHALL BE PERFORMED UNDER THE SUPERVISION OF A MARYLAND-LICENSED ENGINEER.
- 13) THE PERMITTEE WILL BE REQUIRED TO FURNISH COMPACTION REPORTS CERTIFIED BY A MARYLAND-LICENSED ENGINEER ON EACH LAYER OF FILL MATERIAL PRIOR TO PLACING SUBSEQUENT LAYERS.
- DURING THE PLACEMENT OF A STANDARD PAVEMENT SECTION, NO PAVEMENT COURSE OR STONE LIFT SHALL BE PLACED UNTIL THE UNDERLYING COURSE OR SUBGRADE IS APPROVED BY THE DPW&T INSPECTOR. THE APPROVAL SHALL EXPIRE IF TRAFFIC OR INCLEMENT WEATHER AFFECTS THE SITE PRIOR TO PAVING.
- AS SOON AS THE ASPHALT BASE COURSE IS APPROVED, THE INTERMEDIATE ASPHALT COURSE SHALL BE PLACED IMMEDIATELY OVER IT TO FORM A PROTECTIVE SEAL.
- 16) TEMPORARY STREET NAME SIGN INSTALLATION AND MAINTENANCE IS THE OBLIGATION OF THE PERMITTEE ONCE BASE PAVING IS COMPLETED.
- 17) WHERE ROADWAY CONSTRUCTION IS ON OR IN THE VICINITY OF AN EXISTING ROAD, IN-KIND PAVEMENT MARKING AND STRIPING REPLACEMENT (E.G., THERMOPLASTIC, PAINTED, ETC.) ARE REQUIRED. ALSO, APPROPRIATE PAVEMENT MARKING AND STRIPING SHALL BE PROVIDED IN THE AREA OF PAVEMENT WIDENING AND/OR RECONSTRUCTION AND/OR OVERLAY OF AN EXISTING ROAD.
- 18) SAW CUT AND MILL A 2-INCH DEEP, 10-FOOT-WIDE NOTCH AT EXISTING EDGE OF PAVEMENT WHERE IT IS NECESSARY TO CONNECT TO OR TO EXTEND AN EXISTING ROAD. OVERLAY AT POINT OF TIE-IN TO ENSURE A SMOOTH TRANSITION AND POSITIVE DRAINAGE.
- 19) WHERE IT IS NECESSARY TO WIDEN AN EXISTING ROAD, AND MILLING AND OVERLAY REQUIREMENTS HAVE BEEN WAIVED OR REDUCED, THE WIDENING AND THE EDGE TREATMENT OF EXISTING ROAD SHALL BE CONSTRUCTED IN ACCORDANCE WITH DPW&T STANDARD NO. 300.20 UNLESS OTHERWISE DIRECTED BY THE DEPARTMENT.
- 20) ALL RESIDENTIAL ROADWAY FILLET RADII SHALL BE AT LEAST 37 FEET, UNLESS OTHERWISE NOTED. ROADWAYS WITH HIGHER CLASSIFICATION REQUIRE 45 FEET AND/OR 50 FEET RADII.
- 21) AN UNDERDRAIN SYSTEM IS REQUIRED FOR THE FULL LENGTH OF ALL PROPOSED AND MODIFIED ROADWAYS, ON BOTH SIDES, AND TO THE LIMITS OF THE PERMIT SHOWN ON THIS PLAN.
- 22) ALL CURB AND GUTTER SHALL BE CONSTRUCTED IN ACCORDANCE WITH DPW&T STANDARDS NO. 300.01 THROUGH 300.04 UNLESS OTHERWISE DIRECTED BY THE DEPARTMENT.
- 23) BRICK CHANNELIZATION IS REQUIRED IN ALL PUBLIC DPW&T STORM DRAIN STRUCTURES. CONCRETE CHANNELIZATION IS NOT ALLOWED.

- 24) POSITIVE DRAINAGE SHALL BE MAINTAINED THROUGHOUT THE AREA COVERED BY THIS PERMIT AND THROUGH ADJACENT PROPERTY FRONTAGES.
- 25) ALL UNPAVED AREAS WITHIN THE RIGHT-OF-WAY SHALL BE SODDED.
- 26) ALL SIDEWALK RAMPS SHOWN ON THIS PLAN SHALL BE CONSTRUCTED IN ACCORDANCE WITH DPW&T STANDARDS 300.05 THROUGH 300.10 AND SHALL COMPLY WITH THE LATEST REVISION TO THE FEDERAL ACCESSIBILITY GUIDELINES OF THE AMERICANS WITH DISABILITIES ACT.
- 27) ALL SIDEWALKS SHOWN ON THIS PLAN SHALL BE CONSTRUCTED IN ACCORDANCE WITH THE LATEST DPW&T STANDARDS AND SHALL COMPLY WITH THE LATEST REVISION TO THE FEDERAL ACCESSIBILITY GUIDELINES OF AMERICANS WITH DISABILITIES ACT.
- 28) ALL SIDEWALKS (EXCEPT AS NOTED HEREIN) ARE TO BE CONSTRUCTED BY THE SITE DEVELOPER.
- 29) SIDEWALKS ALONG FRONTAGES OF OPEN-SPACE PARCELS AND THOSE NOT COVERED BY A SINGLE-FAMILY BUILDING PERMIT SHALL BE CONSTRUCTED UNDER THIS STREET CONSTRUCTION PERMIT.
- 30) THE WIDTH OF A RESIDENTIAL DRIVEWAY APRON AT THE PROPERTY LINE SHALL NOT BE LESS THAN THE WIDTH OF THE ON-SITE PARKING PAD AT ITS WIDEST POINT, A MAXIMUM WIDTH OF 20 FEET, AND A MINIMUM WIDTH OF 10 FEET. A RESIDENTIAL DRIVEWAY APRON FLARE SHALL NOT BE CONSTRUCTED CLOSER THAN 3.5 FEET TO THE NEAREST ABUTTING PROPERTY LINE.
- 31) ALL DRIVEWAY APRONS ARE TO BE CONSTRUCTED BY THE SITE DEVELOPER.
- 32) ENSURE THAT STREET TREES ARE NO CLOSER THAN 1 FOOT TO THE RIGHT-OF-WAY LINE, IN AN OPEN SPACE SECTION CONFIGURATION, AND NO CLOSER THAN 15 FEET FROM STREET LIGHT OR POLE, AND OF APPROPRIATE HEIGHT SO AS NOT TO INTERFERE WITH EXISTING OR PROPOSED OVERHEAD UTILITY LINES. ALL STREETSCAPE PLANTING SHALL BE IN ACCORDANCE WITH DPW&T STANDARDS 600.01 THROUGH 600.20 UNLESS DIRECTED OTHERWISE BY THE DEPARTMENT.
- 33) PAVEMENT QUALITY CONTROL AND CORING WILL BE REQUIRED OF THE PERMITTEE FOR ALL PAVEMENT COURSES USING THE FOLLOWING PROCESS:
 - a. PRIOR TO PAVING, PERMITEE/PAVING CONTRACTOR SHALL ELECTRONICALLY NOTIFY INSPECTOR OF PAVING DATES (FAX CAN OCCASIONALLY BE ACCEPTED), AND PROVIDE INFORMATION NEEDED FOR CORE TESTING REQUEST (CTR FORM #1). DPW&T INSPECTOR FILLS OUT THE CTR FORM THEN SENDS IT TO THE MATERIALS LAB.
 - b. CONTRACTORS, WHO ARE NEW TO THE MATERIALS LAB, SHALL ELECTRONICALLY SUBMIT QC PLANS TO IT, AND ARRANGE TO BE INITIATED BY IT PRIOR TO PAVING.
 - c. THE PERMITEE/PAVING CONTRACTOR MUST PROVIDE A MD-CERTIFIED FIELD TECHNICIAN FOR DAILY QUALITY CONTROL (QC) TESTING DURING THE ENTIRE

PAVING OPERATION (NOT JUST ITS END). FIELD TECHNICIAN SHALL BE ADEQUATELY EQUIPPED WITH A PHONE, CALIBRATED THERMOMETER, AND A CALIBRATED THIN-LIFT DENSITY GAUGE FOR QC AND INSPECTOR-REQUESTED TESTING.

- d. HMA DENSITY GAUGES SHALL BE VALIDATED AND CALIBRATED DAILY (SHA 504.03.10. A.2), SO THEIR READINGS CAN BE ACCEPTED FOR COURSE PLACED WITH A TOTAL TONNAGE UNDER 200 TONS OR ACCEPTABLE THICKNESS UNDER 1.2" DUE TO PATCHING, WEDGE & LEVELING, BRIDGE DECKS, ... ETC.
- e. FIELD TECH. SHALL CALL THE MATERIALS LAB WITH DATE & TIME OF CORE CUTTING SO IT CAN BE WITNESSED, AND CORES & HMA SAMPLES CAN BE RECEIVED ON SITE BY A LAB INSPECTOR.
- f. INSPECTOR RANDOMLY SELECTS & MARKS CORE LOCATIONS IN THE FIELD;
 NOTES THEM DOWN ON THE CTR STATING STREET'S NAME AND ADDRESS, LOT
 #, STA #, OR DISTANCE FROM NEAREST INTERSECTION; THEN FAXES THE CTR
 AGAIN TO THE LAB, AND GIVES TO FIELD TECH BOXES FOR ONLY PR. GEOGE'S
 COUNTY HMA SAMPLES.
- g. FIELD TECH. SHALL CHECK DELIVERY TICKETS FOR COUNTY-REQUIRED INFO, COLLECT AT LEAST ONE BEHIND-THE-PAVER HMA SAMPLE/MIX/DAY, AND CUT AT LEAST 5 CORES/MIX/DAY BUT NO LESS THAN 2 CORES FROM EACH STREET, UNLESS OTHERWISE INSTRUCTED BY AN INSPECTOR; THEN HAND OVER THE SAMPLES TO DPWT INSPECTOR NO LATER THAN ONE (1) BUSINESS DAY FROM THE PAVING.
- h. IF, AT THE LAB'S DISCRETION, THE CORES' CUTTING IS NOT WITNESSED, CORES SHALL BE RECEIVED IN THE LAB, IN ONE BUSINESS DAY FROM PAVING, AS LONG AS THEY ARE NUMBERED AND WELL IDENTIFIED ON FORM #2 BY: PROJECT NAME, STREET NAME, CORE LOCATION, PAVING DATE, CORING DATE, MIX CODE, ... ETC. IF NOT PROPERLY IDENTIFIED, CORES WILL NOT BE ACCEPTED.
- i. IF, AT THE LAB'S DISCRETION, A BEHIND-THE-PAVER HMA SAMPLE IS NOT RECEIVED ON SITE, IT SHALL BE RECEIVED IN THE LAB ALONG WITH CERTIFIED DELIVERY TICKETS, IN ONE (1) BUSINESS DAY, AND BE IDENTIFIED BY: PROJECT NAME, SAMPLING LOCATION, PAVING DATE, & STATE MIX DESIGNATION. IF NOT PROPERLY LABELED, HMA SAMPLES WILL NOT BE ACCEPTED.
- j. IF CORES ARE TESTED AT AN INDEPENDENT THIRD PARTY'S TESTING LAB, THAT LAB MUST BE AASHTO ACCREDITED FOR SPECIFIC TESTS, AND BE INITIATED BY THE MATERIALS LAB, WHICH SHALL BE NOTIFIED (FAX CAN OCCASIONALLY BE ACCEPTED), OF THE TESTING DATE & TIME SO IT MAY WITNESS THE 3RD PARTY TESTING.
- k. CORE RESULTS SHALL BE REPORTED ON CORE ANALYSIS (FORM #2), E-MAILED1 TO MATERIALS LAB & INSPECTOR NO LATER THAN ONE BUSINESS DAY FROM TESTING (ONE DAY FROM CUTTING FOR COMPANION CORES), AND MAILED OUT TO PERMITEE.

- 1. FIELD TECHNICIANS AND THIRD PARTY TESTING LABS SHALL MAINTAIN A LOG OF THEIR TEST RESULTS; RECOMMENDATIONS, AND ACTIONS TAKEN TO CORRECT THE PROBLEMS, IF ANY. THE LOG SHALL BE AVAILABLE TO DPW&T FOR REVIEW UPON ANY DPW&T INSPECTOR'S REQUEST.
- 34) PERMITTEE SHALL SUBMIT PROPERTY CORNER CERTIFICATIONS AND UTILIZE METAL PROPERTY MARKERS PER PRINCE GEORGE'S COUNTY CODE, SECTION 24-120, PRIOR TO ACCEPTANCE OF STREETS.

35)	WASHINGTON SUBURBAN SANITARY COMMISSION 200 FOOT SHEET NO.:
36)	DEPARTMENT OF PUBLIC WORKS AND TRANSPORTATION SITE CONCEPT APPROVAL NUMBER:
37)	SEDIMENT CONTROL APPROVAL NUMBER:
38)	PRELIMINARY PLAN APPROVAL NUMBER:
39)	RECORD PLAT RECORDING NUMBER:

40) APPROVED STREET GRADE ESTABLISHMENT INFORMATION:

ORIGINAL STREET NAME	APPROVAL NUMBER

- 41) AT THE TIME OF PERMIT RELEASE, THE FOLLOWING MINIMUM SUBMITTAL REQUIREMENTS WHERE APPLICABLE SHALL APPLY:
- WASHINGTON SUBURBAN SANITARY COMMISSION PAVING CLEARANCE CERTIFICATION;
- BITUMINOUS CONCRETE CORE CERTIFICATIONS, ALL PAVEMENT COURSES;
- PROPERTY MARKER CERTIFICATION;
- DEPARTMENT OF PUBLIC WORKS AND TRANSPORTATION LETTER APPROVING STORM DRAIN AS-BUILT;
- TREE APPROVAL AND TREE BOND POSTED, IF NECESSARY;
- STREET LIGHT PROOF OF PAYMENT (MUST BE ACCOMPANIED BY A MEMORANDUM FROM DPW&T'S TRAFFIC SAFETY DIVISION ACCEPTING THE PROOF OF PAYMENT); AND
- PROOF/STATEMENT THAT ALL FINANCIAL MATTERS HAVE BEEN SETTLED.
- THE PERMITTEE IS RESPONSIBLE FOR THE DESIGN AND INSTALLATION OF ALL TRAFFIC SIGNS, TRAFFIC SIGNALS, AND ROADWAY MARKINGS FOR ROADWAY IMPROVEMENTS ON SUBDIVISION ACCESS ROADS WHICH INCLUDE ARTERIAL, COLLECTOR, INDUSTRIAL, AND ANY NECESSARY OFFSITE CONDITIONS WHICH REQUIRE ROADWAY IMPROVEMENTS. THE DESIGN AND/OR CONSTRUCTION DRAWINGS SHALL BE INCLUDED ALONG WITH THE PERMIT PLANS, AND SHALL BE REVIEWED AND APPROVED BY THE DEPARTMENT'S TRAFFIC SAFETY DIVISION PRIOR TO PERMIT ISSUANCE.

- 43) THE PERMITTEE IS RESPONSIBLE FOR THE DESIGN AND INSTALLATION OF ALL TRAFFIC MARKINGS, TRAFFIC SIGNALS, IF REQUIRED, AND PAYMENT OF FEE FOR STREET NAME SIGNS ON INTERNAL SUBDIVISION STREETS. TRAFFIC SIGNS WILL BE FURNISHED AND INSTALLED BY THE COUNTY.
- 44) ALL CONCRETE PIPE SYSTEMS 48 INCHES OR LESS SHALL BE INSPECTED WITH A VIDEO CAMERA AS PART OF THE FINAL "AS BUILT" CONSTRUCTION REQUIREMENTS.

GENERAL STORM DRAIN NOTES

- 1) ALL STORM DRAINS SHALL BE CONSTRUCTED IN ACCORDANCE WITH THE LATEST EDITION OF THE STORMWATER STANDARDS AND SPECIFICATIONS OF PRINCE GEORGE'S COUNTY DEPARTMENT OF ENVIRONMENTAL RESOURCES, UNLESS OTHERWISE NOTED.
- 2) FOR TYPES OF STRUCTURES REFER TO THE LATEST STORMWATER MANAGEMENT STANDARD DETAILS, DER (SWMSD), UNLESS OTHERWISE NOTED.
- 3) INFORMATION CONCERNING UNDERGROUND UTILITIES WAS OBTAINED FROM AVAILIABLE RECORDS. THE CONTRACTOR MUST DETERMINE THE EXACT LOCATIONS AND ELEVATIONS OF THE UTILITIES BY DIGGING TEST PITS AT ALL UTILITY CROSSINGS WELL IN ADVANCE OF TRENCHING. IF CLEARANCES ARE LESS THAN SPECIFIED, CONTACT THE ENGINEER, AND THE OWNER OF OTHER INVOLVED UTILITY BEFORE PROCEEDING WITH CONSTRUCTION.
- 4) ALL STORM DRAIN PIPES MUST HAVE A MINIMUM OF 1 FOOT COVER.
- 5) ALL INLET TOP SLAB FRONT FACES SHALL BE PAINTED WITH THE FOLLOWING CHESAPEAKE BAY DRAINAGE, "DON'T DUMP" (STANDARD 82.0).
- 6) CONTRACTORS SHALL ADJUST ALL EXISTING UTILITIES AS NEEDED TO CONSTRUCT PROPOSED ROAD IMPROVEMENTS. ADJUSTMENTS MAY INCLUDE BUT NOT LIMITED TO MANHOLE COVERS, VALVES, FIRE HYDRANTS, STORM DRAIN INLETS, STREET LIGHTS, TRAFFIC SIGNALS STRUCTURES, UTILITY POLES, SIDEWALKS, BURIED UTILITY CONDUIT AND PIPES.

MARLBORO CLAY GEOTECHNICAL INVESTIGATION

Marlboro Clays are extremely expansive clays of marine deposition. They are basal member of the Nanjemoy geologic formation. In appearance, they generally range from pale red to brown and most often outcrop on slopes.

Criteria for soil investigations and reports on the presence and effect of Marlboro clay upon proposed developments.

Field Investigation

Test borings

- To be adequate in number and location to address all stability concerns.
- To be of adequate depth equal to the height of existing slopes or penetrating into the Aquia formation at least 10-15 feet.
- To be performed in accordance with ASTM D 1586-67 "Penetration Test and Split Barrel Sampling of Soils".
- Subsurface soil samples to be classified using both the USDA and USCS soils classification system.
- Specify presence of all slicken sided joints.
- Soil samples also to be classified by geologic formation.
- Presence of groundwater to be noted (at time of borings' completion and after 24 hours).
- Slope profiles to be provided which show the location of geologic strata, soil boring location, and existing & proposed slope gradients.

Laboratory Analysis

All tests to be performed in accordance with applicable ASTM criteria.

- A minimum of three 3-point direct shear tests to be performed on representative samples from Marlboro formation to establish residual shear strength parameters.
- Natural moisture %
- Liquid limit
- Plastic limit
- Plastic Index
- Residual Shear Angle (degrees)
- Residual cohesion psf

Slope Stability Analysis of all Critical Slopes

- Note internal angles of friction used on geologic formation, which are to be estimated using Standard Penetration Test results.
- For the Marlboro deposits, the lowest laboratory residual shear strength parameters are to be used in the analysis.
- Analyze natural gradients to determine factor of safety.
- A required factor of safety of 1.5 must be met or recommendation presented to provide the necessary factor of safety.


Conclusions and Recommendations

- Address long-term stability
- Include necessary precaution
- Identify areas where structures should not be located, based on potential shear planes, and the 1.5 factor of safety (FOS) line.
- Show the 1.5 FOS line and the Marlboro Clay limits on the site plans.


Disclaimer

These are general guidelines to aid in the geotechnical investigation of potential development sites in the vicinity of suspected Marlboro Clay outcrops. They do not necessarily address all factors which should be evaluated during such investigations. Nor do these relieve the geotechnical engineer of the responsibility for determining and conducting other appropriate tests as may be necessary for a specific site or proposed use.

OVERLAND SHEET FLOW (MSHA-61.1-402.1)



GRASS SWALE FLOW VELOCITY (MSHA-61.1-402.3)



GRASS SWALE FLOW VELOCITY


(N=0.06)

MARYLAND STATE HIGHWAY ADMINISTRATION

I-2-A-17

8/5/80 SHA-61.1 - 402.3

CONCRETE SWALE FLOW VELOCITY (MSHA-61.1-402.4)



CONCRETE SWALE FLOW VELOCITY


(N = 0.015)

MARYLAND STATE HIGHWAY ADMINISTRATION

I-2-A-19

8/5/80 SHA.-6I.I-402.4

GRASS DITCH FLOW VELOCITY (MSHA-61.1-402.5)




GRASS DITCH FLOW VELOCITY (N=0.04)

MARYLAND STATE HIGHWAY ADMINISTRATION

I-2-A-21

8/5/80 SHA-6I.1-402.5

CONCRETE DITCH FLOW VELOCITY (MSHA-61.1-402.6)




CONCRETE DITCH FLOW VELOCITY (N=0.015)

MARYLAND STATE HIGHWAY ADMINISTRATION

I-2-A-23

8/5/80 SHA-61.1-402.6

GUTTER FLOW VELOCITY (MSHA-61.1-402.7)



GUTTER FLOW VELOCITY

MARYLAND STATE HIGHWAY ADMINISTRATION

I-2-A-25

MODIFIED 8/5/80 SHA-61.1-402.7

RATIONAL METHOD RAINFALL INTENSITY TABLE

	NO	AA 14-2004: Inte	ermediate Value	s from Interpola	tion		
			arlboro 3 NNW				
	PRINCE G	EORGE'S COUN			NTENSITY		
	TRITTEL		NCHES/HOUR				
DURATION		DETI	RN PERIOD (YI	7 A DC)			
(MINUTES)	1	2	KN PERIOD (11	10	25	50	100
5.00	4.20	5.04	6.00	6.72	7.56	8.28	
6.00			5.76	6.72	7.36	7.93	8.88 8.51
7.00	4.03 3.86	4.84	5.52	6.44	6.96	7.93	8.14
8.00	3.70	4.43	5.28	5.89	6.66	7.24	7.76
9.00	3.53	4.22	5.04	5.62	6.36	6.89	7.39
10.00	3.36	4.02	4.80	5.34	6.06	6.54	7.02
11.00	3.25	3.89	4.65	5.18	5.86	6.34	6.80
12.00	3.14	3.76	4.50	5.01	5.67	6.13	6.58
13.00	3.02	3.62	4.34	4.85	5.47	5.93	6.36
14.00	2.91	3.49	4.19	4.68	5.28	5.72	6.14
15.00	2.80	3.36	4.04	4.52	5.08	5.52	5.92
16.00	2.74	3.29	3.96	4.44	4.99	5.43	5.83
17.00	2.68	3.22	3.89	4.35	4.91	5.34	5.74
18.00	2.62	3.16	3.81	4.27	4.82	5.25	5.64
19.00	2.57	3.09	3.73	4.19	4.73	5.16	5.55
20.00	2.51	3.02	3.65	4.11	4.65	5.07	5.46
21.00	2.45	2.95	3.58	4.02	4.56	4.98	5.37
22.00	2.39	2.88	3.50	3.94	4.47	4.89	5.28
23.00	2.33	2.82	3.42	3.86	4.39	4.79	5.18
24.00	2.27	2.75	3.34	3.78	4.30	4.70	5.09
25.00	2.21	2.68	3.27	3.69	4.21	4.61	5.00
26.00	2.15	2.61	3.19	3.61	4.13	4.52	4.91
27.00	2.10	2.54	3.11	3.53	4.04	4.43	4.82
28.00	2.04	2.48	3.03	3.45	3.95	4.34	4.72
29.00	1.98	2.41	2.96	3.36	3.87	4.25	4.63
30.00	1.92	2.34	2.88	3.28	3.78	4.16	4.54
31.00	1.90	2.31	2.85	3.24	3.74	4.12	4.49
32.00	1.87	2.28	2.81	3.20	3.70	4.07	4.45
33.00	1.85	2.25	2.78	3.17	3.65	4.03	4.40
34.00	1.82	2.22	2.74	3.13	3.61	3.98	4.35
35.00	1.80	2.19	2.71	3.09	3.57	3.94	4.31
36.00	1.78	2.16	2.67	3.05	3.53	3.89	4.26
37.00	1.75	2.13	2.64	3.01	3.48	3.85	4.21
38.00	1.73	2.11	2.60	2.97	3.44	3.80	4.16
39.00	1.70	2.08	2.57	2.94	3.40	3.76	4.12
40.00	1.68	2.05	2.53	2.90	3.36	3.71	4.07
41.00	1.66	2.02	2.50	2.86	3.31	3.67	4.02
42.00	1.63	1.99	2.46	2.82	3.27	3.62	3.98
43.00	1.61	1.96	2.43	2.78	3.23	3.58	3.93
44.00	1.58	1.93	2.39	2.74	3.19	3.53	3.88
45.00	1.56	1.90	2.36	2.71	3.15	3.49	3.84
60.00	1.20	1.46	1.84	2.71	2.51	2.82	3.13

PIPE MATERIAL SPECIFICATION TABLE

Type	Specia	fication	Limitations
	AASHTO	ASTM	
Reinforced Concrete Pipe	M170	C76	Reinforced Concrete Pipe (RCP)
(RCP)			
Preformed, Rubber Joint for	M198	C443	Preformed, Rubber Joint for
Circular Reinforced Concrete	Type A		Circular Reinforced Concrete
Pipe			Pipe
Reinforced Concrete Pipe		C361	Reinforced Concrete Pipe
Polyvinyl Chloride (PVC)	M278	D1785 or D3034	Polyvinyl Chloride (PVC)
(solid), Plastic Pipe and Drain			(solid), Plastic Pipe and Drain
Pipe			Pipe
Polyvinyl Chloride (PVC)	M278	F758	Polyvinyl Chloride (PVC)
(perforated), Plastic Pipe and		Type PS 28	(perforated), Plastic Pipe and
Drain Pipe			Drain Pipe
Polyethylene (HDPE) Plastic,	M252 or M294	D2321	Polyethylene (HDPE) Plastic,
Drain Pipe			Drain Pipe
Reinforced Concrete Arch,	M206	C506	Reinforced Concrete Arch,
Culvert			Culvert
Reinforced Concrete	M207	C507	Reinforced Concrete Elliptical
Elliptical Pipe			Pipe
Corrugated Steel Pipe, Pipe	M36	A760	Corrugated Steel Pipe, Pipe
Arches			Arches
Corrugated Aluminized,	M36	A760	Corrugated Aluminized, Steel
Steel Pipe			Pipe
Aluminum Steel, Spiral Rib	M36	A760	Aluminum Steel, Spiral Rib Pipe
Pipe			
Aluminum Steel, Spiral Rib	M196	B745	Aluminum Steel, Spiral Rib Pipe
Pipe			
Corrugate, Aluminum Alloy	M196	B745	Corrugate, Aluminum Alloy
Pipe			Pipe
Aluminum, Structural, Plate	M219	B746	Aluminum, Structural, Plate
Pipe, Pipe Arches, and			Pipe, Pipe Arches, and Arches
Arches			

This table was modified from Table I-10 from the Department of Public Works and transportation "Specification and Standards for Roadways and Bridges"

Pipe Material Specification Table Issue Date: July 26, 2014

SAMPLE PIPE COMPUTATION FORM

Sample Pipe Computation Form Issue Date: July 26, 2014

	S X 8)											DATE		PROJECT NO.
	REMARKS												ГЕО		SHEET NO. PF
	TIME IN PIPE	(min)											COMPUTED	СНЕСКЕР	SHE
	PIPE	(feet)													
	>	(fps)											9	2	
S	MIN	(%)											-	OLA!IO	
PIPE COMPUTATIONS	PIPE	(inches)											l	PIPE COMPULATIONS	(PROJECT NAME)
PE COM	σ	(cfs)													ROJEC
ĪĒ	-	(in/hr)													9)
	75	(min)													
	O V	rw.													
	9	Ę													
	(2													
	AREA	TOTAL AREA											(AME)		
	AR	INCR. AREA											(FIRM NAME)		
Y, 1983.	ñ	ТО													
MCDOT JULY, 1983	PIPE	FROM													

SAMPLE STRUCTURE SCHEDULE

BONDED AND INSPECTED BY			ST	RUCTU	RE SCI	IEDULI	E,
BONDEI INSPEC BY	NO.	ТҮРЕ	WIDTH DIAM.	INV. ELEV.	TOP EL	LOWER	STANDARD DETAIL
F	6	Endwall For 30" RCP	-	166.40	17	0.23	Modified DER Standard SD/30.0
DPW&T	7	SHA Drop MH	5'	166.67	18	7.30	MD SHA Standard MD-383.11 *2
0	8	Type 'A' MH	5'	180.14	18	8.10	DER Standard SD/20.0 or 21.2
000	9	Concrete Riser	5' x 5'	192.75	19:	2.75	See Detail Sheet 4 *3
DER	10	Endwall For 30" RCP	-	185.40		- 144	DER Standard SD/30.0
	11	Type 'B' MH	- 5'	186.06	194	4.00	DER Standard SD/22.0 *3
	12	Type 'B' MH	5'	192.08	19	7.50	DER Standard SD/22.0 *3
	13	'A-10' Inlet modified	5'	186.50	199	9.90	DER Standard SD/10.1 see sht. 3
	14	Type 'B' MH	5'	195.70	29	2.50	DER Standard SD/22.0 '3
lic)	15	'A-10' Inlet	2'-6"	200.50	(24)	120	DER Standard SD/10.0 or 10.1
(Public)	16	Type 'A' MH precast	4'	201.66	12/	1/96	DER Standard SD/21.1
	17	Type 'A' MH precast	4'	202.32	1/3/	1/0)	DER Standard SD/21.1
F.	18	'A-10' Inlet	2'-6"	208.8	15%	1.70	DER Standard SD/10.0 or 10.1
D.P.W.&T.	19	Type 'B' MH	4'	543.16	~227	2.20	DER Standard SD/22.0 *3
2.	20	'D-2' Inlet, modified	2'-6"	219.24	225	5.83	DER Standard SD/14.0 *4
0.1	21	'A-10' Inlet	2'-6"	19432	198.53	198.08	DER Standard SD/10.0 or 10.1
	22	'D-2' Inlet, modified	2'-6"	194.77	198	3.33	DER Standard SD/14.04
	23	'A-10' Inlet	2'-6"	198.04	203	3.90	DER Standard SD/100 or 10.1
	24	'D-2' Inlet, modified	2'-6"	203.36	207	1.33	DER Standard SD/14.0
	25	Type 'B' MH	4'	187.50	195	5.00	DER Standard SD/22.0 *3
	13B	Observation Well	6" dia.	189.50	197	.90	See Detail Sheet 3
DER	13C	Observation Well	6" dia.	189.50	196	5.00	See Detail Sheet 3
	26	Type 'B' MH	4'	218.75	228	3.00	DER Standard SD/22.0 *3

REMARKS:

Remove wing of existing endwall as required to structurally tie existing and proposed endwalls together.
Precast structure may be substituted. Approval of shop drawings by DPW&T is required.
Precast structure maybe substituted. Approval of shop drawings by DER is required.
Standard opening on all four sides.

PIPE LOADING CHART (C-76)

T		
R.C.P. PIPE	CLASS	DEPTH TO INVERT
DIAMETER	(ASTM C76)	GRANULAR BED
12"	III	2.7' – 9.9'
12"	IV	V.L – 17.2°
12" 15" 15"	V	V.L – V.G.
15"	III	2.8' – 11.2'
15"	IV	V.L – 21.5'
15"	V	V.L –V.G.
18"	III	3.1' – 10.3'
18"	IV	V.L. – 19.4'
18"	V	V.L – V.G.
21"	III	3.4' – 11.4'
21"	IV	V.L. – 18.8'
21"	V	V.L –V.G.
24"	III	3.7' – 11.7'
24"	IV	V.L. – 18.1'
24"	V	V.L. – 16.1 V.L – V.G.
27"	III	3.8' – 11.9'
27" 27" 27" 27"	IV	V.L. – 18.1'
27"	V	V.L. – 18.1 V.L – V.G.
30"	III	3.8° – 13.7°
30"	IV	V.L – 20.9'
30"	V	V.L – 20.9 V.L – V.G.
33"		V.L. – 12.3'
	III	
33"	IV	V.L – 17.9'
33"	V	V.L – 30.2'
36"	III	V.L – 12.7'
36"	IV	V.L – 18.0'
36"	V	V.L -29.4'
42"	III	V.L. – 13.6'
42"	IV	V.L – 19.7°
42"	V	V.L 32.3
48"	III	V.L. – 14.0'
48"	IV	V.L. – 19.7'
48"	V	V.L - 30.8
54"	III	V.L. – 15.1'
54"	IV	V.L. – 21.1'
54"	V	V.L. – 33.0
60"	III	V.L16.1'
60"	IV	V.L. – 22.5'
60"	V	V.L. – 22.5 V.L – 34.5'
66"	III	V.L. – 34.3 V.L. – 17.0'
66"		V.L. – 17.0 V.L – 23.6'
	IV	V.L – 23.0
66"	V	V.L – V.G. V.L – 18.0'
72"	III	V.L – 18.0° V.L. – 24.8°
72"	IV	V.L. – 24.8°
72"	V	V.L – V.G.

ABBREVIATIONS

V.L. – Very Little – 1' Of Cover (Min.) V.G. – Very Great – 30' Of Cover


CRITERIA


Dead Load Based On Marston Formula With Saturated Clay; W-120 PCF. H-20 L.L. & AASHTO Impact

Granular Cradle-Bedding Factor = 1.50

Safety Factor 1.0 @ 0.01" Crack

Note: Storm Drain Pipe Located Within The Public Road R/W Must Also Meet DPIE Criteria.





SAMPLE PIPE SCHEDULE

BONDED AND INSPECTED BY			PIPE S	CHEDULE	*"
BOND	FROM	то	SIZE	ТҮРЕ	LENGTH
DER	1	2	24"	R.C.P. CL-III	126.00
	2	3	27"	R.C.P. CL-IV	96.00'
Z.T.	3	4	30"	R.C.P. CL-IV	27.33'
Α.	4	5	30"	R.C.P ELIV	66.50'
D.P.W.&T	6	7	18"	R.C.P. CHEN	175.00
	7	8	184	RCP. CL-IV	79.00
~	9	10	V 31/15	R.C.P. CL-III	15.00
D.E.R.	10	5	42"	R.C.P. ASTM C-361 TYPE B-25	263.00
-	12	14	15"	R.C.P. CL-III	36.00'
D.P.W&T	14	F.C. 15	15"	R.C.P. CL-III	21.00
D.P.	16	17	7'-0"x5'-1	TWIN CMP ARCH	107.00
DED	111	111	21"	R.C.P. CL-III	382.00
DER	112	1	24"	R.C.P. CL-III	126.00

Pipe Schedule

Pipe Size	ASTM/AASHTO	Material	Class or	Public -	Public -	Other -	Other -
•	Standard		Gauge	Design	As-Built	Design	As-Built
			-		-	-	
Pipe Total							
				-			
 All roun 	d concrete pipe wi	ll be installed	using manu	facturer pr	ovided rub	ber gaskets	5
2. All conc	rete pipe delivered	with lifting h	noles will blo	ck the liftir	ng hole with	a concret	e plug.

HEADLOSS COEFFICIENT MSHA $61.1 - 408.1(K_B)$

ANGLE	INLET	MANHOLE	BEND	ANGLE	INLET	MANHOLE	BEND
			STRUCTURE				STRUCTURE
0	0.5	0.15	0.01	46	1.11	0.76	0.18
1	0.51	0.16	0.01	47	1.12	0.76	0.19
2	0.52	0.18	0.02	48	1.13	0.77	0.19
3	0.53	0.19	0.02	49	1.14	0.78	0.19
4	0.54	0.2	0.03	50	1.15	0.78	0.19
5	0.54	0.22	0.03	51	1.16	0.79	0.19
6	0.55	0.22	0.03	52	1.17	0.8	0.19
7	0.56	0.24	0.04	53	1.18	0.8	0.19
8	0.57	0.26	0.05	54	1.19	0.81	0.2
9	0.58	0.27	0.05	55	1.2	0.82	0.2
10	0.59	0.28	0.06	56	1.21	0.82	0.2
11	0.6	0.3	0.06	57	1.22	0.83	0.2
12	0.61	0.31	0.07	58	1.23	0.84	0.2
13	0.62	0.34	0.07	59	1.24	0.84	0.2
14	0.62	0.34	0.07	60	1.25	0.85	0.2
15	0.63	0.35	0.08	61	1.26	0.85	0.2
16	0.64	0.36	0.08	62	1.27	0.86	0.2
17	0.65	0.38	0.09	63	1.27	0.86	0.2
18	0.66	0.39	0.09	64	1.28	0.87	0.2
19	0.67	0.4	0.09	65	1.29	0.87	0.2
20	0.68	0.42	0.1	66	1.3	0.88	0.21
21	0.69	0.43	0.1	67	1.31	0.88	0.21
22	0.7	0.44	0.11	68	1.32	0.89	0.21
23	0.71	0.46	0.11	69	1.32	0.89	0.21
24	0.73	0.47	0.11	70	1.33	0.9	0.21
25	0.74	0.48	0.12	71	1.34	0.91	0.21
26	0.76	0.5	0.12	72	1.35	0.91	0.21
27	0.78	0.51	0.13	73	1.36	0.91	0.21
28	0.8	0.52	0.13	74	1.37	0.92	0.22
30	0.82	0.54	0.13	75 76	1.37	0.92	0.22
31	0.83	0.55	0.14	77	1.38 1.39	0.93	0.22
32	0.87	0.58	0.14	78	1.39	0.94	0.22
33	0.89	0.59	0.14	79	1.41	0.94	0.22
34	0.89	0.59	0.14	80	1.41	0.94	0.23
35	0.92	0.62	0.15	81	1.42	0.95	0.23
36	0.94	0.63	0.15	82	1.43	0.96	0.23
37	0.96	0.64	0.16	83	1.44	0.96	0.23
38	0.98	0.66	0.16	84	1.45	0.97	0.24
39	0.99	0.67	0.16	85	1.46	0.97	0.24
40	1.01	0.68	0.17	86	1.47	0.98	0.24
41	1.03	0.7	0.17	87	1.47	0.98	0.24
42	1.05	0.71	0.17	88	1.49	0.99	0.25
43	1.06	0.72	0.17	89	1.49	0.99	0.25
44	1.08	0.74	0.18	90	1.5	1	0.25
45	1.1	0.75	0.18				

HEADLOSS COEFFICIENT MSHA 61.1 - 408.1(KB)

Issue Date: July 26, 2014

SAMPLE HEADLOSS CALCULATION

GENERAL EQUATIONS FOR HEADLOSS COMPUTATION


$$H_{B=} \qquad \frac{K_B V_F^2}{2g}$$

Where: H_B = Head loss (in feet)

 K_B = Head loss coefficient (Appendix 8-14 which is MSHA form 61.1 - 408.1)

 V_F = Velocity in the outlet pipe in feet per second based on flowing full.

g = Acceleration due to gravity (in feet per second, per second).



Example 1:

Ø₁=30° and Structure type is Manhole,

so $K_B=0.55$ (from Appendix 8-14)

$$V_F = V_2 = 8.2 \text{ fps}$$

Therefore,
$$H_B = (0.55 \times 8.2^2) /_{64.4} = 0.58 \text{ ft}$$

Example 2 (Junctions):

Structure Type is Inlet. From Appendix 8-14

Pipe 1: $V_{1/3}=2.1$ fps & $\emptyset_1=81^{\circ}$, So $K_1=1.42$

=>>
$$H_1 = \frac{(1.42 \times 2.1^2)}{64.4} = 0.10 \text{ ft}$$

 $H_2>H_1$. so \emptyset_2 is the controlling angle.

so $K_B = K_2 = 1.39$ (from Appendix 8-14)

 $V_F = V_3 = 8.2 \text{ fps}$

Therefore,
$$H_B = \frac{(1.39 \times 8.2^2)}{64.4} = 1.45 \text{ ft}$$

Pipe 2: V _{2/3}=2.5 fps & Ø₂=77°, So K₂=1.39
=>>
$$H_2 = \frac{(1.39 \times 2.5^2)}{64.4} = 0.14 \text{ ft}$$


SAMPLE HEADLOSS FORM



		-493											STO	ORM SEWERS	ATE
HEC	KED	BY:	200		_			TRAC						#FROM FORM S	HA-6LI-420
Mruci				Runoff	_		TIT	LE_	Pi					#FROM FORM S	
T				i Rainfall intens		Size	n or	So			L	d _n Normal			Elevation
rom	То	ΣCA ₩	†c	intena in/hr.	ds.		ing's Coet	Slope # %	Slope %	ft./sec	Ft.	An Normal Depth ft	Kb .	Desciption of Loss	Esercision
\dashv	-	_													
+		_		\vdash	_	-				_			-	7	
4															
\dashv	_	-													
				_		_			-		_				_
+															
						-		-				-			-
-		-		-	_	-									
_					_	-	-		-		-				
			-				-								
							-	-	-	-	-	-	-		
-	-			-	-	-		-		-					
				-	-	-	-	-	-		-	-	-		
		-	-	-		-	-	-	1	-					
	_	-	-	-	-	-	-	-	-	-	-	-	-		
-	-		-	+	-	+	-	-							
													-		
	_	-	-	-	-	-	-	+	+	-	-	-	-		
_	-	-	-	+	-	+	+	-	-	-					
_											L		F		
													-		

CURB AND GUTTER SPREAD GRAPH


Gutter Flow Rates For 2% Cross Slope For Public Streets





INLET CAPACITY


- 1. Inlet Capacity Form
- 2. 5' Curb Opening Inlet Capacity
- 3. 10' Curb Opening Inlet Capacity
- 4. 15' Curb Opening Inlet Capacity
- 5. 2' Curb Opening Inlet Capacity

GUTTER FLOW
DEPTH SPREAD DATE PROJECT NO. THROAT DEPRESS. (ii) SHEET NO. COMPUTED CHECKED CURB Œ CROSS SLOPE (ft/ft) STREET SLOPE (%) COMP. ACTUAL
(ft) (ft) cfs TO FLOW INLET COMPUTATIONS (PROJECT NAME) FLOW INTER. (cfs) TOTAL INFLOW (cfs) OVER FLOW (cfs) Base Flow (cfs) l (in/hr) T.C. (min) ΣAR AR C.A (FIRM NAME) TOTAL AREA (ac) INCR. AREA (ac) NO.










MSHA INLET INTERCEPTION AND EFFICIENCY CAPACITY CURVE



STRUCTURE WIDTH SAMPLE COMPUTATION

$$D = 2\left(\frac{d}{12} + 1\right) + d$$

$$\sin \theta = \frac{D}{x_2} \implies X_2 = \frac{D}{\sin \theta}$$

$$\tan \theta = \frac{T}{X_1} \Rightarrow X_1 = \frac{T}{\tan \theta}$$

$$W_{min} = X_1 + X_2 = \frac{D}{\sin\theta} + \frac{T}{\tan\theta}$$

d = inside (nominal) diameter (inches)

D = outside pipe diameter (inches)

T = wall thickness (inches)

W = inside dimension of the structure (inches)

 W_{min} = minimum inside dimension of the structure wall (inches


DETERMINING "n" FOR RIPRAP LINED CHANNEL USING DEPTH OF FLOW

Figure H.2: Determining "n" for Riprap Lined Channel using Depth of Flow 0.08 0.07 0.06 Manning's 0.05 0.04 0.03 0.02 0.8 1 0.5 10 20 Depth of Flow (FT) $n = \frac{y^{\frac{1}{8}}}{[21.6\log_{10}(\frac{y}{d_{50}}) + 14.0]}$ (y = Depth of Flow) PAGE H.13

2011 MARYLAND STANDARDS AND SPECIFICATIONS FOR SOIL EROSION AND SEDIMENT CONTROL


DETERMINING "n" FOR RIPRAP LINED CHANNEL USING DEPTH OF FLOW Issue Date: July 26, 2014

LIMITING VELOCITIES FOR RIP-RAP LINING (MSHA-61.1-405.1)



Limiting Velocities For Rip-Rap Lining (Msha-61.1-405.1) Issue Date: July 26, 2014

M-NCPPC HEAD/ENDWALL STONE VENEER DETAIL



SWM LANDSCAPE CRITERIA

To be provided later

SWM FACILITY VEGETATION GUIDELINES

PLANTS FOR STORMWATER MANAGEMENT FA'EILITIES In PRINCE GEORGE'S COUNTY, MARYLAND

The lists on the following pages are intended as a starting point for those who are creating or enhancing wetlands for stormwater management facilities in Prince George's County. Other species may be included on the Landscape Plan plant schedule for consideration by PRD on a case-by-case basis. For stormwater management facilities in upland areas, designers should consult the Prince George's County Bioretention plant list available from DER PPD.

The attached lists give information on three variables; wildlife value, adaptation to wetland growing conditions and tolerance to periodic flooding. These are discussed below.

Wildlife values are given as high, medium or low. Information on which plant species are useful to various wildlife species is available in existing publications and will be of particular interest to those designing for wildlife management.

Wetland indicators are taken from the <u>National List of Plant Species That Occur in Wetlands:</u> <u>Northeast (Region 1)</u>. USDI/Fish and Wildlife Service, 1988. While compiled as an aid to wetland identification, they may be used as a guide to the adaptability of various species to various <u>prevailing</u> soil moisture conditions. The categories are defined as follows:

Obligate Wetland (BL): Occur almost always (estimated 90% probability) under natural conditions in wetlands.

<u>Facultative Wetland</u> (FACW)): Usually occur in wetlands (estimated probability 67-99%), but occasionally found in nonwetlands.

<u>Facultative</u> (FAC): Equally likely to occur in wetlands or nonwetlands (estimated probability 34-67%)

<u>Facultative Upland</u> (FACU): Usually occur in nonwetlands (estimated probability 76-99%), but occasionally found in wetlands (estimated probability 1-33%)

Obligate Upland (UPL): Occur in wetlands in another region, but occur almost always (estimated probability > 99%) under natural conditions in nonwetlands in this region. If a species does not occur in wetlands in any region, it is not included on this list.

A plus or minus sign indicates if the species is usually found in the wetter (+) or drier (-) end of its category.

<u>Flood tolerance</u> refers to the ability to survive <u>periodic</u> flooding. While this is shown as "yes" or "no", these are not absolutes. Actual plant survival will also depend on such variables as the amount of soil loss around roots and the amount of silt deposited over the root zone during the storm event.

																٦				<u>=</u>												
· ·	Comments	rapid prowth		rapid growth; streambanks	and the state of t	prefers shad; understory		streambank stabilizer							needs full sun	prefers shad; well-drained loam	stream stabilizer	stream stabilizer		conifer, full sun; acid, boggy soil	rapid growth	tolerates acid or clay soils	requires some shade	• 5.				rapid growth				*
	Flood Tol.	800	200	yes		yes		yes					probably		0	0	yes	yes		yes	2	yes	yes			yes		yes		2	yes	
JS TREES	Wetland Status	FAC		A P) () ()	J. A.	FACU+	FACW	FACU	FACU+	FACU-	FACW	FAC+	FACU	FAC-	FACU	FACW	FACW	FACU			FAC	FACW+		FACU	FAC	FACW	FACW	FACU	FACU	OBL	FACU
DECIDIOOUS TREES	Wildlife	high			1	ngin		low		high	high			high	mod.	high	mod.	mod.	high	you	mod.	mod.	No		mod.	high		Nol	high	high	high	high
	Common Name	Red Maple		Black Alder		Serviceberry	Common Paw-Paw	River Birch	American Hornbeam	Bitternut Hickory	Shagbark Hickory	Sugar Hackberry	Fringe Tree	Hawthorns	Persimmon	American Beech	Green Ash	Black Ash	Black Walnut	Larch or Tamarack	Tulip Tree	Sweet Gum	Sweetbay	Dawn Redwood	Red Mulberry	Black Gum	Eastern Cottonwood	Sycamore	Black Cherry	Purple Chokecherry	Swamp White Oak	Southern Red Oak
	Botanical Name	Ager rubrum		Ainus giutinousa	A serial diagram	Ameianchier canadensis	Asimina triloba	Betula nigra	Carpinus caroliniana	Carya cordiformis	Carya ovata	Celtis laevagata	Chionanthus virginicus	Crataegus spp.	Diospyros virginiana	Fagus grandiflora	Fraxinus pennsylvanica	Franxinus nigra	Juglans nigra	Larix laricina	Liriodendron tulipifera	Liquidamber styraciflua	Magnolia virginiana	Metasequoia glyptostroboides	Morus rubra	Nyssa sylvatica	Populus deltoides	Platanus occidentalis	Prunus serotina	Prunus virginiana	Quercus bicolor	Quercus falcata

	Comments	P 26	streambanks	prefers full sun		Comments	plant 1 male, 10 females	semi-evergreen			Comments		shade; drought tolerant shade tolerant
	Flood Tol.	yes yes yes	yes	yes		Flood Tol. no no	infrequent	yes	some no		Flood Tol. yes no	yes	yes
STREES	Wetland Status	FACW FACW FACW FACW-	FACW+ FACU	FACW+	A LUELO	Wetland Status FAC OBL	FACU	FACW+ FACU	FACW	SHRUBS	Wetland Status FACW FACU	OBL FAC+	FACW FACW+ FACU
DECIDUOUS TREES	Wildlife	high high high	low	mod. FAC	LVENGREE	Wildlife	food	<u>wol</u>	high cover	DECIDUOUS SHRUBS	Wildlife mod.	high	mod. mod.
	Common Name	Swamp Chestnut Oak Pin Oak Willow Oak White Willow Weeping Willow	Black Willow Mountain Ash European Ash	Common Bald Cypress		Common Name Balsam Fir Cedar, Atlantic White	Holly, American Eastern Redcedar	Swamp Magnolia or Sweetbay Pitch Pine	Lobiolly Pine Eastern Arborvitae		Common Name Red Chokeberry Black Chokeberry Sweet Chokeberry	Sweet Pepperbush	Silky Dogwood Red Osier Dogwood Hawthorns
	Botanical Name	Quercus michauii Quercus palustris Quercus phellos Salix alba Salix babylonica	Salix nigra Sorbus americana Sorbus aucuparia	Taxodium distichum		<u>Vame</u> amea ars thyoides	<i>a</i>	giniana	Pinus taeda Thuja occidentalis		Botanical Name Aronia arbutifolia Aronia melanocarpa	Cephalanthus occidentalis	Cornus amonum Cornus stolinifera Crataegus spp.

)
1
)
`
)
)
)
)
)
١
5
j

Comments	S	,							iš					*			and the standard of the standa	streambank stabilizer						
Flood Tol.		0	on		0		0				yes					200	200							
Wetland Status	FAC	FAC-	OBC	FACW	FACW	FAC	FACU	FAC		FAC	OBL		OBL	FACU-	FACW	FACW.		FACW	FACW	FACW-	FAC		FACU	
Wildlife	high	wol	mod.	high	mod.	high	high				wol	mod.		high	high	hich	20	mod.		high				
Common Name	Huckleberries	Witch Hazel	Smooth Winterberry	Common Winterberry	Spice Bush	Northern Bayberry	Purple Chokecherry	Smooth Azalea		Rosebay Rhododendon	Swamp Azalea	Staghorn Sumac	Swamp Rose	Rugosa Rose	Bristly Hispoides Blackberry -	Amerian Elder		Purple-osier Willow	Steeple Bush	Highbush Blueberry	Southern Arrowwood	European Cranberry	Black Haw	
Botanical Name	Gaylussacia spp.	Hamamelis virginiana	llex laevigata	llex verticillata	Lindera benzoin	Myrica pennsylvanica	Prunus virginiana	Rhododendron	arborescens	Rhododendron maxima	Rhododendron viscosum	Rhus typhina	Rosa palustris	Rosa rogosa	Rubus hispida	Signature of the state of the s	Sallibucus calladelisis	Salix purpurea 'Streamco'	Spirea tormentosa	Vaccinium corymbosum	Viburnum dentatum	Viburnum opulus	Vibumum prunifolium	

BROADLEAF EVERGREEN SHRUBS

Comments			tolerates acid soils		rampant	rampant						
Flood Tol.	yes	00	0		01	0	0			0	9	no
Wetland Status	FACW-	FAC	FACU	VES	FAC	FACU-		FACU		FACW	FACW	FAC
Wildlife	yes		wol	WOOD VINES		Mol	Nol			high	high	high
Common Name Strawbery-bush American	Inkberry	Sheep-Laurel	Mountain Laurel		Trumpet Vine	Bittersweet	Autum Clematis		Virginia Creeper	Swamp Dewberry	Riverbank Grapes	Winter Grapes
Botanical Name Fuonymus americanus	llex glabra	Kalmia augustifolia	Kalmia latifolia		Capsis radicans	Celastris scandens	Clematis paniculata	Parthenocissus	quinquefolia	Rubus hispidus	Vitis riparia	Vitis vulpina

(n	
ĭ	_	
-	,	
4	4	
<	ι	
_	ı	
C	250	
(ע	
ī	_	
'	-	
-	\$	
-	ر	
(3	
2	1	
	_	
C	ひこく つびて る	
1	,	
4	÷	
L	П	
(D	
C	LINE COLUMN	
ī	11	
-	≓	
	2	
	11	

Botanical Name	Common Name	Wildlife	Wetland Status	Flood I ol.	Comments
Acorus calamus	Sweet Flag	wol	OBL	yes	emergent
Cephalanthus occidentalis	Buttonbush	high	OBL	yes	emergent
Ceratophyllum demersum	Coontail	wol	OBL	yes	emergent
Cyperus spp.	Sedges	mod.	varies	yes	emergent
	Marsh Hibiscus		OBL	yes	emergent
	Rice Cutgrass		OBL	yes	emergent
	Water Cress		OBL	yes	perimeter
Nuphar luteum	Spatterdock		OBL	yes	emergent
	Arrow Arum/Duck Corn		OBL	yes	emergent
	Smartweed		varies	yes	emergent
ata	Pickerelweed		OBL	yes	emergent
,	Pond Weed		OBL	yes	submergent
	Arrowhead/Duck Potato		OBL	yes	emergent
Saururus cernuus	Lizard's Tail	wol	OBL	yes	emergent
Scirous americanus	Common Three-Square	high	OBL	yes	emergent
Scirpus validus	Soft-stem Bulrush	mod.	OBL	yes	emergent
Viburnum recognitum	Smooth Arrowwood		FACW-		
'Fernald'	Highbush Cranberry	pour	FACW	Ves	
Viburnum milopain	financia lispansi				

WARNING SIGN

To be provided later

STORM DRAIN DISCHARGE OPTIONS INTO SWM FACILITY

To Be Provided Later

M-NCPPC GUIDELINES FOR STORMWATER MANAGEMENT FACILITIES

GUIDELINES FOR STORMWATER MANAGEMENT FACILITIES TO BE LOCATED ON M-NCPPC PROPERTY IN PRINCE GEORGE'S COUNTY

There are three levels of SWM/ESD facilities that will be approved for installation on Maryland National Capital Park and Planning Commission (M-NCPPC) property. The first level are large facilities incorporated into the park recreation area. Examples include Cosca Lake. The second level of SWM facilities are those that control SWM or provide water quality for park development facilities or private development using M-NCPPC property and generally have drainage areas less than 50 acres. The third level of facilities is the small ESD devices required by the Maryland 2007 SWM Act and generally have drainage areas less than 2 acres. They may be used either for Developer projects with permission from Department of Parks and Recreation (DPR) or for M-NCPPC projects.

- **A.** The following guidelines shall be considered in the location and design all Level 1 SWM facilities proposed on M-NCPPC property. These are in addition to the requirements established by DPIE in their design manual.
 - 1. SWM facilities will be considered for placement on M-NCPPC property either existing or to be conveyed as part of a subdivision requirement after all alternatives for locating the facility on private property have been exhausted. This includes any portion of the proposed pond including areas to be flooded by 1-, 10-, and 100-year flood pool. Refer to "Public Stormwater Management Pond Ownership and Maintenance Policy" for guidance on these issues.
 - 2. The preferred alternative for all level 1 Stormwater Management (SWM) facilities located on the M-NCPPC property in Prince George's County is a wet pond.
 - 3. The SWM facility shall be part of a community open space system with a park land connection(s) to other park areas such as Stream Valley Parks Community Parks, Natural Corridors, Environmentally Unique or Sensitive areas, etc. The SWM facility shall be designed to be accessible for community level use when appropriate, serving an area with a population of approximately 24,000 to 40,000 people living within a 15 minute driving time.
 - 4. A Recreation Plan shall be submitted for the SWM facility by the Developer, in conjunction with DPR.

- a. The plan shall stress the proposed recreation uses for the facility such as nature study, non-motorized boating, and fishing.
- b. The physical layout of the SWM facility shall reflect the proposed recreation use through the development of facilities, which may include trails, fishing docks, boat access points, etc.
- c. The recreation plan shall be reviewed and approved by DPR at the Site Development Concept Plan phase of the project. Final construction documents for the SWM facility will also require DPR review and approval.
- 5. Vehicular access to the SWM facility shall be from a through street or road. Access from the cul-de-sac is only acceptable for maintenance access of the SWM/Park facility.
- 6. The shapes of the facility shall be as natural as possible and in keeping with the general topography of the area.
- 7. The slopes around the facility and dam embankment should be 4:1 or flatter. However, where that is not feasible, the steepest acceptable slopes are 3:1 only for the dam embankment.
- 8. A minimum 15-foot wide upland bench shall be provided around the pond, with a 2% cross slope draining toward the pond. The bench shall be located in between the 1 and 10-year pool elevations. These requirements may vary where existing wooded slopes adjacent to the normal pool are to be retained.
- 9. An aquatic shelf shall be located 6"-12" below the permanent pool and shall be a minimum of 10 feet in width around the entire shoreline of the pond, except where the riser structure and outfalls require greater depth. These benched areas are primarily for the safety of the park users.
- 10. SWM facilities shall not be fenced unless DPR requires fencing.
- 11. A maintenance access road/trail shall be provided around the entire SWM pond. The road/trail shall be 12 feet wide, with asphalt paving meeting the County road standard for secondary residential road from the initial access point to the riser structure. The remainder of the road/trail may be 4" thick asphalt paving and suitable for use by maintenance trucks as well as pedestrians and bicycles.


- a. The road/trail shall be located on the shoreline bench where possible.
- b. In other "natural" shoreline areas the road/trail shall be concealed where possible, behind existing trees or other plantings, providing access to the edge of the pond as needed for maintenance and recreation purposes.
- 12. An adequate buffer strip shall be included around the entire SWM pond. The buffer shall be minimum 100-foot wide strip of well-vegetated park property between the 100-year flood elevation and any adjacent private property line.
- 13. DPR shall approve a separate Landscape Plan for the SWM facility as part of their approval of the SWM plan.
 - a. The entire aquatic shelf shall be planted in a mix of aggressive colonizing native emergent plants installed a maximum 1'6" on center.
 - b. All graded side slopes above the upland bench outside of the embankment limits shall be reforested with a mix of native tree species 15' on center, ½ "caliper, placed in a random pattern.
 - c. Include masses of native flowering trees and shrubs at visible edges of reforested areas.
 - d. Individual specimen trees may be installed at spacing greater than 15' where views of the pond from adjacent areas of developed park or residences are desirable.
- 14. All storm drain outfalls shall have a stone veneer or stamped concrete on the head wall, per the M-NCPPC detail in the County SWM Design Manual for pipe sizes greater than 12 inches.
 - a. End sections are acceptable for pipes sizes 24" or smaller.
 - b. The stamped concrete shall be a rusticated ashlar stone created with a form liner by Scofield or approved equal is acceptable. Shop drawings are to be approved by DPR.
 - c. The concrete mix shall meet Maryland State Highway Administration (MSHA) Mix 3 for strength and shall include a brownish tan pigment.

- d. The riser structure shall also provide for a stone veneer or stamped concrete.
- 15. For additional design criteria and suitable plant species see Controlling Urban Runoff: A Practical Manual for Planning and Designing Urban BMP's by Thomas R. Schueler, Chapters 4 and 9, published by Metropolitan Washington Council of Governments.
- 16. A MOU is required to be signed by the Developer, DPIE, and M-NCPPC outlining the maintenance responsibilities and any payments. For projects that are residential in nature, the County may perform the functional maintenance whereas M-NCPPC will perform the daily maintenance.
- **B.** The following guidelines shall be considered in the location and design all Level 2 SWM facilities proposed on M-NCPPC property. These are in addition to the requirements established by DPIE in their design manual.
 - 1. SWM facilities will be considered for placement on M-NCPPC property after all alternatives for locating the facility on private property have been exhausted. This includes any portion of the proposed pond including areas to be flooded by 1-, 10-, and 100-year flood pool. Refer to "Public Stormwater Management Pond Ownership and Maintenance Policy" for guidance on these issues.
 - 2. Vehicular access to the SWM facility shall be from a through street or road. Access from the cul-de-sac is only acceptable for maintenance access of the SWM facility.
 - 3. The shapes of the ponds shall be as natural as possible and in keeping with the general topography of the area.
 - 4. Where excavation has to be restored to, it is preferred that the slopes around the ponds and dams be 4:1 or flatter, however, where that is not possible, the steepest acceptable slopes are 3:1 for the dams embankment only.
 - 5. An adequate buffer strip shall be included around the entire SWM pond. The buffer shall be minimum 50 feet wide strip of well-vegetated park property between the 100-year flood pool line and any adjacent private property line.
 - 6. DPR shall approve a separate Landscape Plan for the SWM facility as part of their approval of the SWM plan.

- a. The entire aquatic shelf shall be planted in a mix of aggressive colonizing native emergent plants installed a maximum 1'6" on center.
- b. All graded side slopes above the upland bench outside of the embankment limits shall be reforested with a mix of native tree species 15' on center, ½ "caliper, placed in a random pattern.
- c. Include masses of native flowering trees and shrubs at visible edges of reforested areas.
- d. Individual specimen trees may be installed at spacing greater than 15' where views of the pond from adjacent areas of developed park or residences are desirable.
- 7. All storm drain outfalls shall have a stone veneer or stamped concrete on the head wall, per the M-NCPPC detail in the County SWM Design Manual for pipe sizes greater than 12 inches.
 - a. End sections are acceptable for pipes sizes 24" or smaller.
 - b. The stamped concrete shall be a rusticated ashlar stone created with a form liner by Scofield or approved equal is acceptable. Shop drawings are to be approved by DPR.
 - c. The concrete mix shall meet MSHA Mix 3 for strength and shall include a brownish tan pigment.
 - d. The riser structure shall also provide for a stone veneer or stamped concrete.
- 8. A MOU is required to be signed by the Developer, DPIE, and M-NCPPC outlining the maintenance responsibilities and any payments. For projects that are residential in nature, the County may perform the functional maintenance whereas M-NCPPC will perform the daily maintenance.
- C. The following additional guidelines shall be considered in the location and design all Level 3 SWM facilities proposed on M-NCPPC property. These are in addition to the requirements established by DPIE in their design manual.


A MOU is required to be signed by the Developer, DPIE, and M-NCPPC outlining the maintenance responsibilities and any payments. For projects that are residential in nature, the County may perform the functional maintenance whereas M-NCPPC will perform the daily maintenance.

RISER WEIR AND ORIFICE FLOW SCENARIOS



ELEV. OUTSIDE OF RISER < TOP OF OPENING ELEV. ELEV. INSIDE OF RISER < CREST ELEV.


WEIR FLOW FREE FALL CONDITION



ELEV. OUTSIDE OF RISER < TOP OF OPENING ELEV. ELEV. INSIDE OF RISER > CREST ELEV.


WEIR FLOW SUBMERGED CONDITION

Riser Weir And Orifice Flow Scenarios Issue Date: July 26, 2014



ELEV. OUTSIDE OF RISER > TOP OF OPENING ELEV. ELEV. INSIDE OF RISER < \not C OF OPENING ELEV.


ORIFICE FLOW FREE FALL CONDITION - NOT PREFERRED




ELEV. OUTSIDE OF RISER > TOP OF OPENING ELEV. ELEV. INSIDE OF RISER > \bigcirc OF OPENING ELEV.

ORIFICE FLOW SUBMERGED CONDITION - PREFERRED

RISER LOCATION SKETCH



RISER PROFILE




BENCHES:

- A 10 FOOT WIDE MAINTENANCE/SAFETY BENCH SHALL BE LOCATED AT LEAST 1 FOOT BELOW THE 1 YEAR WEIR (THE WEIR SET AT THE EXTENDED DETENTION WATER SURFACE ELEVATION).
- FOR WET EXTENDED DETENTION PONDS, A 5' WIDE SAFETY BENCH WILL BE PLACED 6" 1' BELOW PERMANENT POOL DEEPER THAN 2'.
- ACCESS TO THE REAR OF THE RISER STRUCTURE SHALL BE MAINTAINED BY EMBEDDING THE RISER INTO THE EMBANKMENT SO IT CAN BE ACCESSED IF THE 1 YEAR CONTROL OPENING IS CLOGGED.

LOW FLOW PIPE EXAMPLES


To Be Provided Later

TYPICAL BARREL & RISER PROFILE



TYPICAL BARREL AND RISER PROFILE

TYPICAL EMBANKMENT CROSS SECTION



TYPICAL EMBANKMENT CROSS SECTION

EMERGENCY SPILLWAY CROSS SECTION & PROFILES

To be provided later

GEOTECHNICAL TESTING REQUIREMENT FOR INFILTRATION SYSTEMS

Documentation

Infiltration testing data shall be documented, and include a description of the infiltration testing method. This is to ensure that the tester understands the procedure.

Test Pit/Boring Requirement


- a. Excavated a test pit or dig a standard soil boring to a depth of 4 feet below the proposed facility bottom;
- b. Determine depth to groundwater table (if within 4 feet of proposed bottom) upon initial digging or drilling, and again 24 hours later;
- c. Conduct Standard Penetration Testing (SPT) every 2' to a depth of 4 feet below the facility bottom;
- Determine United States Department of Agriculture (USDA) or Unified Soil Classification (USC) System textures at the proposed bottom and 4 feet below the bottom of the best management practice (BMP);
- e. Determine depth to bedrock (if within 4 feet of proposed bottom);
- f. The soil description should include all soil horizons; and
- g. The location of the test pit or boring shall correspond to the BMP location; test pit/soil boring stakes are to be left in the field for inspection purposes and shall be clearly labeled as such.

Infiltration Testing Requirements (field testing required)

- a. Install casing (solid 5 inch diameter, 30" length) to 24" below proposed BMP bottom (See Figure D.1.1).
- b. Remove any smeared soiled surfaces and provide a natural soil interface into which water may percolate. Remove all loose material from the casing. Upon the tester's discretion, a two (2) inch layer of course sand or fine gravel may be placed to protect the bottom from scouring and sediment. Fill casing with clean water to a depth of 24' and allow pre-soaking for twenty-four hours.
- c. Twenty-four hours later, refill casing with another 24" of clean water and monitor water level (measured drop from the top of the casing) for 1 hour. Repeat this procedure (filling the casing each time) three additional times, for a total of four observations. Upon the tester's discretion, the final field rate may either be the average of the four observations, or the value of the last observation. The final rate shall be reported in inches per hour.
- d. May be done through a boring or open excavation.
- e. The location of the test shall correspond to the BMP location.
- f. Upon completion of the testing, the casings shall be immediately pulled, and the test pit shall be back-filled.

Laboratory Testing

Use grain-size sieve analysis and hydrometer tests (where appropriate) to determine USDA soils classification and textural analysis. Visual field inspection by a qualified professional may also be used, provided it is documented. The use of lab testing to establish infiltration rates is prohibited.



INFILTRATION TRENCH SPECIFICATIONS & NOTES

To be provided later

BMP SUMMARY TABLE

	ON_OFF.SITE																									ı
	8		T																							
	100 100																									
THE CHARLES AND A CHARLES AND	DESIGN VOLUME (GT) N USING STRUCTURAL PRACTICES																									
NAME OF THE PROPERTY OF THE PR	DESIGN VOL (FT) USING ESD FRACTICES																									
	TARGET VOL																									
	TARGET P _E (IN)																									
	.≩																									
	PERCENT																									
ABLE ABLE		0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
, Suite 420 10774 MARY	TOTAL NEW MPRYVOUS (MPRYVOUS AREA (AC) AREA (AC)																									
lan Review com Place Maryland 2 P SUMI Date: May 31	TOTAL TOTAL INPERVIOUS AREA (AC)																									
StieRoad Plan Review Division 9400 Peppercom Place, Suite 420 Largo, Maryland 20774 Final Plan BMP SUMMARY TABLE Revision Date: May 30, 2014	DHINGE HER (1C) WERNOTS INVENTOR DRINGS																									1
Lius	CONSTRUCTION PURPOSE																									
	LANDUSE																									ı
	MDEAST																									
	MD NORTH																									
	NAVE																									
	19861																									

SAMPLE BMP CALCULATIONS -

- 1. Rooftop Disconnect
- 2. Non Rooftop Disconnect
- 3. Sheet Flow to Conservation Area
- 4. Dry Well
- 5. Grass Swale
- 6. Bio Swale

To be provided later

BMP SPECIFICATION

- 1. Landscape Specification
- 2. Submerged Gravel Wetlands
- 3. Wet Swales
- 4. Bio Device Specification
- 5. Dry Well Specification
- 6. Permeable Paving TO BE PROVIDED LATER
- 7. Green Roof TO BE PROVIDED LATER

LANDSCAPE SPECIFICATIONS

LANDSCAPE SPECIFICATIONS SHALL BE AS OUTLINED BELOW OR AS SPECIFIED AS BEST PRACTICES IN THE INDUSTRY. ANY ITEM OR PROCEDURE NOT MENTIONED BELOW SHALL BE AS SPECIFIED IN THE LANDSCAPE SPECIFICATION GUIDELINES PUBLISHED BY THE LANDSCAPE CONTRACTORS ASSOCIATION (LATEST EDITION) OR AS SUBSEQUENTLY AMENDED.

(a) PLANT MATERIALS

THE LANDSCAPE CONTRACTOR SHALL FURNISH AND INSTALL AND/OR DIG, BALL, BURLAP, AND TRANSPLANT ALL OF THE PLANT MATERIALS CALLED FOR ON THE DRAWING AND/OR LISTED IN THE PLANT SCHEDULE.

(b) PLANT NAMES

PLANT NAMES USED IN THE PLANT SCHEDULE SHALL BE IDENTIFIED IN ACCORDANCE WITH HORTUS THIRD, BY L.H. BAILEY, 1976 OR ANY SUBSEQUENT EDITION.

(c) PLANT STANDARDS

ALL PLANT MATERIALS SHALL BE EQUAL TO OR BETTER THAN THE REQUIREMENTS OF THE "AMERICAN STANDARD FOR NURSERY STOCK," LATEST EDITION, AS PUBLISHED BY THE AMERICAN NURSERY AND LANDSCAPE ASSOCIATION (HEREAFTER REFERRED TO AS "ANLA STANDARDS"). ALL PLANTS SHALL BE TYPICAL OF THEIR SPECIES AND VARIETY, SHALL HAVE A NORMAL HABIT OF GROWTH, AND SHALL BE FIRST QUALITY, SOUND, VIGOROUS, WELL-BRANCHED, AND WITH HEALTHY WELL-FURNISHED ROOT SYSTEMS. THEY SHALL BE FREE OF DISEASE, INSECT PESTS, AND MECHANICAL INJURIES.

- (1) ALL PLANTS SHALL BE NURSERY GROWN AND SHALL HAVE BEEN GROWN UNDER THE SAME CLIMATIC CONDITIONS AS THE LOCATION OF THIS PROJECT FOR AT LEAST TWO YEARS BEFORE PLANTING. NEITHER HEELED-IN PLANTS NOR PLANTS FROM COLD STORAGE WILL BE ACCEPTED.
- (2) COLLECTED PLANTS OR TRANSPLANTED TREES MAY BE CALLED FOR BY THE LANDSCAPE ARCHITECT AND USED, PROVIDED, HOWEVER, THAT LOCATIONS AND SOIL CONDITIONS WILL PERMIT PROPER BALLING.

(d) PLANT MEASUREMENTS

ALL PLANTS SHALL CONFORM TO THE MEASUREMENTS SPECIFIED IN THE PLANT SCHEDULE.

BMP Specification Issue Date: July 26, 2014

- (1) CALIPER MEASUREMENTS SHALL BE TAKEN SIX (6) INCHES ABOVE GRADE FOR TREES UNDER FOUR (4) INCH CALIPER AND TWELVE (12) INCHES ABOVE GRADE FOR TREES FOUR (4) INCHES CALIPER AND OVER.
- (2) MINIMUM BRANCHING HEIGHT FOR ALL SHADE TREES SHALL BE SIX (6) TO EIGHT (8) FEET.
- (3) MINIMUM SIZE FOR PLANTING SHADE TREES SHALL BE TWO AND ONE HALF TO THREE (2-½-3) INCHES CALIPER, TWELVE TO FOURTEEN (12-14) FEET IN HEIGHT.
- (4) MINIMUM SIZE FOR PLANTING MINOR SHADE TREES SHALL BE TWO AND ONE HALF TO THREE (2 $\frac{1}{2}$ -3) INCHES CALIPER, EIGHT TO TEN FEET (8-10) FEET IN HEIGHT.
- (5) MINIMUM SIZE FOR PLANTING ORNAMENTAL TREES SHALL BE ONE AND A HALF TO ONE AND THREE-FOURTHS (1- ½ -1- ¾) INCHES CALIPER, SEVEN TO NINE (7-9) FEET IN HEIGHT.
- (6) MINIMUM SIZE FOR PLANTING EVERGREEN TREES SHALL BE SIX TO EIGHT (6-8) FEET IN HEIGHT.
- (7) CALIPER, HEIGHT, AND SPREAD SHALL BE GENERALLY AS FOLLOWS:

CALIPER	HEIGHT	SPREAD
2-2-1/2"	12'-14'	6'-8'
2-1/2"-3	12'-14'	6'-8'
3"-3-1/2"	14'-16'	6'-8'
3-1/2"-4"	14'-16'	8'-10
4"-4-1/2"	16'-18'	8'-10'
4-1/2"-5"	16'-18'	10'-12'
5"-5-1/2"	18'-20'	10'-12'
5-1/2"-6"	18'-20'	12'-14'

ALL PLANT MATERIAL SHALL GENERALLY AVERAGE THE MEDIAN FOR THE SIZE RANGES INDICATED ABOVE AND AS INDICATED IN THE ANLA STANDARDS.

(8) MINIMUM SIZE FOR PLANTING SHRUBS SHALL BE, IN GENERAL, EIGHTEEN TO TWENTY-FOUR (18-24) INCHES IN HEIGHT OR SPREAD, AS APPROPRIATE, EXCEPT THAT A LARGER SIZE MAY BE REQUIRED WHEN DEEMED

APPROPRIATE BY THE PLANTING DIRECTOR (OR DESIGNEE) IN THE CASE OF PARTICULAR SPECIES OR PLANTING SITUATIONS.

(e) PLANTING METHODS

ALL PROPOSED PLANT MATERIAL THAT MEETS THE SPECIFICATION IN APPENDIX 4, SECTION (A), PLANT MATERIALS, ARE TO BE PLANTED IN ACCORDANCE WITH THE FOLLOWING PLANTING METHODS DURING THE PROPER SEASONS AS DESCRIBED BELOW.

(1) PLANTING SEASONS

A PROFESSIONAL HORTICULTURALIST/NURSERYMAN SHALL BE CONSULTED TO DETERMINE THE PROPER TIME, BASED ON PLANT SPECIES AND WEATHER CONDITIONS, TO MOVE AND INSTALL PARTICULAR PLANT MATERIAL TO MINIMIZE STRESS TO THE PLANT. PLANTING OF DECIDUOUS MATERIAL MAY BE CONTINUED DURING THE WINTER MONTHS PROVIDED THERE IS NO FROST IN THE GROUND AND FROST-FREE TOP SOIL PLANTING MIXTURES ARE USED.

DIGGING (2)

ALL PLANT MATERIAL SHALL BE DUG, BALLED, AND BURLAPPED OR BARE ROOT IN ACCORDANCE WITH THE AMERICAN STANDARD FOR NURSERY STOCK, AMERICAN NURSERY AND LANDSCAPE ASSOCIATION.

(3) **EXCAVATION OF PLANT PITS**

THE LANDSCAPE CONTRACTOR SHALL EXCAVATE ALL PLANT PITS, VINE PITS, HEDGE TRENCHES AND SHRUB BEDS AS FOLLOWS:

- ALL PITS SHALL BE GENERALLY CIRCULAR IN OUTLINE, WITH BOWL (A) SHAPED SIDES. THE TREE PIT SHALL BE DEEP ENOUGH TO ALLOW ONE-EIGHTH (1/8) OF THE BALL TO BE ABOVE THE EXISTING GRADE. PLANTS SHALL REST ON UNDISTURBED EXISTING SOIL OR WELL-COMPACTED BACKFILL. THE TREE PIT MUST BE A MINIMUM OF NINE (9) INCHES LARGER ON EVERY SIDE THAN THE BALL OF THE TREE.
- (B) IF AREAS ARE DESIGNATED AS SHRUB BEDS OR HEDGE TRENCHES, THEY SHALL BE CULTIVATED TO AT LEAST AN EIGHTEEN (18) INCHES IN DEPTH MINIMUM. AREAS DESIGNATED FOR GROUND COVERS AND VINES SHALL BE CULTIVATED TO AT LEAST TWELVE (12) INCHES IN DEPTH MINIMUM.
- (4) STAKING, GUYING, AND WRAPPING

SEE THE LANDSCAPE SPECIFICATION GUIDELINES.

- (5) PLANT PRUNING, EDGING, AND MULCHING
 - (A) EACH TREE, SHRUB, OR VINE SHALL BE PRUNED IN AN APPROPRIATE MANNER TO ITS PARTICULAR REQUIREMENTS IN ACCORDANCE WITH ACCEPTED STANDARD PRACTICES AS STATED IN ANSI STANDARDS A300 FOR PRUNING. BROKEN OR BRUISED BRANCHES SHALL BE REMOVED WITH CLEAN CUTS MADE ON AN ANGLE FROM THE BARK RIDGE TO THE BRANCH COLLAR, NO FLUSH CUTS, TO MINIMIZE THE AREA CUT. ALL CUTS SHALL BE MADE WITH SHARP TOOLS. TRIM ALL EDGES SMOOTH. NO TREE WOUND DRESSINGS SHALL BE APPLIED.
 - (B) ALL TRENCHES AND SHRUB BEDS SHALL BE EDGED AND CULTIVATED TO THE LINES SHOWN ON THE DRAWING. THE AREAS AROUND ISOLATED PLANTS SHALL BE EDGED AND CULTIVATED TO THE FULL DIAMETER OF THE PIT. SOD THAT HAS BEEN REMOVED AND STACKED SHALL BE USED TO TRIM THE EDGES OF ALL EXCAVATED AREAS TO THE NEAT LINES OF THE PLANT PIT SAUCERS, THE EDGES OF SHRUB AREAS, HEDGE TRENCHES AND VINE POCKETS.
 - (C) AFTER CULTIVATION, ALL PLANT MATERIALS SHALL BE MULCHED WITH A TWO OR THREE (2-3) INCH LAYER OF TAN BARK, PEAT MOSS, OR ANOTHER APPROVED MATERIAL OVER THE ENTIRE AREA OF THE BED OR SAUCER.
- (f) SEEDING AND SODDING

ALL SEEDING AND SODDING SHALL BE AS PER 1994 STANDARDS AND SPECIFICATIONS FOR SOIL EROSION AND SEDIMENT CONTROL OR THE LATEST EDITION.

(g) TOP SOIL

TOP SOIL SHALL BE RETAINED AND/OR PROVIDED ON ALL SITES AND SPREAD OVER ALL UNIMPROVED AREAS.

PLANTING DETAILS

SHALL BE IN ACCORDANCE WITH STANDARD PRACTICES IN THE INDUSTRY.

TREE PRESERVATION MEASURES

FOR MORE INFORMATION ON THIS SUBJECT, CONTACT THE ENVIRONMENTAL PLANNING SECTION, COUNTYWIDE PLANNING DIVISION OF THE MARYLAND-NATIONAL CAPITAL PARK AND PLANNING COMMISSION.

BMP Specification

SUBMERGED GRAVEL WETLAND (SGW) MATERIAL AND CONSTRUCTION SPECIFICATIONS (not finished)

EXCAVATION

1. EXCAVATED MATERIALS SHALL BE PLACED AWAY FROM THE FACILITY SIDES TO AVOID CONTAMINATION AND POSSIBLE SIDEWALL INSTABILITY. LARGE TREE ROOTS MUST BE TRIMMED FLUSH WITH THE SIDEWALLS OF THE TRENCH USING ROOT PRUNING TECHNIQUES AND THE SIDEWALLS ROUGHENED WHERE SHEARED AND SEALED BY HEAVY EQUIPMENT.

SOIL TEXTURE AND STRUCTURE

- 1. TOPSOIL FOR SUBMERGED GRAVEL WETLAND SHALL HAVE A SANDY LOAM, LOAMY SAND, OR LOAM TEXTURE PER USDA TEXTURAL TRIANGLE. NO CLAY CONTENT IS PERMITTED. THE SOIL MEDIA MIXTURE SHALL BE;
 - A. 50-60% SAND;
 - B. 20-30% LEAF MULCH; AND
 - C. 20-30% TOPSOIL.
- 2. THE SOIL SHALL BE 20"-30" DEEP WITH A UNIFORM MIX, FREE OF STONES, STUMPS, ROOTS, OR OTHER SIMILAR OBJECTS LARGER THAN TWO (2) INCHES.
- 3. NO OTHER MATERIALS OR SUBSTANCES SHALL BE MIXED OR DUMPED WITHIN THE SUBMERGED GRAVEL WETLAND THAT MAY BE HARMFUL TO PLANT GROWTH, OR PROVE A HINDRANCE TO THE PLANTING OR MAINTENANCE OPERATIONS.
- 4. THE SOIL MEDIA SHALL BE FREE OF BERMUDA GRASS, QUACK GRASS, JOHNSON GRASS, MUGWORT, NUTSEDGE, POISON IVY, CANADIAN THISTLE, TEARTHUB, OR OTHER NOXIOUS WEEDS.

SOIL TESTING

- 1. THE SOIL SHOULD MEET THE FOLLOWING CRITERIA (LANDSCAPE CONTRACTORS ASSOCIATION, 1986).
 - A. PH RANGE: 5.5-6.5
 - B. ORGANIC MATTER: 1.5-3.0%
 - C. IT IS REQUIRED THAT A SIEVE ANALYSIS, PH, AND ORGANIC MATTER TEST BE PERFORMED FOR EACH SUBMERGED GRAVEL WETLAND AREA.

CHECK DAMS

- 1. ONLY EARTH CHECK DAMS ARE ALLOWED WITH GABION INFLOW PROTECTION AS SHOWN IN DETAIL ??
- 2. THE MAXIMUM SIDE SLOPE IS 3:1.

BMP Specification

- 3. NON-WOVEN GEOTEXTILE FABRIC SHALL MEET:
 - A. ASTM D-6241 (PUNCTURE STRENGTH 450 LB)
 - B. ASTM D-4632 (GRAB TENSILE STRENGTH 200 LB; ELONGATION 50%)
 - C. ASTM D-4533 (TRAPEZOIDAL TEAR STRENGTH 80 LB)
 - D. FABRIC SHALL HAVE US SIEVE 70 APPARENT OPENING SIZE, 1.1/SECOND PERMITTIVITY AND 70% STRENGTH IN TERMS OF ULTRAVIOLET RESISTANCE RETAINED AT 500 HOURS.
- 4. STONE SHALL BE 2 TO 3 INCHES.
- 5. BASKET SHALL BE MADE OF MINIMUM 11 GAUGE WIRE AND ARRANGED AT 4X1X0.5 FOOT SPACING.

SOIL INSTALLATION

- 1. AFTER SCARIFYING THE BOTTOM AREA OF THE PROPOSED FACILITY, PLACE SOIL AT 8"-12" LIFTS. LIFTS ARE NOT TO BE COMPACTED.
- 2. AVOID OVER-COMPACTION BY ALLOWING TIME FOR NATURAL COMPACTION AND SETTLEMENT. ADDITIONAL MANUAL SOIL COMPACTION MUST NOT BE PERFORMED. RAKE SOIL MATERIAL AS NEEDED TO LEVEL OUT. OVERFILL ABOVE THE PROPOSED SURFACE INVERT TO ACCOMMODATE UP TO 20% NATURAL SETTLEMENT TO PROPER GRADE.
- 3. PRESOAKING MAY BE PERFORMED TO HASTEN NATURAL COMPACTION, PREFERABLY BY RAIN EVENTS.

PLANT MATERIALS

- 1. SEED WITH FLOOD/DROUGHT RESISTANT GRASSES, AS INCLUDED IN APPENDIX A, SECTION 2.4 OF THE MDE SWM MANUAL.
- 2. IF PLANT MATERIALS ARE STOCKPILED ON SITE, ROOT BALLS MUST BE KEPT WET TO ENABLE PLANTS' SURVIVAL PRIOR TO INSTALLATION.
- 3. PLANT INSTALLATION SHOULD BE PLANNED TO MINIMIZE ADDITIONAL SOIL COMPACTION BY PERSONS ACCESSING THE BIO-FILTRATION AREA.

MAINTENANCE

1. THE CONTRACTIOR IS RESPONSIBLE FOR WATERING AND MAINTAINING PLANTS DURING THE PLANT ESTABLISHMENT PHASE.

BMP Specification Issue Date: January 20, 2014

WET SWALE MATERIAL AND CONSTRUCTION SPECIFICATIONS

EXCAVATION

2. EXCAVATED MATERIALS SHALL BE PLACED AWAY FROM THE FACILITY SIDES TO AVOID CONTAMINATION AND POSSIBLE SIDEWALL INSTABILITY. LARGE TREE ROOTS MUST BE TRIMMED FLUSH WITH THE SIDEWALLS OF THE TRENCH USING ROOT PRUNING TECHNIQUES AND THE SIDEWALLS ROUGHENED WHERE SHEARED AND SEALED BY HEAVY EQUIPMENT.

SOIL TEXTURE AND STRUCTURE

- 5. TOPSOIL FOR WET SWALE SHALL HAVE A SANDY LOAM, LOAMY SAND, OR LOAM TEXTURE PER USDA TEXTURAL TRIANGLE. NO CLAY CONTENT IS PERMITTED. THE SOIL MEDIA MIXTURE SHALL BE;
 - D. 50-60% SAND;
 - E. 20-30% LEAF MULCH; AND
 - F. 20-30% TOPSOIL.
- 6. THE SOIL SHALL BE 20"- 30" DEEP WITH A UNIFORM MIX, FREE OF STONES, STUMPS, ROOTS, OR OTHER SIMILAR OBJECTS LARGER THAN TWO (2) INCHES.
- 7. NO OTHER MATERIALS OR SUBSTANCES SHALL BE MIXED OR DUMPED WITHIN THE WET SWALE THAT MAY BE HARMFUL TO PLANT GROWTH, OR PROVE A HINDRANCE TO THE PLANTING OR MAINTENANCE OPERATIONS.
- 8. THE SOIL MEDIA SHALL BE FREE OF BERMUDA GRASS, QUACK GRASS, JOHNSON GRASS, MUGWORT, NUTSEDGE, POISON IVY, CANADIAN THISTLE, TEARTHUB, OR OTHER NOXIOUS WEEDS.

SOIL TESTING

- 2. THE SOIL SHOULD MEET THE FOLLOWING CRITERIA (LANDSCAPE CONTRACTORS ASSOCIATION, 1986).
 - D. PH RANGE: 5.5-6.5
 - E. ORGANIC MATTER: 1.5-3.0%
 - F. IT IS REQUIRED THAT A SIEVE ANALYSIS, PH, AND ORGANIC MATTER TEST BE PERFORMED FOR EACH WET SWALE AREA.

CHECK DAMS

- 6. ONLY EARTH CHECK DAMS ARE ALLOWED WITH GABION INFLOW PROTECTION AS SHOWN IN DETAIL ??
- 7. THE MAXIMUM SIDE SLOPE IS 3:1.
- 8. NON-WOVEN GEOTEXTILE FABRIC SHALL MEET:

BMP Specification

- A. ASTM D-6241 (PUNCTURE STRENGTH 450 LB)
- B. ASTM D-4632 (GRAB TENSILE STRENGTH 200 LB; ELONGATION 50%)
- C. ASTM D-4533 (TRAPEZOIDAL TEAR STRENGTH 80 LB)
- D. FABRIC SHALL HAVE US SIEVE 70 APPARENT OPENING SIZE, 1.1/SECOND PERMITTIVITY AND 70% STRENGTH IN TERMS OF ULTRAVIOLET RESISTANCE RETAINED AT 500 HOURS.
- 9. STONE SHALL BE 2 TO 3 INCHES.
- 10. BASKET SHALL BE MADE OF MINIMUM 11 GAUGE WIRE AND ARRANGED AT 4X1X0.5 FOOT SPACING.

SOIL INSTALLATION

- 4. AFTER SCARIFYING THE BOTTOM AREA OF THE PROPOSED FACILITY, PLACE SOIL AT 8"-12" LIFTS. LIFTS ARE NOT TO BE COMPACTED.
- 5. AVOID OVER-COMPACTION BY ALLOWING TIME FOR NATURAL COMPACTION AND SETTLEMENT. ADDITIONAL MANUAL SOIL COMPACTION MUST NOT BE PERFORMED. RAKE SOIL MATERIAL AS NEEDED TO LEVEL OUT. OVERFILL ABOVE THE PROPOSED SURFACE INVERT TO ACCOMMODATE UP TO 20% NATURAL SETTLEMENT TO PROPER GRADE.
- 6. PRESOAKING MAY BE PERFORMED TO HASTEN NATURAL COMPACTION, PREFERABLY BY RAIN EVENTS.

PLANT MATERIALS

- 4. SEED WITH FLOOD/DROUGHT RESISTANT GRASSES, AS INCLUDED IN APPENDIX A, SECTION 2.4 OF THE MDE SWM MANUAL.
- 5. IF PLANT MATERIALS ARE STOCKPILED ON SITE, ROOT BALLS MUST BE KEPT WET TO ENABLE PLANTS' SURVIVAL PRIOR TO INSTALLATION.
- 6. PLANT INSTALLATION SHOULD BE PLANNED TO MINIMIZE ADDITIONAL SOIL COMPACTION BY PERSONS ACCESSING THE BIO-FILTRATION AREA.

MAINTENANCE

2. THE CONTRACTIOR IS RESPONSIBLE FOR WATERING AND MAINTAINING PLANTS DURING THE PLANT ESTABLISHMENT PHASE.

BIORETENTION MATERIAL AND CONSTRUCTION SPECIFICATIONS

TIMING

- 1. A BIORETENTION FACILITY SHALL NOT BE PLACED IN SERVICE UNTIL ALL OF THE CONTRIBUTING DRAINAGE AREA HAS BEEN STABILIZED AND INSTALLATION APPROVED BY THE INSPECTOR. PROVISIONS FOR SEDIMENT CONTROL SHALL BE IN PLACE AS SPECIFIED WITHIN THE SEDIMENT CONTROL PLAN.
- 2. DELIVERY OF MATERIALS SUCH AS SOIL MEDIA, PLANTS, GRAVEL, GEOTEXTILE FABRIC, AND UNDERDRAINS MUST BE COORDINATED TO AVOID STOCKPILING AND CONTAMINATION PROBLEMS. SOIL MEDIA SHOULD NOT BE DELIVERED UNTIL THE BIORETENTION FACILITY LOCATION HAS BEEN EXCAVATED OR GRADED TO THE DESIGN ELEVATIONS WITH THE GEOTEXTILE FABRIC AND UNDERDRAIN SYSTEM IN PLACE. PLANT MATERIALS SHOULD NOT BE DELIVERED UNTIL AFTER THE SOIL MEDIA HAS SETTLED AND BEEN TRIMMED TO THE PROPER GRADE ELEVATION.
- 3. PRIOR TO THE INSTALLATION OF SOIL MEDIA, UNDERDRAIN SYSTEM, GEOTEXTILE FABRIC AND PLANTING MATERIAL, THE COUNTY INSPECTOR MUST APPROVE THAT THE EXCAVATION HAS BEEN PREPARED PROPERLY.

EXCAVATION

3. EXCAVATED MATERIALS SHALL BE PLACED AWAY FROM THE FACILITY SIDES TO AVOID CONTAMINATION AND POSSIBLE SIDEWALL INSTABILITY. LARGE TREE ROOTS MUST BE TRIMMED FLUSH WITH THE SIDEWALLS OF THE TRENCH USING ROOT PRUNING TECHNIQUES AND THE SIDEWALLS ROUGHENED WHERE SHEARED AND SEALED BY HEAVY EQUIPMENT.

SOIL TEXTURE, STRUCTURE, AND PREPARATION

- 9. SOIL MEDIA SHALL MEET THE MSHA SPECIFIVCATIONS 920.01.02 AND SHALL HAVE A SANDY LOAM, LOAMY SAND, OR LOAM TEXTURE PER USDA TEXTURAL TRIANGLE.
- 10. THE SOIL SHALL BE A UNIFORM MIX, FREE OF STONES, STUMPS, ROOTS, OR OTHER SIMILAR OBJECTS LARGER THAN TWO (2) INCHES.
- 11. NO OTHER MATERIALS OR SUBSTANCES SHALL BE MIXED OR DUMPED WITHIN THE BIORETENTION THAT MAY BE HARMFUL TO PLANT GROWTH, OR PROVE A HINDRANCE TO THE PLANTING OR MAINTENANCE OPERATIONS.
- 12. THE SOIL MEDIA SHALL BE FREE OF BERMUDA GRASS, QUACK GRASS, JOHNSON GRASS, MUGWORT, NUTSEDGE, POISON IVY, CANADIAN THISTLE, TEARTHUB, OR OTHER NOXIOUS WEEDS.

BMP Specification Issue Date: January 20, 2014

- 13. THE SOIL MEDIA FOR BIORETENTION AREAS MUST BE TESTED PRIOR TO INSTALLATION FOR NUTRIENTS, PH AND ORGANIC MATTER. A SHOP DRAWING REVIEW AND APPROVAL OF THE SOIL MIX SHALL BE PROVIDED TO THE COUNTY SITE/ROAD INSPECTOR. THE SOIL SAMPLE MUST BE CERTIFIED AS MEETING THE CRITERIA ESTABLISHED FOR THE SOIL MEDIA
- 14. INSUTU SOIL USED FOR BIORETENTION MUST ALSO BE PREPARED. SCARIFICATION OF SOIL SURFACES BY MANUALLY RAKING TO AERATE AND REDUCING SOIL COMPACTION IS RECOMMENDED.
- 15. SOIL MEDIA THAT DOES NOT CONFORM TO COMPOSITION REQUIREMENTS FOR PH OR NUTRIENT ANALYSIS SHALL BE AMENDED AS SPECIFIED BY THE NMP. SOIL MEDIA THAT EXCEEDS MAXIMUM PHOSPHORUS CONCENTRATION OR FAILS OTHER COMPOSITION REQUIREMENTS WILL NOT BE ACCEPTED, AND SHALL NOT BE DELIVERED OR USED AS SOIL MEDIA.
- 16. SOIL MEDIA SHALL BE STORED IN A STOCKPILE THAT IS PROTECTED FROM WEATHER UNDER TARP OR SHED. BSM STORED FOR 6 MONTHS OR LONGER SHALL BE RESAMPLED, RETESTED, AND REAPPROVED BEFORE USE.

SOIL TESTING

UNDERDRAINS AND FILTER MATERIALS

- 1. UNDERDRAIN PIPE JOINTS AND STORM DRAIN STRUCTURE CONNECTIONS MUST BE ADEQUATELY SEALED TO AVOID PIPING CONDITIONS. PIPE SECTIONS SHALL BE COUPLED USING SUITABLE CONNECTION RINGS, GASKETS, AND FLANGES. FIELD CONNECTIONS TO STORM DRAIN STRUCTURES AND PIPES SHALL BE SEALED WITH POLYMER GROUT MATERIAL THAT IS CAPABLE OF ADHERING TO SURFACES. UNDERDRAIN PIPE SHALL BE CAPPED (AT STRUCTURE) UNTIL COMPLETION OF SITE.
- 2. UNDERDRAIN PIPES MUST NOT BE WRAPPED IN FILTER FABRIC.
- 3. DURING GRAVEL BED INSTALLATION, GRAVEL SHALL BE SPILLED DIRECTLY OVER UNDERDRAIN AND SPREAD MANUALLY.

GEOTEXTILE SPECIFICATIONS

- 11. GEOTEXTILE FABRIC SHALL MEET:
 - A. ASTM D-751 (PUNCTURE STRENGTH 125 LB)
 - B. ASTM D-1117 (MULLEN BURST STRENGTH 400 PSI)

BMP Specification

- C. ASTM D-1682 (TENSILE STRENGTH 300 LB)
- D. FABRIC SHALL HAVE 0.08" THICK E.O.S.OF#80 SIEVE, AND MAINTAIN 125 GPM PER SQ. FT. FLOW RATE.

SAND AND GRAVEL SPECIFICATIONS

- 1. UNDERDRAIN GRAVEL SHALL MEET MSHA TABLE 901A FOR NO. 57 STONE. PEA GRAVEL SHALL MEET SIZE 7 FROM MSHA TABLE 901A
- 2. PROVIDE CLEAN SAND, FREE OF DELETERIOUS MATERIALS. SAND SHALL MEET MSHA TABLE 901A FOR "FINE AGGRAGATE/LIGHTWEIGHT PORTLAND CEMENT CONCRETE. MANUFACTURED SAND IS NOT ACCEPTABLE.

SOIL INSTALLATION

- 7. AFTER SCARIFYING THE BOTTOM AREA OF THE PROPOSED FACILITY, PLACE SOIL AT 8"-12" LIFTS. LIFTS ARE NOT TO BE COMPACTED.
- 8. AVOID OVER-COMPACTION BY ALLOWING TIME FOR NATURAL COMPACTION AND SETTLEMENT. ADDITIONAL MANUAL SOIL COMPACTION MUST NOT BE PERFORMED. RAKE SOIL MATERIAL AS NEEDED TO LEVEL OUT. OVERFILL ABOVE THE PROPOSED SURFACE INVERT TO ACCOMMODATE UP TO 20% NATURAL SETTLEMENT TO PROPER GRADE.
- 9. PRESOAKING MAY BE PERFORMED TO HASTEN NATURAL COMPACTION, PREFERABLY BY RAIN EVENTS.
- 10. CONSTRUCTION ACTIVITIES MUST BE PLANNED SUCH THAT EQUIPMENT DOES NOT CROSS THE BIORETENTION AREA FOLLOWING SOIL INSTALLATION.
- 11. CONTRACTOR SHALL ARRANGE FOR AS-BUILT SURVEY PRIOR TO LANDSCAPE INSTALATION AND FINAL MULCHING OF AREA.

PLANT MATERIALS

- 7. IF PLANT MATERIALS ARE STOCKPILED ON SITE, ROOT BALLS MUST BE KEPT WET TO ENABLE PLANTS' SURVIVAL PRIOR TO INSTALLATION.
- 8. PLANT INSTALLATION SHOULD BE PLANNED TO MINIMIZE ADDITIONAL SOIL COMPACTION BY PERSONS ACCESSING THE BIORETENTION AREA.
- 9. SOD FOR SIDE SLOPES SHALL BE PLACED PRIOR TO FINAL MULCH INSTALLATION.

MULCH INSTALLATION

1. ACCEPTABLE MULCH SHALL BE SHREDDED HARDWOOD ONLY. MULCH MUST BE WELL AGED, UNIFORM IN COLOR, AND FREE OF FOREIGN MATERIAL INCLUDING

BMP Specification

- PLANT MATERIAL. WELL AGED MULCH IS DEFINED AS MULCH THAT HAS BEEN STOCKPILED OR STORED FOR AT LEAST TWELVE (12) MONTHS.
- 2. MULCH SHALL BE PLACED AFTER TREES, SHRUBS, GROUNDCOVER, SOD, ETC. HAS BEEN INSTALLED. VEGETATION SHOULD BE PROTECTED AND LIFTED TO PLACE MULCH UNDERNEATH AND BETWEEN PLANTINGS.

MAINTENANCE

3. THE CONTRACTIOR IS RESPONSIBLE FOR WATERING AND MAINTAINING PLANTS DURING THE PLANT ESTABLISHMENT PHASE.

DRY WELL MATERIAL AND CONSTRUCTION SPECIFICATIONS

EXCAVATION

4. EXCAVATED MATERIALS SHALL BE PLACED AWAY FROM THE FACILITY SIDES TO AVOID CONTAMINATION AND POSSIBLE SIDEWALL INSTABILITY. LARGE TREE ROOTS MUST BE TRIMMED FLUSH WITH THE SIDEWALLS OF THE TRENCH USING ROOT PRUNING TECHNIQUES AND THE SIDEWALLS ROUGHENED WHERE SHEARED AND SEALED BY HEAVY EQUIPMENT.

UNDERDRAINS AND CLEANOUTS

- 4. RUNOFF SHALL ENTER THE DRY WELL VIA MINIMUM 4 INCH DIAMETER SCHEDULE 40 PVC DOWNSPOUT PIPING OR STRONGER. PIPE MUST BE SOLID FOR FIRST 6 INCHES AFTER THE PIPE ENTERS THE DRY WELL. PERFORATIONS MUST BE 3/8 INCH IN DIAMETER AND MUST BE LOCATED 4 INCHES ON CENTER, EVERY 90 DEGREES AROUND THE PIPE. UNDERDRAIN PIPES MUST NOT BE WRAPPED IN FILTER FABRIC. AN ACCEPTABLE ALTERNATIVE TO PERFORATED PIPE IS 6" DIAMETER SCHEDULE 40 SLOTTED PVC PIPE WITH 0.125 INCH SLOTS. SLOTS SHALL BE 0.125 INCHES WIDE AND A MINIMUM OF 1.9 INCHES IN LENGTH, WITH A MINIMUM OF 4 SLOTS PER ROW AND 4 ROWS PER LINEAR FOOT OF PIPE. THE UNDERDRAIN MUST BE FITTED WITH A REMOVABLE CAP. THIS CAP MUST BE PERFORATED WITH SEVEN(7) 3/8" HOLES
- 5. UNDERDRAIN PIPE JOINTS AND STORM DRAIN STRUCTURE CONNECTIONS MUST BE ADEQUATELY SEALED TO AVOID PIPING CONDITIONS. PIPE SECTIONS SHALL BE COUPLED USING SUITABLE CONNECTION RINGS, GASKETS, AND FLANGES. FIELD CONNECTIONS TO STORM DRAIN STRUCTURES AND PIPES SHALL BE SEALED WITH POLYMER GROUT MATERIAL THAT IS CAPABLE OF ADHERING TO SURFACES. UNDERDRAIN PIPE SHALL BE CAPPED (AT STRUCTURE) UNTIL COMPLETION OF SITE.
- 6. ACCESS FOR CLEANING ALL UNDERDRAIN PIPING IS NEEDED. WATERTIGHT CLEAN-OUTS FOR EACH PIPE SHALL BE LEVEL WITH THE SURFACE OF THE MEDIA. ALL CLEANOUTS SHALL HAVE A REMOVABLE WATERPROOF CAP. CLEANOUTS MUST BE CAPPED IMMEDIATELY AFTER FILTER MEDIA IS IN PLACE.

FILTER STONE AND SAND BED

- 1. DRY WELLS SHALL BE FILLED WITH CLEAN 1.5-3.0 INCH DIAMETER STONE MEETING ASTM D448, SIZE NO. 1. GEOTEXTILE FABRIC SHALL BE PLACED ON THE TOP AND SIDES OF THE FACILITY. NO GEOTEXTILE IS ALLOWED TO BE PLACED ON THE BOTTOM OF THE FACILITY OR IN ANY OTHER LOCATION NOT CALLED FOR SPECIFICALLY ON THE DESIGN DETAIL.
- 2. A 12-INCH LAYER OF FINE AGGREGATE SAND SHALL BE PROVIDED AT THE

BMP Specification Issue Date: January 20, 2014 BOTTOM OF THE EXCAVATION WITH CLEAN ASTM C33 OR AASHTO M6 FINE AGGREGATE CONCRETE SAND.

GEOTEXTILE SPECIFICATIONS

- 12. GEOTEXTILE FABRIC SHALL MEET:
 - A. ASTM D-751 (PUNCTURE STRENGTH 125 LB)
 - B. ASTM D-1117 (MULLEN BURST STRENGTH 400 PSI)
 - C. ASTM D-1682 (TENSILE STRENGTH 300 LB)
 - D. FABRIC SHALL HAVE 0.08" THICK E.O.S.OF#80 SIEVE, AND MAINTAIN 125 GPM PER SQ. FT. FLOW RATE.
- 13. NO GEOTEXTILE OR FILTER FABRIC IS ALLOWED TO BE PLACED HORIZONTALLY ANYWHERE WITHIN THE FILTER MEDIA.


MAINTENANCE

4. THE CONTRACTIOR IS RESPONSIBLE FOR KEEPING THE DRYWELL AREA CLEAN AND FREE OF SEDIMENT DURING THE CONSTRUCTION PHASE.

EASEMENT PROCESSING FLOW CHART

To Be Provided Later


EASEMENT WIDTH FOR MULTIPLE PIPES



NOTES:

- 1. SINCE THE DEPTH OF THE PIPE IS VARIABLE, THE EASEMENT SIZE DETERMINATION WILL BE BASED ON THE HIGHEST COVER PIPE.
- 2. FOR STORM DRAIN PIPE THAT IS DESIGNED DEEPER THAN 8 FEET DEPTH, ADD 2 FEET FOR EVERY FOOT DROP TO THE EASEMENT REQUIREMENT.
- 3. FOR ELLIPTICAL PIPE, USE THE EQUIVALENT ROUND PIPE STANDARD EASEMENT REQUIREMENT.
- 4. THIS DETAIL IS NOT APPLICABLE TO MD-378 POND OUTFALLS.

CHANNEL/SWALE EASEMENT WIDTH



CHANNEL / SWALE EASEMENT WIDTH

* Based on a 10-year storm and 6" freeboard

BLOCK EASEMENT SKETCH ALONG PUBLIC R/W

To be provided later

COUNTY BOILER PLATE EASEMENT LANGUAGE

- 1. Storm Drain and SWM
- 2. Floodplain
- 3. Grading
- 4. Conservation
- 5. Ingress- Egress
- 6. Public Utility Easement (L F)

To Be Provided Later

RIGHT-OF-WAY SURVEY TRANSMITTAL



PRINCE GEORGE'S COUNTY GOVERNMENT

Department of Permitting, Inspections and Enforcement (301) 636-2060



RIGHTS-OF-WAY SURVEY TRANSMITTAL (for submittal and processing of easements and deeds)

Name of Project:	Date Submitted:
Name of Street: (For Street Dedication)	
SD #:	200' Sheet No.:
DPIE Permit #:	Subdivision:
DPIE District Engr:	Lot(s):
Election District:	Block(s):
Tax Account #:	Plat Reference:
Tax Map:	Tax Grid:
Parcel:	IMPORTANT: Provide document which confirms the organization, signatory, and title.
Owner/Grantor:	organically and another the second
Signatory:	Title/Capacity:
Name, Address to where document is to be mailed for signatur (includephone number, email address for contact):	re or instructions for method of delivery
For Signature Send to:	Telephone #:
Address:	Email Address:
City/State/Zip:	
General:	9
Total Number of R/W's Included in this Submission/Tr	ansmittal:
On-SiteOff-site	Total
Total Number of R/W's Transmitted (Per Grantor)	
Number of On-site R/W's Transmitted H	erewith
(Parts if Applicable)	
Number of Off-site R/W's Transmitted H	ferewith
(Parts if Applicable)	
NOTE: ALL RIGHTS-OF-WAY SHALL BE PROVIDED	GRATIS TO PRINCE GEORGE'S COUNTY.
Submitted/Prepared By:	
Concultant Name	Contact Person:

Kignt-or-vvay Survey 1 ransmittal Issue Date: July 26, 2014

SAMPLE SECURITY FORMS

- 1. Sample Performance Bond
- 2. Labor and Materials Bond
- 3. Bond Instruction
- 4. Sample Certified Release of Lien Form
- 5. Certified List of Contractors, Supplies, and Material man





Prince George's County

Department of Permitting, Inspections and Enforcement

Site/Road Permit Processing Unit Performance Bond No. -PB Case Number:

Case Number:	DATE:
for construction in Subdivision/Case Name:	
KNOW ALL MEN BY THESE PRESENTS TH. As a condition precedent to the approval and/or issuance of	AT: of the above application/permit (the "Permit"), PERMITTEE
hereby binds itself and its successors and assigns, to pay to dollars,	Prince George's County, Maryland (the "County") the full amount of
$\boldsymbol{0}$, subject to the conditions stated below. To secure said in the full amount of this Bond:	payment, Permittee has provided the County with the following security
Irrevocable Letter of Credit No	from
	3000
Surety Bond No	
	from
Cash, County to hold in non-interest esca	
	from the Requirements listed below in a manner satisfactory to the County, this Bond
by the Permit. 4. Provide and maintain Security in full force and effective fails to satisfy any of the above Requirem full amount thereof unless Permittee promptly completes, a applicable, posts substitute Security. If the Permittee after Security less the amount of any claims, damages or costs in If payment is not made within thirty (30) days, Permitt (10%) per annum. If suit is filed to collect on this Bond or fees at the rate of \$60 per hour (subject to change).	fect until all work under the Permit has been accepted by the County ents, the County shall enforce this Bond and draw upon the Security for up to the und has accepted by the County, all work required under the Permit, or, when rewards completes the work as required, the County shall return the amount of the neutred by the County in connection with this Bond. tee shall pay interest on the unpaid amount of the demand at the rate of ten percent the Security, Permittee shall pay the costs of the collection, including attorney's binds itself and its in accordance with and subject to the terms and conditions set forth above.
SIGNED AND SEALED on the date set forth ab	
	PERMITTEE:
WATENDOO	BY:
WITNESS	DATE:SIGNATURE AND TITLE
	SURETY:
WITNESS	BY:
	(Attorney-in-Fact)
A DDD OVED.	AGENCY NAME:
APPROVED:	
	Cartification/License No
DEPARTMENT DIRECTOR	Certification/License No Counter-signed by Maryland Resident Agent
	(If required by Maryland Resident Agent
COUNTY ATTORNEY	
	WLEDGEMENT
State of	County of
On thisday of20	, before me, a Notary Public of the State and County aforesaid,
personally appearedthe	,who acknowledged that he/she isof the Permittee identified in the above Bond and that being so authorized ,
he/she executed the above Bond for and on behalf of the I	Permittee.
My Commission expires:	Notary Public



PRINCE GEORGE'S COUNTY, MARYLAND DEPARTMENT OF PUBLIC WORKS AND TRANSPORTATION LABOR & MATERIALMAN'S BOND NO.



Case Number: DATE: for construction in Subdivision/Case Name: KNOW ALL MEN BY THESE PRESENTS THAT: As a condition precedent to the approval and/or issuance of the above application/permit (the "Permit"), PERMITTEE hereby binds itself and its successors and assigns, to pay to Prince George's County, Maryland (the "County") the full amount of (), subject to the conditions stated below. To secure said payment, Permittee has provided the County with the following security in the full amount of this Bond: Irrevocable Letter of Credit No ._____ from _____ Assignment of Funds with Surety Bond No. _ Assignment of Account No. from Cash, County to hold in non-interest escrow Certificate of Guaranty No. _____ from _____ Certificate of Deposit No. The condition of this Bond is that if Permittee fulfills the Requirements listed below in a manner satisfactory to the County, this Bond shall be discharged, but otherwise it shall remain in full force and effect . 1. Comply with all requirements of the Prince George's County Code, including all applicable statutes, provisions and code sections. 2. Promptly make payment to all persons supplying labor and materials, including lessors of the equipment to the extent of the fair rental value thereof, for all work under the Permit, which includes the application, plans and specifications, as approved by the County. 3. Provide and maintain Security in full force and effect until all work under the Permit has been accepted by the County and for one calendar year thereafter or until all claims against the Bond have been resolved, whichever is the later, unless the Permittee earlier provides proof satisfactory to the County of payment of all its obligations for labor and materials set forth above . 4. Indemnify the County against all costs, claims and damages asserted against or incurred by the County in connection with this Bond. If Permittee fails to satisfy any of the above Requirements, the County shall enforce this Bond and draw upon the Security for up to the full amount thereof unless Permittee promptly provides the County substitute Security or proves to the County that Permittee has satisfied all Requirements. In making a demand under this Bond, the County shall not thereby incur any liability to satisfy the Requirements except in regard to proven claims on the Bond. Upon satisfaction or discharge of all claims under this Bond and reimbursement of any costs incurred in connection with this Bond, the County shall return any remaining funds to the Permittee . If payment is not made within thirty (30) days, Permittee shall pay interest on the unpaid amount of the demand at the rate of ten percent (10%) per annum. If suit is filed to collect on this Bond or the Security, Permittee shall pay the costs of the collection, including attorney's fees at the rate of \$60 per hour (subject to change). binds itself and its successors and assigns to pay the full amount of this Bond in accordance with and subject to the tems and conditions set forth above. SIGNED AND SEALED on the date set forth above. PERMITTEE: BY: WITNESS SIGNATURE AND TITLE DATE: SURETY: WITNESS (Attorney-in-Fact) AGENCY NAME:____ ADDRESS: APPROVED: Certification/License No. DEPARTMENT DIRECTOR Counter-signed by Maryland Resident Agent (If required by Maryland law) **COUNTY ATTORNEY** ACKNOWLEDGEMENT , before me, a Notary Public of the State and County aforesaid, On this day of ,who acknowledged that he/she is personally appeared of the Permittee identified in the above Bond and that being so authorized, he/she executed the above Bond for and on behalf of the Permittee. My Commission expires:

Notary Public



THE PRINCE GEORGE'S COUNTY GOVERNMENT

Department of Permitting, Inspections and Enforcement Permitting & Licensing Division



BOND FORM INSTRUCTIONS

GENERAL INSTRUCTIONS

- 1. The permittee must execute/post ALL bonds.
- 2. All cash bond refunds will be returned to the permittee listed on the permit.
- 3. Do not use white out when making corrections to the bond form. Instead, "XXXX" out and have appropriate person initial the corrections.
- 4. All bond forms must be <u>originals</u> (le: must remain in legal size 8 ½ x 14, must have original signatures and no alterations to the document will be permitted) and submitted in triplicate.
- 5. Upon completion of the bond form, bonds should be returned to the department issuing the permit and not the Office of Law.
- 6. Inquiries regarding whether a bond has been approved or rejected should be directed to the agency it was submitted to, not the Office of Law.

FILLING OUT THE BOND FORM

PLEASE read the following instructions carefully

As YOU, the permittee, are ultimately responsible for your bond being accepted as legally sufficient.

- 1. Date in upper right hand corner of bond should be filled in. This is the bond date.
- 2. Application/Permit Number should be listed.
- Name of subdivision or street address must be filled in for the Department of Permitting Inspections and Enforcement (DPIE) bonds. If the bond is for the Department of Environmental Resources (DER), provide subdivision's name, the street address and, if known, city, state, and zip code.
- 4. In the blank that follows "Permittee", permittee's name and address must be filled in. **Remember to also Indicate permittee's type of entity (e.g. owner, partnership/corporation).**
 - a) If the permittee is an individual trading as a corporation, please indicate using the following form: John Doe t/a Mechanical, Inc.
 - b) If the permittee is a corporation or L.L.C. with a non-Maryland address on the bond form, provide a copy of the corporation's Certificate of Authority to do business in Maryland. A copy of this certificate can be obtained from the State Department of Assessments and Taxation (SDAT) located at 301 West Preston Street,

Baltimore, MD 21201. (The telephone number is (410) 225-1340.) The certificate cannot be more than six (6) months older than the bond.

- 5. Dollar amount of bond must be written out and numerically listed. These two figures must agree.
- 6. Type of security must be checked off and filled out.
- 7. The permittee name must be the same as the name on the application and/or on the permittee signature line.
- 8. All signatures must be originals.
- 9. In the space provided, indicate permittee; also, affix signature and print the name of the signatory, their title, and the date signed (this date must be the same as or after the bond date). If the Permittee is a business entity, the type of entity must be clearly indicated on the form; (i.e., partnership, corporation).
 - a) If permittee is a corporation, then President or Vice-President must sign. The corporation must provide documentation (such as a board resolution) that the designated officer has actual authority to bind the corporation.
 - b) If permittee is a partnership, then the general or managing partner must sign.
 - c) If the general/managing partner is a corporation, please indicate this fact and have the President or Vice-President sign on behalf of the corporation. In this case, the title would read, for example, "President of the General Partner X Corporation."
 - d) If permittee is the owner, then the owner himself signs the bond; his title is "owner."
 - e) If permittee is a limited liability company ("L.L.C."), then provide documentation to indicate that the signatory has the ability to bind the limited liability company, such as the articles of organization, Resolutions of the Members, and the operating agreement and any amendments, if any.
 - f) Plus provide an original statement signed by all of the members of the L.L.C. stating that "the articles of organization and the operating agreement were entered into on blank date. That there have been no amendments if true, if not then state all of the amendments and the dates the amendments were passed and that the articles of organization and that the operating agreement remain in full force and effect." This statement must be dated the bond date or after, but not before the bond date.
 - g) If the Limited Liability Company submitting the bond is a subsidiary of multiple-level entities that are LLCs, applicant must provide an organization chart that discloses the ownership structure for at least three levels, if applicable, and proof that each separate entity is duly incorporated and in good standing, and proof that the declared authorized agent for each entity is vested with actual authority by all of the members of that particular entity to act on behalf of the respective LLC. If the authorizing agent of the LLC is a Corporation, applicant must provide documentation that the officer has actual authority to act on behalf of the parent corporation.
 - h) If permittee is a close corporation, supply a copy of the statement of election which is in either the articles of incorporation or an amendment to the corporation's charter. The statement of election must identify the individual with actual authority to bind the corporation. The permittee's Certificate of Good Standing must also expressly reference a designation of close corporation.
- 10. The witness shall sign as to the permittee's signature. This Witness cannot be the same person who signs the acknowledgement.

- 11. Acknowledgement must be completed by a Notary Public indicating:
 - a) State and County where notary is commissioned.
 - b) Day, month, and year (this date must be same or later date than permittee's signature).
 - c) Permittee's name and title.
 - d) Notary's signature, seal, and date of commission's expiration.
- 12. Submit bond for the appropriate Department Director's signature at that department.

BOND TYPES

LETTER OF CREDIT

- Fill in Letter of Credit number.
- · Fill in name of financial institution.
- Letter of Credit date must be prior to or the same as the bond date.
- A least one original and two copies of the Letter of Credit must be submitted.
- · Bond number must be included in the Letter of Credit.
- Permit Number must be included in the Letter of Credit.
- Permittee's address must be the same on the Bond application form and the Letter of Credit.

(Letter of Credit must be issued by a financial institution approved by the Prince George's County Office of Law and Office of Finance. Financial institutions will prepare Letters of Credit on bank's letterhead in accordance with format and requirements previously approved by the Prince George's County Office of Law. All approved financial institutions possess copies of the appropriate format.)

ASSIGNMENT OF ACCOUNT/FUNDS

- Fill In Assignment of Account/Funds number.
- Fill in name of financial institution.
- Assignment of Account/Funds form must be dated the same date as or prior to the bond date.
- At least one original and two copies of the Assignment of Account/Funds forms must be submitted.

(See attached instructions for completion of Assignment of Account/Funds form. These forms are available upon request from the appropriate permit office.)

SURETY

- Indicate surety bond number
- Indicate surety (insurance) company in the space provided in the last paragraph on the bond form.
- Authorized attorney-in-fact must sign in space provided on the bond form and print his/her name underneath the signature. (The authorized attorney-in-fact is any of the named persons on the Power of Attorney certificate provided by your bonding company.)

- Witness must sign as to attorney-in-fact's signature.
- Agency's name, address and certifications/license number of agent must also be furnished.
- If required by Maryland law, the Maryland resident agent must sign in the space provided for counter-signature.
- Surety (insurance) company must furnish at least one (1) original power of attorney certificate for each bond (i.e., Performance Bond and Labor & Materialman's Bond) and two (2) copies.
- Power of Attorney certificate must be dated the same as the bond date.
- Surety number must be included on the Power of Attorney certificate.
- Surety (Insurance) company must include a copy of surety's certificate of authority to do business in Maryland with each bond document. This certificate must be current and is good for one (1) year.

CASH

• Prepare the same as other bonds using instructions, Part II – 1-5 and 7-10. Items (a), (b), and (c) are not related to cash bonds. Check or money order is to be made out to Prince George's County, Maryland for the amount of the bond. Check must be from the permittee listed on the permit. If the bond amount is paid with cash, the bond will be refunded to the permittee after work is complete.

INSTRUCTIONS FOR COMPLETION OF ASSIGNMENT OF ACCOUNT/FUNDS

- 1. Fill in appropriate date.
- 2. Fill in permit number.
- 3. Fill in appropriate account number.
- 4. Fill in appropriate bond amount.
- 5. President or Vice-President of financial institution must sign form and indicate title.
- 6. Fill in bank name and address.
- 7. Permittee must sign form and indicate title.
- 8. Witness (es) must sign as to both signatures. The witness (es) cannot be the same person (s) who signs the acknowledgement.
- 9. Acknowledgement date must be same as assignment of account date.
- 10. Acknowledgement as to each individual's signature must be completed by notary public.
- 11. The contractor on this form means the permittee.

ASSIGNMENT OF ACCOUNT/FUNDS FUNDS FORMS ARE AVAILABLE AT PERMITS OFFICE UPON REQUEST.

PARTNERSHIPS and PERFORMANCE/LABOR BONDS

Limited Partnership (LP)


In limited partnerships (LPs), at least one of the owners is considered a "general" partner who makes business decisions and is personally liable for business debts. General or Managing Partner must sign on behalf of permittee partnership. Indicate relationship on the title line. Should general or managing partner be a corporation, please have president or vice president of corporation sign. Indicate such a relationship on title line. Provide copy of partnership agreement.

Limited Liability Partnership (LLP)

Each member of an LLP is an agent for that LLP and can bind that LLP, except in limited circumstances. LLP member must sign on behalf of permittee partnership and indicate relationship on title line. Provide copy of partnership agreement.



THE PRINCE GEORGE'S COUNTY GOVERNMENT





CERTIFIED RELEASE OF LIENS

(PLEASE COMPLETE AND RETURN TO ADDRESS BELOW)

Re:Subdivision							
Permit Number:							
Gentlemen:							
This is to certify that I/we,							
did provide the following work on the above referenced permit:							
(Check Appropriate Items)							
Excavation Bituminous Base Entrance Driveway							
Sediment Control Bituminous Surface Storm Drainage							
Gravel Base Concrete Work Landscaping							
Other Work: (describe work performed)							
I/We have been paid in full and there are no outstanding							
claims; liens, or unpaid bills for any of the work contracted							
for/by							
(Name of Permittee)							
I/We hereby release and waive any and all rights, claims,							
liens and damages arising in any manner in connection with the							
project.							
Name of Contractor/Supplier							
Witness Signature and Title							
Date: Date:							



THE PRINCE GEORGE'S COUNTY GOVERNMENT

Department of Permitting, Inspections and Enforcement Permitting & Licensing Division



CERTIFIED LIST OF CONTRACTORS, SUPPLIERS, AND MATERIALMAN

(PLEASE COMPLETE AND RETURN TO ADDRESS BELOW)

DATE:	
PROJECT/SUBDIVISION:	
PERMIT NUMBER:	* * *;
PERMITTEE:	
contractors, suppliers and mat were utilized on the above re	, the permittee, hereby ist is inclusive of all of the erialmen contracted by me/us that eferenced project under the above all have been paid in full in conditions of their contract:
1, 2, 3, 4, 5, 6, 7, 8, 9, 10, 11, 12, 13,	
VITNESS	PERMITTEE
NOTARY	
SUBSCRIBED AND SWORN BEFORE, 20	ME THIS DAY OF
AV COMMISSION EYDIDES.	NOTARY PUBLIC

SAMPLE CONSTRUCTION COST ESTIMATE

DEPARTMENT OF PERMITTING, INSPECTIONS AND ENFORCEMENT (DPIE) APPLICATION/PERMIT FEE AND BOND CALCULATION WORKSHEET



Case Name:				Case/Permit#			
Permit Type: SI	TE DEVELOPMENT - FINE GRADING			Prepared by:	MT_	Date:	July 20, 2014
				FEE AMOUNTS			BOND AMOUNTS
Street Constructi	on (Grading, SD, Paving, Etc. within the R/ Estimated Cost =		1	Fee = 10% of Cost \$73,731.91	i.		PB = 125% of Cost \$921.648.89
	emporary Entrance Permit efer to Fee Schedule			\$0.00			\$0.00
	Disturbed Area (Ac)						
Note: 0.00	6¢ per sf for a portion of an acre Whole Area	Partial Area					PB = 12¢ per sf
	9	0.17		\$1,638.20			\$47,933.42
			Full Permit Fee	\$75.370.11			
	al Capital Park & Planning Commission Fe	e	\$5.00				
Street Name Sign	Number of Signs Fee = \$228.94/ Sign(s)	1		\$228.94			
Special Utility fee							
	Administrative Fee Length of Longitudinal Cut (LF) Number of Lateral Cuts Length of Lateral Cuts > 75 (LF)	47 0 0	\$300.00 \$94.00 \$0.00 \$0.00				
Note: \$150)/ lateral cut or \$2/ LF if longer than 75 LF			\$394.00			
P	53/LF Public or \$1.50/LF Private) ublic System (LF) 1413 rivate System (LF) 0		TOTAL	\$4,239,00 \$0.00 \$4,239,00			
Note: SD ir	ncludes any pipes for SWM Pond outfalls		10111	y WATER STORY			
E	stimated SD Construction Cost stimated Pond Construction Cost - New stimated Pond Construction Cost - Retrofit	1) 2) 3)	\$24,807.47 \$0.00 \$0.00				PB = 125% of Cost
Total Cost	of SD/ SWM Construction = 1) + 2) + 3)		\$24.807.47				\$31,009.34
SWM Fee-In-Lieu Note: Refe	Site Concept No.: 44738- er to SWM Concept Approval Letter	-2005-01		\$6,500.00			
Street Construct Note: Inclu	ion Fee-In-Lieu udes Developer's Contribution						
Tree Preservation Note: Refe	on Fee er to approved TCP-2 Plan			\$0.00			\$0.00
	Criteria Area (CBCA) Reforestation Ee er to approved CBCA Plan			\$0.00			\$0.00
	i ce Fee Estimated Cost of Construction 6 of construction or \$10,000 minimum. No Pr	\$0.00 rivate Acilities		\$0.00			
Floodplain Revie	ew Fee			\$0.00			
	No L&M Bond required for On-site grading on .&M equals 40% of Performance Bond if Stre			Total Performa	nce Bond	(PB)	\$1.000,600.00
h	as on-site grading &M equals 50% of Construction estimate if		n only	Labor & Materi	als Bond		\$400,250.00

DEPARTMENT OF PERMITTING, INSPECTIONS AND ENFORCEMENT (DPIE) APPLICATION/PERMIT FEE AND BOND CALCULATION WORKSHEET

	-
DPI	F
DEPARTMENT OF PER	MITTING.

Case Name:		Case/Permit#			CALCULATION OF THE PARTY OF THE	_
Permit Type:	SITE DEVELOPMENT - HNE GRADING	Prepared by:	MT	Date:	July 20, 2014	

ADDITIONAL PERMIT COMMENTS

- 1. SC NO.
- 2. Concept No.
- 3. Project Impervious Area = 13.3 Ac

REV. DATE:

2/4/2014

PROJECT NAME:

PREPARED BY:

Site Development Permit #

TOTAL FILING AND REVIEW FEES FOR SD & PAVING

Filing fee for Storm Drain & Paving Permit (3.3% of the cost estimate) (Sheet 2)	\$24,577
Filing fee for Grading (Sheet 6)	\$940
Total Fees	\$25,517

COST ESTIMATE (ROW)

DATE: 02/04/2014 PROJECT NAME:

APPLICATION/Permit

Item No.	ITEM DESCRIPTION	CRIPTION QUANTITY UNIT UNIT COST CO		ITEM DESCRIPTION QUANTITY UNIT UNIT		JANTITY UNIT UNIT COST	
4040	MISCELLANEOUS - LIGHTING	4	EA	\$ 15,000.00	\$60,000.00		
1010	RELOCATE UTILITY POLE	9	EA	\$ 1,450.00	\$13,050.00		
1013 1016	STREET LIGHT COLONIAL POST STREET LIGHT W/ CUT-OFF OPTIC LUMINAIRE ON EXISTING POLE	2	EA	\$ 1,050.00	\$2,100.00		
		NEXT OF STREET	MENNESON MILITARY	VI LEWELCK DIECUTORIUS			
1054	MISCELLANEOUS - SITE GENERAL MOBILIZATION (CONSTRUCTION COST \$500K-1000K)	1	LS	\$ 20,000.00	\$20,000.00		
- 10 337 20	REMOVALS - SITE REMEDIATION	TO THE REAL PROPERTY.	INSTANCE CONTRACT	II INSUNVERNOUS NOUS ON THE STATE OF THE STA	SHE NU		
2101	MILL EXISTING PAVEMENT 2 INCH	839	SY	\$ 5.00	\$4,195.00		
	SITE WORK-SITE PREPARATION				de terre and		
2202	CLEAR AND GRUB HEAVY	11.09	AC	\$ 11,000.00	\$121,990.00		
2204	FINAL GRADING (ROAD)	1.92	AC	\$ 6,160.00	\$11,827.20		
OF BEAUTY	EARTHWORK-SITE	and Solding the	THE TANK BUILDING	MIN WINDS	0.00 V		
2300	CUT AND FILL	3098	CY	\$ 10.00	\$30,980.00		
2303	DITCH EXCAVATION	55	CY	\$ 38.00	\$2,090.00		
かり上がり	GRADED AGGREGATE SUBBASE (GASB)		MAN IN A FORM	Pines Rannie	MUNICIPAL AND IN		
2704	4 INCH GRADED AGGREGATE SUBBASE (GASB) COURSE	4788	SY	\$ 6.00	\$28,728.00		
2706	6 INCH GRADED AGGREGATE SUBBASE (GASB) COURSE	744	SY	\$ 8,00	\$5,952.00		
可感应流	SUPERPAVE-FLEXIBLE HOX MIX ASPHALT (HMA)		112 114 114 124	LUST DE LUCRON	CHAIR PHAN		
4000	1 1/2 INCH HOT MIX ASPHALT (HMA) SURFACE 9.5MM PG64-22 (FIN)	4788	SY	\$ 8.00	\$38,304.00		
4000	1 1/2 INCH HOT MIX ASPHALT (HMA) SURFACE 9.5MM PG64-22 (INT)	4788	SY	\$ 8.00	\$38,304.0		
4009	2 INCH HOT MIX ASPHALT (HMA) SURFACE 9.5MM PG 70-22 (FIN)	1583	SY	\$ 10.00	\$15,830.0		
4025	2 INCH HOT MIX ASPHALT (HMA) SURFACE 12.5MM PG 70-22 (INT)	744	SY	\$ 10.00	\$7,440.00		
4040	3 INCH HMA BASE 19MM PG64-22	4788	SY	\$ 15,00	\$71,820.0		
4047	4 1/2 INCH HMA BASE 25MM PG64-22	744	SY	\$ 23.00	\$17,112.0		
4750	STORM DRAIN-REINFORCED CONCRETE PIPE (RCP) CLASS III ROUND 15 INCH RCP CL III W/ RUBBER GASKET	152	LF	\$ 44.00	\$ 6,688.00		
		Silver March Street Street	CARROLL MANAGES AN				
4828	STORM DRAIN-REINFORCED CONCRETE PIPE (RCP) CLASS IV ROUND 15 INCH RCP CL IV W/ RUBBER GASKET	187	LF	\$ 60.00	\$11,220.0		
	The state of the s						
4933	STORM DRAIN-REINFORCED CONCRETE PIPE (RCP) CLASS IV ELLIPTICAL 12 INCH X 18 INCH RCP CL IV W/ RUBBER GASKET	47	LF	\$ 66.00	\$3,102.0		
	STORM DRAIN-REINFORCED CONCRETE PIPE-ROUND-END SECTIONS		new to the second	a South March	1100 0000000000000000000000000000000000		
5050	15 INCH END SECTION	52	EA	\$ 380.00	\$19,760.0		
	STORM DRAIN - UNDERDRAINS	and the same of th			Extended to		
5250	6 INCH PVC UNDERDRAIN	615	LF	\$ 13.00	\$7,991.1		
Mag A Male	STORM DRAIN STRUCTURES - INLETS		MS TO ME SO THE SE	a Scullennians	The state of the s		
5708	A-10 INLET 3.0 FOOT <=3V.F	3	EA	\$ 3,110.00	\$9,330.0		
5713	A-10 > 3.0 V.F.	2.7	VF	\$ 240.00	\$645.6		
5783	E-INLET	1	EA	\$ 3,700.00	\$3,700.0		
5785	K-INLET	4	EA	\$ 1,800.00	\$7,200.0		
i barron	CONCRETE WORK	and granter	No Street Lives		A DESCRIPTION		
5870	CONCRETE CURB AND GUTTER	615	LF	\$ 16.00	\$9,835.2		
5882	RURAL RESIDENTIAL DRIVEWAY ENTRANCE W/ PIPE - DOUBLE	26	EA	\$ 2,500.00	\$65,000.0		
5884 5886	CONCRETE SIDEWALK - 4 FOOT WIDE CONCRETE SIDEWALK RAMP TYPE "Å"	463	LF EA	\$ 18.00 \$ 600.00	\$8,334.0 \$2,400.0		
					N. Or Appell		
7300	SODDING	2778	SY	\$ 4.00	\$11,112.0		
		THE STATE OF THE S			William Co.		
7700	DPW&T STREET TREE (SHADE TREE)	57	EA	\$ 250.00	\$14,250.0		

Item No.	ITEM DESCRIPTION	QUANTITY	UNIT	UNIT COST	COST
SUBTOTAL					\$670,290.10
	SEDIMENT CONTROL (10% SUBTOTAL)	TO STREET WORK TO		(6) 水色层。	\$67,029.01
TOTAL					\$737,319.11
	ADDITIONAL		ORIGINAL		
EST, COSTS	9	-	APPLICANT EST.		737,319
+ % CONTING.			ESD EST. AMT.		
TOTAL COST			+25.00% CONTING.		\$921,649
FEE			ESD TOTAL EST.		
BOND AMOUNT			PREPARED BY*		
TOTAL BOND			DATE*		
TOTAL FEES			FILING FEE; 3.3%		\$24,577
PREPARED BY*			PERMIT FEE; 10%		\$73,732
DATE*					

NUMBER OF STREET SIGNS: STREET LIGHTS WILL BE NECESSARY (Y/N) ENGINEERING COMPANY: DEWBERRY CONSULTANTS LLC

*BY ESD (ENGINEERING SERVICES DIVISION, DPW&T)

PGC FORM #1042 (REV. 7/93)

COST ESTIMATE - ON SITE GRADING (OUTSIDE ROW)

PREPARED BY*
DATE*

FILING FEE; 3.3%

PERMIT FEE; 10%

APPLICATION/Permit #

BOND AMOUNT

TOTAL BOND

TOTAL FEES PREPARED BY*

DATE*

PROJECT NAME:

Item No.	ITEM DESCRIPTION	QUANTITY	UNIT	UNIT UNIT COST		соѕт
	SITE WORK-SITE PREPARATION	Mary Indoputions in the	a sometiment	1 1927		ATTACK TO COLUM
2206	FINAL GRADING (SLOPE - ON SITE)	9.17	AC	\$	5,227.20	\$47,933.42
						\$47,933.42
100	SEDIMENT CONTROL (10% SUBTOTAL)	STATE OF THE PARTY	F. C. L. C. L. C.	150	AL MARKET	\$4,793.34
TOTAL						\$52,726.77
	ADDITIONAL		ORIGINAL	200		
EST. COSTS	CONTING.		APPLICANT EST. ESD EST. AMT.			52,727
TOTAL COST	2.0		+25.00% CONTIN	NG.		\$65,908

NUMBER OF STREET SIGNS: STREET LIGHTS WILL BE NECESSARY (Y/N) ENGINEERING COMPANY: DEWBERRY & CONSULTANTS LLC

*BY ESD (ENGINEERING SERVICES DIVISION, DPW&T)

PGC FORM #1042 (REV. 7/93)

N/A

N/A

COST ESTIMATE - ON SITE STORM DRAIN (OUTSIDE ROW)

APPLICATION/Permit #

PROJECT NAME:

Item No.	ITEM DESCRIPTION	QUANTITY	UNIT	Uf	UNIT COST		UNIT COST COST		COST
SELEXULE DE	STORM DRAIN-REINFORCED CONCRETE PIPE (RCP) CLASS III ROUND	THE RESIDENCE	TAILED NOTE		产于则持至	1	The Telephone		
4750	15 INCH RCP CL III W/ RUBBER GASKET	412	LF	\$	44.00	\$	18,128.00		
1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	STORM DRAIN STRUCTURES - CONCRETE ENDWALLS	DESCRIPTION A					The same		
5811	ENDWALL 15 INCH RCP	3	EA	\$	930.00		\$2,790.00		
	STONE PROTECTION	INDEX. IN AS	Multi-Design	J. Smith	to a property		M ") 21		
5900	RIP-RAP CLASS I GROUTED	7	SY	\$	95.00		\$633.33		
5901	RIP-RAP CLASS I UNGROUTED	20	SY	\$	50.00		\$1,000.00		
SUBTOTAL							\$22,551.33		
	SEDIMENT CONTROL (10% SUBTOTAL)	Rine mehrin	A CONTRACTOR			EPS.	窗		
TOTAL							\$24,806.47		

ADDITIONAL ORIGINAL

EST. COSTS	-	APPLICANT EST.	24,806
+ % CONTING.		ESD EST. AMT.	
TOTAL COST		+25.00% CONTING.	\$31,008
FEE		ESD TOTAL EST.	
BOND AMOUNT	2	PREPARED BY*	
TOTAL BOND		DATE*	
TOTAL FEES		FILING FEE; 3.3%	N/A
PREPARED BY*		PERMIT FEE; 10%	N/A
DATE*			

NUMBER OF STREET SIGNS: STREET LIGHTS WILL BE NECESSARY (Y/N) ENGINEERING COMPANY: DEWBERRY & CONSULTANTS LLC

*BY ESD (ENGINEERING SERVICES DIVISION, DPW&T)

PGC FORM #1042 (REV. 7/93)

Page 5 of 6 2/5/2014

REV. DATE:

2/4/2014

PREPARED BY:

PROJECT NAME:

Site Development Permit #

REVIEW FEES FOR GRADING

Disturbed Area (ac) =	11.09
Review Fee =	\$1861 + \$90 x 0.09
Review Fee =	\$1,869
Park & Planning Fee =	\$5
Filing Fee = 1/2 Review Fee + P&P Fee =	\$940

OFFICE OF LAW BOND REVIEW CHECKLIST

To Be Provided Later

SAMPLE ACCEPTANCE MEMORANDUM

INTER-OFFICE MEMORANDUM

PRINCE GEORGE'S COUNTY, DEPARTMENT OF PERMITTING, INSPECTIONS AND ENFORCEMENT CONSTRUCTION INSTRUCTION INSPECTION REPORT SITE/ ROAD INSPECTIONS

Date:	July 15, 2014
То:	James Coutourier, Chief, Permits Section (No Attachments)
From:	Joe D. Brown Chief Inspector dist. 1 301-883-5741
Thru:	Michael Reahl Code Enforcement Officer
Cc:	Tayman, Juanita F. (<u>JFTayman@co.pg.md.us</u>) 301-883-3822 1801 McCormick Drive Largo, MD 20774
Re:	
The work per	formed under the referenced permit has been recommended for acceptance by the Prior to the release of the
performance	bond, please obtain the following from the permittee:
Partial Bond(s):
	None.
_	

SHOP DRAWING SUBMITTAL FORM



Department of Permitting, Inspections and Enforcement

SITE/ROAD PLAN REVIEW DIVISION



9400 Peppercorn Place Largo, Maryland 20774 301.636.2060 ◆ FAX: 301.925.8510

SHOP DRAWING REVIEW CHECKLIST

PROJECT NAM	E:	CASE NUMBER:	
STRUCTURE N	UMBER:		
The precaster is approval, but pr dimensions per	to send the shop drawings with strior to construction. The design ethis checklist and submit two add Plan Review Revision Division.	gineer submitting shop drawings for approval by ructural computations to the design engineer afte engineer must review and approve the shop drawings, titional copies of the approved shop drawings, This checklist must be approval by DPIE process.	er plan awing to the
	the correctness of shop drawings for the design engineer:	or acceptance by DPIE the following (at a minimu	ım)
[] Wall and slate [] Correct size any precast acceptable. [] Structural de structural de has been de [] The following •	esign certification and P.E. seal by esign of this structure is in accordanged for the specified loadings at motes are to appear on the drawing Structure must be watertight. Annular space between pipe and heconcrete (as specified). For Storm required. Adapters are available for	ngs, orifices and manholes per the approved pla allation of the structure. Coring of structures is a preparer of shop drawing ("I hereby certify that redance with applicable codes and that this struct as indicated on the plan.") ang: note to be filled with an approved non-shrink grounceptor and Stormfilter, a rubber boot connection	the ure
[] Anti-flotation [] Flotation com [] Steps (if requ [] Reference o Engineering	n shop drawings that concrete sho	nere applicable).	type II

Shop Drawing Submittal Form Issue Date: July 26, 2014

conformance with the latest edition a Construction and Materials. [MSHA Standards and Specifications for
Dimensional conformity with the ap dimensions that differ from the approve the structure will not be allowed once design engineer to insure the correctne	ed drawings will be r the structure has be	ejected. Dimensional modifications to en cast. It is the responsibility of the
SUBMITTEDBY:	Firm:	
Address:		
Phone #:		-
Prepared By:		_ DATE:
CHECKLIST APPROVED BY DPIE:		
NAME:	DATE:	

SAMPLE CONSTRUCTION INSPECTION FORM

The latest forms are available on the DPIE website. These are for information only.

- 1. Preconstruction Meeting
 - A. Site Grading Certification
 - B. Landscape Certification
 - C. Fill/Soil Certification
- 2. Construction Inspection Report (2 pages)
- 3. General Inspection Report (2 pages)
- 4. Notice of Violation (2 pages) 2 versions
- 5. Correction Order
- 6. Construction Completion Form
- 7. Inspection Checklist for Paving
- 8. Final Inspections Report
 - A. Site Grading Certification
 - B. Landscape Certification
 - C. Structure Location Certification (Property Corners)
 - D. Fill/Soil Certification



Department of Permitting, Inspections and Enforcement

INSPECTIONS DIVISION

1801 McCormick Drive, Suite 120 Largo, Maryland 20774 (301) 883-3820 • FAX: (301) 883-3873



PRE-CONSTRUCTION MEETING

The objective of the Initial Meeting is to assist in better understanding the responsibilities of the Department of Permitting, Inspections and Enforcement and the responsibilities of the permittee and/or developer toward environmentally safe quality development.

- a) Erosion and Sediment Control Plan;
- b) Woodland Conservation Plan Type II or a letter of exemption;
- c) Grading/Site Development Plan
- 1) **CALL MISS UTILITY AT 1–800–257–7777.** Call 48 hours BEFORE beginning work and **OBTAIN approval**. Approval is good for ten (10) days and can be renewed over the phone.
- 2) MANDATORY INSPECTIONS/SEQUENCE OF WORK. Very Important. The following sequence of Inspections ARE MANDATORY INSPECTIONS. Obtain written Inspection approval prior to proceeding to each activity.
 - a) Obtain erosion and sediment control approval, Maryland National Capital Park and Planning Commission (M NCPPC) TCP II plan approval, and obtain DPIE permits.
 - b) Pre-construction Meeting to review permits and inspect installation of TCP II.
 - c) Initial meeting to inspect installation of erosion and sediment (E&S) controls. Then authorize to clear and grade.
 - d) Authorization to Remove Sediment Controls Obtain written authorization from Inspector prior to removal of any E&S controls.

Failure to obtain these Inspections will result in Violations, Stop Work Orders, and Fines up to \$1,000 per day.

- 3) **FOLLOW THE PLAN SEQUENCE OF CONSTRUCTION!** Observe the requirements as they relate between the Woodland Conservation Plan Type II, the Erosion and Sediment Control Plan, and the Grading/Site Development Plan. Obtain clarification from the Site Development Inspector as to which work items can be done simultaneously, if any.
- 4) ADHERE CLOSELY TO PLAN DETAILS FOR EACH EROSION AND SEDIMENT CONTROL DEVICE. Observe all relative elevations and dimensions. Each device required should have detail in that plan.
- 5) INITIAL CLEARING WORK ONLY FOR EROSION AND SEDIMENT CONTROLS.
- 6) INITIAL INSPECTION APPROVAL. After erosion and sediment controls have been installed and stabilized, obtain written inspections approval prior to further grading and subsequent site development.
- 7) DO NOT GO BEYOND THE APPROVED LIMITS OF DISTURBANCE! Buffer areas, wetland/floodplain areas and tree/vegetative save areas are to be protected to prevent disturbance. If unauthorized disturbance has occurred, notify the Site Development Inspector immediately to resolve the matter. Note: It is the responsibility of the owner/permittee to utilize the necessary resources to assure that the location of tree save areas and limits of disturbance are in full accord with the approved plans.
- 8) **EXCAVATIONS.** The sides of temporary excavations/trenches made for foundations, buildings and utility installations shall be protected, shored or sloped as required by regulations of the Maryland State Department of Labor and Industry. Their toll-free number in Maryland is 1–800–492–6226.
- 9) STABILIZATION. Very Important. Erosion and Sediment Controls must be stabilized within 3 days. Areas that have been disturbed and are not actively being worked as well as areas that are on final grade must be stabilized within 7 days. Stabilization requirements are detailed in the plan. Unless otherwise indicated, the area to be stabilized may require four inches of topsoil.
- 10) KEEP STREETS, CURBS, GUTTERS, AND SIDEWALKS CLEAN AT ALL TIMES. If mud is tracked onto a street, do not hose into any storm drain unless the storm drain outfalls into an approved erosion and sediment control device.

- 11) TRANSITION FROM ROUGH GRADE TO FINAL GRADE. Sites that are opened and mass graded under a Rough Grading Permit are required to revise the Grading Permit to a Fine Grade/Site Development Permit prior to initiating other site work such as house construction, recreational areas, athletic fields, tot-lots and hiker/biker trails or other site amenities pursuant to an approved Site Plan. Upon submitting the appropriate plans, obtaining all agency review approvals, changing the work description to "Fine Grading/Site Development," the existing Grading Permit can then be revised to include such work.
- 12) SCD (EROSION & SEDIMENT CONTROL PLANS) PLANS/UPDATE & RENEWAL. Approved SCD plans remain valid for two (2) years, (except surface mines and landfill plans which remain valid for five (5) years). It is the responsibility of the Permittee to maintain current SCD plans until Final acceptance of the permit. (Subtitle 4, Division 3, 4-299, & COMAR 26.17.01.08F.09C)
- 13) MAINTENANCE OF EROSION & SEDIMENT CONTROLS/SELF-DIRECTED REPAIRS. Very Important. Maryland State Law (COMAR 26.09.01.06) requires "responsible personnel" (i.e., owner, contractor, foreman, superintendent, project engineer, etc.) who is in charge of on-site clearing and grading operations or sediment control associated with a project shall hold a current State Certificate of Training in Erosion & Sediment Control. It is further required that "Self-Directed Repairs" of on-site erosion & sediment controls be implemented by the Permittee. This person shall inspect the erosion and sediment controls on a daily basis and make self-directed repairs. Consult with the Inspector if there are any questions or necessary changes to the plans.
 - Failure to maintain these controls will result in Violations, Stop Work Orders, and Fines up to \$1,000 per day.
- 14) SEPTIC SYSTEMS. Very Important. Sites utilizing Septic Systems must provide particular attention to the proposed limits of disturbance for septic areas. Encroachment or disturbance in these areas may result in significant delays or suspension of permit. It is the responsibility of the permittee to obtain all necessary inspections from the Health Department. Any questions regarding septic systems may be referred to the Health Department at (301) 883–7681.
- 15) PERMITS/PLANS. All work must be performed in accordance with the approved plans and completed within the time frame of the Permit. It is the responsibility of the Permittee to maintain current plans, to include all applicable revisions and permits.
- 16) **FILLS.** Areas receiving FILL under a grading permit, which are shown on the approved plan as supporting structures or pavement, must be properly placed and compacted as required for that class of fill and be certified by a Maryland Registered Professional Engineer. Fill must be placed in locations as noted on the approved permitted grading and/or site development plan any changes require plan/permit revision.
- 17) **CERTIFICATION.** Upon completion of any or all of the following work stages rough grading, site development, permanent fine grading and landscaping a Certification may be required from the permittee's engineer attesting that all work (*i.e.*, grade elevations, type of fill placed, etc.) has been completed in accordance with the approved plan and the Prince George's County Code.
- 18) SAFETY FENCING FOR EROSION AND SEDIMENT CONTROL DEVICES. Very Important. Sediment traps and basins located within a densely populated area or in the proximity of an elementary school, playground or other area where small children may congregate without adult supervision, MUST be enclosed with a minimum 42-inch-high safety fence.

/We have personally reviewed the	e information contained	herein.	
Certified Responsible Personnel for Eros		Card Number	Date Issued
Certified Responsible Personnel for Eros Owner/Developer's Representative			Date Issued Date



Department of Permitting, Inspections and Enforcement

INSPECTIONS DIVISION

1801 McCormick Drive, Suite 120 Largo, Maryland 20774 (301) 883–3820 ◆ FAX: (301) 883–3873



TYPES OF INSPECTIONS

The inspections below are not all inclusive — other inspections may be required pursuant to permit and plan conditions, and County Code requirements.

Many Inspections are mandatory prior to proceeding with other work. Review the conditions of your permit and plan in consideration of sequence of construction. Consult with your Inspector regarding mandatory inspection requirements. FAILURE TO OBTAIN REQUISITE INSPECTIONS MAY JEOPARDIZE THE PROGRESS OF THE SITE AND RESULT IN VIOLATIONS, STOP WORK ORDERS, AND FINES UP TO \$1,000 PER DAY.

PRE-CONSTRUCTION MEETING. Meeting between the owner, contractor, engineer and Inspection personnel to review the requirements and conditions as established by the Erosion/Sediment Control Plan, the Woodland Conservation Plan — Type II and the Grading/Site Development Plan along with Prince George's County policy, procedures and required inspections. **Note:** When the pre-construction meeting is approved, the permittee receives a written report validating the pre-construction meeting.

WOODLAND CONSERVATION PLAN — **TYPE II INSPECTION.** Unless otherwise agreed upon by the Inspector at the pre-construction meeting, once the permit has been obtained, the only work that may start is the placement of the tree protection devices according to the approved woodland conservation Type II plan. These tree protection devices must then be inspected and approved before the erosion and sediment controls can be installed. **Note:** It is the responsibility of the owner/permittee to utilize the necessary resources to assure that the location of the tree save areas and devices and the limits of disturbance are in full accord with the plans.

INITIAL SEDIMENT CONTROL INSPECTION. This occurs before any clearing of trees or grading occurs. This inspection verifies permittee has installed TCP II controls. When the initial sediment control inspection is approved, the permittee receives written authorization to install erosion and sediment controls.

ROUTINE INSPECTION. This inspection verifies compliance and performance of erosion and sediment control maintenance, site development requirements, and compliance with sequence of construction, approved permit and plans, and Prince George's County Code. Self-directed repairs of erosion and sediment controls are required of permittee. Consult with Inspector for guidance and assistance.

STORMWATER MANAGEMENT INSPECTION. The Department of Permitting, Inspections and Enforcement Management Design Manual, Chapter 10, "Inspection and Enforcement Procedures" sets forth the inspection and enforcement guidelines to be followed for inspections of stormwater management/water quality measures.

AUTHORIZATION TO REMOVE SEDIMENT CONTROLS. Written authorization to remove ANY sediment controls must be obtained from the Inspector PRIOR to removal of controls. As a general rule, a minimum 75% of the contributing drainage area must be complete and permanently stabilized to request removal of any E&S controls.

FINAL INSPECTION. When occupancy is involved, this inspection verifies that the site development is in compliance. Individual occupancies may then be recommended by the Site Development Inspection Section.

Note: For final approval and bond release of a Grading Permit and/or the Stormwater Management Permit, all grading, permanent stabilization and site development shall be 100% complete, and all required Engineer's certifications, final reports and/or "as built" plans must be approved, certifying compliance with the approved permit and plans.



Department of Permitting, Inspections and Enforcement

INSPECTIONS DIVISION

1801 McCormick Drive, Suite 120 Largo, Maryland 20774 (301) 883-3820 • FAX: (301) 883-3873



FINAL ACCEPTANCE OF SITE AND BOND RELEASE

The majority of delays associated with final acceptance of site and bond release can be avoided if the following issues are addressed prior to final inspection. This "Final Acceptance of Site and Bond Release" is NOT to be taken as a comprehensive list of permit and plan requirements and does not waive any provision thereof. REVIEW THE CONDITIONS OF THE PERMIT AND APPROVED PLANS COMPLETELY!

DRAINAGE. All graded/disturbed areas must have positive drainage. Surface runoff must discharge acceptably, *i.e.*, across no more than one adjacent lot unless an approved surface drainage easement exists to accommodate its flow into a publicly maintained drainage system, street or continuously flowing natural watercourse. Springs, seeps, or groundwater having objectionable effects must be capped and conveyed into a piped outfall to a public drainage system or continuously flowing natural watercourse.

FILLS. All Class I & II fills or other structural fill soils placed on site shall be certified by a licensed Maryland Professional Engineer certifying acceptable placement and compaction including necessary supporting documentation. The certification shall include the permit number, address of the site, and P.E. seal with registration number.

FINAL REPORT/SITE CERTIFICATION. A certification must be submitted from a licensed Maryland Professional Engineer certifying that "all grading and site development has been completed in accordance with the plans and Subtitle 4, Division 3 of the Prince George's County ordinance." The certification shall include the permit number, address of the site, and P.E. seal with registration number. The Final Report shall include any and all approved waivers.

GRADING. All grades and final elevations must be in accordance with the approved grading/site development plans and Subtitle 32, Division 3, Grading Ordinance. Any modifications must be authorized by waiver or approved revisions to the plan.

LANDSCAPING/WOODLAND CONSERVATION. All requisite landscaping, reforestation, afforestation, wetland plantings shall be completed in accordance with the approved Landscaping and/or TCP II plans, including location(s), size, type, and quantity. Any substitutions shall be approved in writing by M-NCPPC. All landscaping shall be properly labeled for Inspection. A Landscaping Certification shall be submitted by a licensed Maryland Professional Engineer, or Registered Landscape Architect certifying that all landscaping and/or reforestation work has been completed in accordance with the approved plans and that the planted material is healthy.

OTHER AGENCIES

- Chesapeake Bay Critical Area
- M-NCPPC
- · Department of Public Works & Transportation
- Wetland/Floodplain

- · Planning Board
- Tree Conservation
- · Health Department
- · State of Maryland
- . Department of the Environment
- . Department of Natural Resources

PARKING LOT/MAC/ADA ACCESSIBILITY REQUIREMENTS. Is the topcoat paving completed? Does the parking space layout and number of parking spaces agree with the approved plan? Are parking spaces properly sized (standard = 9.5• x 19•; compact = 8• x 16.5•; handicapped = 13• x 19• or 5• access lane with 8• parking space)? Are the handicapped signs properly installed? Are the handicapped curb cuts/ramps installed for free access? Are all other MAC/ADA accessibility requirements met?

RECREATIONAL AREAS. Have all recreational areas, *i.e.*, open play areas, tot-lots, hiker/biker trails been properly installed? Has the M-NCPPC given final inspection approval and acceptance of the recreational requirements? If yes, provide copies of written final inspection approval of all recreational areas to the inspector. If no, obtain M-NCPPC written final inspection approval.

SEDIMENT CONTROLS. All storm drain systems and outfalls (riprap, grassed waterways, etc.) must be free of sediment. All areas must be permanently stabilized to prevent erosion. All erosion and sediment controls must be removed. Note: Obtain written authorization from the inspector BEFORE removing any sediment control.

SITE DEVELOPMENT. Site development shall be completed in accordance with the approved plans prior to granting occupancy of any building or structure on site. Adequate and acceptable completion of recreational facilities, landscaping, parking, lighting, retaining walls, and other site work may occur with the progress of the development of any project as determined by the Director. Ensure any changes or deviations to the permit plans are approved and reflect revised plans and permits.

STABILIZATION. All areas MUST have acceptable PERMANENT STABILIZATION well established prior to final acceptance. Poor soil areas may require a minimum of 4. of acceptable topsoil. Note: Excessive weeds throughout the grass cover is NOT acceptable.

STORMWATER MANAGEMENT.

Typical Certifications and Reports may include:

- · As-Builts
- Landscape Certification
- · Maintenance Agreement

- Pipe Certification
- · Engineer Certification Letter
- Structure Certifications
- Embankment Certification
- · Release of Liens

TRASH/DEBRIS. All objectionable and/or waste materials (excess spoil material, dead trees, tree limbs, stumps, building trash/materials) must be removed from the site to an authorized disposal facility.

VIOLATIONS/COMPLAINTS. Any outstanding violations/complaints must be closed prior to final inspection approval and subsequent bond release.



INSPECTIONS DIVISION

1801 McCormick Drive, Suite 120 Largo, Maryland 20774 (301) 883-3820 • FAX: (301) 883-3873



SITE GRADING CERTIFICATION

Job Address:	
Lot:	Block:
Building Permit #:	
grading, drainage, erosion co water quality facilities, woodla have been completed in acc Maryland-National Capital Par	best of my knowledge, information and belief that all ontrol facilities, landscaping, stormwater management/and conservation and other site work at this address cordance with the permit, approved plans, and the k and Planning Commission approved detailed site, tree plans dated () and revised on ept as noted. **Insert Date**
	Signature
SEAL	Print Name
	Date



INSPECTIONS DIVISION

1801 McCormick Drive, Suite 120 Largo, Maryland 20774 (301) 883-3820 ◆ FAX: (301) 883-3873



LANDSCAPING CERTIFICATION

Job Address:	
Lot:	Block:
Building Permit #:	
landscaping on the above-referenced si plans, and latest revision to the Ma Commission approved detailed site, tre	ny knowledge, information and belief that all ite is in accordance with the permit, approved aryland–National Capital Park and Planning see conservation, and landscaping plans dated (), except as noted.
Exceptions:	
	Signature
SEAL	Print Name
	Date



INSPECTIONS DIVISION

1801 McCormick Drive, Suite 120 Largo, Maryland 20774 (301) 883-3820 • FAX: (301) 883-3873



FILL/SOIL CERTIFICATION

Job Address:	
Lot:	Block:
Permit #:	
attached compaction test results and deall Class #1 and/or Class #2 fills as delir	wledge, information and belief, and based on the ocumentation prepared by our representatives, neated on the approved plans has been properly accordance with Subtitle 32, Division 3 of the bove referenced permit(s).
Exceptions:	
	Signature
SEAL	Print Name
	Date

MANDATORY INSPECTIONS/SEQUENCE OF WORK.

The following sequence of inspections ARE MANDATORY INSPECTIONS (4-290 Inspections & Supervision).

Obtain written Inspection approval prior to proceeding to each activity.

Pre-Construction Meeting

TCP II Inspection — Installation of Tree Conservation/Protection Initial Inspection — Installation of all required Erosion & Sediment Controls to include Stabilization

Authorization to Clear/Grade — Upon written approval of Initial Inspection, okay to enter clearing/grading phase

Authorization to Remove Sediment Controls — Obtain written authorization from Inspector prior to removal of any E&S controls

FAILURE TO OBTAIN THESE INSPECTIONS WILL RESULT IN VIOLATIONS, STOP WORK ORDERS, AND FINES UP TO \$1,000 PER DAY.

FOLLOW THE PLAN SEQUENCE OF CONSTRUCTION! Observe the requirements as they relate between the Woodland Conservation Plan — Type II, the Erosion and Sediment Control Plan, Storm Drain-Stormwater Management Plan, and the Grading/Site Development Plan. Obtain clarification from the Site Development Inspector as to which work items can be done simultaneously, if any,

EROSION & SEDIMENT CONTROLS STANDARDS. Adhere closely to plan details for each erosion and sediment control device. Observe all relative methods, specifications, elevations and dimensions. Each device required should have detail in the plan. Refer to the latest edition of the Maryland Standards and Specifications for Erosion and Sediment Control. These are the MINIMUM requirements — NO EXCEPTIONS.

DO NOT GO BEYOND THE APPROVED LIMITS OF DISTURBANCE! Buffer areas, wetland/floodplain areas and tree/vegetative save areas are to be protected to prevent disturbance. If unauthorized disturbance has occurred, notify the Site Development Inspector immediately to resolve the matter. Note: It is the responsibility of the owner/permittee to utilize the necessary resources to verify the location of tree save areas and limits of disturbance are in full compliance with the approved plans. INITIAL CLEARING WORK ONLY FOR EROSION AND SEDIMENT CONTROLS.

INITIAL INSPECTION APPROVAL, Mandatory Inspection. After erosion and sediment controls have been installed and stabilized, obtain written inspection approval prior to any further disturbance or grading and subsequent site development.

EXCAVATIONS. The sides of temporary excavations and trenches made for foundations, buildings and utility installations shall be protected, shored or sloped as required by regulations of the Maryland State Department of Labor and Industry. The toll-free number in Maryland is 1-800-492-6226.

STABILIZATION. Very important. Seed, Lime Fertilizer, Mulch, & Tack. Hydro-seeding or Sod. STABILIZATION IS THE BEST DEFENSE AGAINST EROSION — AND REDUCES MAINTENANCE COSTS. Erosion and Sediment Controls must be stabilized within 3 days. Areas that have been disturbed and are not actively being worked as well as areas that are on final grade must be stabilized within 7 days. Stabilization requirements are detailed in the plan. Unless otherwise indicated, areas to be stabilized shall require four inches of topsoil and other soil amendments as necessary. Refer to Stabilization Notes and Details on Plans.

KEEP STREETS, CURBS, GUTTERS, AND SIDEWALKS CLEAN AT ALL TIMES. If mud is tracked onto a street, do not hose into any storm drain unless the storm drain outfalls into an approved erosion and sediment control device. Sediment tracked onto streets is subject to immediate issuance of a civil citation up to \$1,000 per day.

TRANSITION FROM ROUGH GRADE TO FINAL GRADE. Sites that are opened and mass graded under a Rough Grading Permit are required to revise the Grading Permit to a Fine Grade/Site Development Permit prior to initiating other site work such as house construction, recreational areas, athletic fields, tot-lots and hiker/biker trails or other site amenities pursuant to an approved Site Plan.

SCD (EROSION & SEDIMENT CONTROL PLANS) PLANS/UPDATE & RENEWAL. Approved SCD plans remain valid for two (2) years, (except surface mines and landfill plans, which remain valid for five (5) years). It is the responsibility of the Permittee to maintain current SCD plans until Final acceptance of the permit. (Subtitle 4, Division 3, 4-299, & COMAR 26.17.01.08F.09C)

MAINTENANCE OF EROSION & SEDIMENT CONTROLS/SELF-DIRECTED REPAIRS. Very Important. Maryland State Law (COMAR 26.09.01.06) requires "responsible personnel" (i.e., owner, contractor, foreman, superintendent, project engineer, etc.) who is in charge of on-site clearing and grading operations or sediment control associated with a project shall hold a current State Certificate of Training in Erosion & Sediment Control. It is further required that "Self-Directed Repairs" of on-site erosion & sediment controls be implemented by the Permittee. This person shall inspect the erosion and sediment controls on a daily basis and make self-directed repairs in accordance with the approved plans and specifications. Consult with the Inspector if there are any questions or necessary changes to the plans, FAILURE TO MAINTAIN E&S CONTROLS WILL RESULT IN VIOLATIONS, STOP WORK ORDERS, AND FINES UP TO \$1,000 PER DAY.

SEPTIC SYSTEMS, Very Important. Sites utilizing Septic Systems must pay particular attention to the proposed limits of disturbance of septic areas. Encroachment or disturbance in these areas may result in significant delays or suspension of permit. It is the responsibility of the permittee to obtain all necessary inspections from the Health Department, Any questions regarding septic systems may be referred to the Health Department at (301) 883-7681.

PERMITS/PLANS. All work must be performed in accordance with the approved plans, Code, Standards and Specifications, and completed within the time frame of the Permit. It is the responsibility of the Permittee to maintain current plans, to include all applicable revisions and permits.

FILLS. Areas receiving FILL under a grading permit, which are shown on the approved plan as supporting structures or pavement, must be properly placed and compacted as required for that class of fill and be certified by a Maryland Registered Professional Engineer. Fill must be placed in locations as noted on the approved permitted grading and/or site development plan — any changes require plan/permit revision.

CERTIFICATIONS & REPORTS. Certifications shall be signed and sealed by a Maryland Registered Professional Engineer. Any work requiring Certification and/or Reports pursuant to Code and/or at the discretion of the Director shall be submitted within thirty (30) days of completion, including but not limited to: Fills, Grading, Storm Drain & SWM Systems, Pipes, Structures, Embankment/Core Trench, Anti-Seep Collars, Concrete, Retaining Structures, Reforestation, CBCA, Landscaping ADA/Handicap, and Site Development. Certifications shall attest that all work has been completed in accordance with the approved plan, specifications, and the Prince George's County Code.



INSPECTIONS DIVISION

1801 McCormick Drive, Suite 120 Largo, Maryland 20774 (301) 883-3820 • FAX: (301) 883-3873



GENER	RAL INSPECT	ION REPO	KT	
Site:	Inspector:		Date:	
Permit #:			Renewal	Required
SCD #:	Expires:	Revision	Renewal	Required
Notified Owner:	Contractor:	7 🗖	Other:	
Inspection Type: Pre-Construction Initial Responsible Party On Site: Yes No S	al Complaint Meeting C Site Activity: Clearing Grad	RoutineFollow-up lingSite WorkSWM	Utilities Bldg	J. Road Const.
COMMENTS:				
· · · · · · · · · · · · · · · · · · ·				
¥				
All Toronto Property and Indiana Control of the Con	91 N P L			
All items in non-compliance must be repaired in compliance date shown. Failure to comply may ENFORCEMENT ACTION TAKEN: Violati	y result in any <u>or</u> all of the follow	ing ac <u>tio</u> ns being taken on t	his site:	
Compliance Date:		nded From:		
	LAUI			
Permittee Representative Signatu	re		Date	

MANDATORY INSPECTIONS/SEQUENCE OF WORK

The following sequence of inspections ARE MANDATORY INSPECTIONS (4-290 Inspections & Supervision).

Obtain written Inspection approval prior to proceeding to each activity.

Pre-Construction Meeting — Obtain Permit

TCP II Inspection — Installation of Tree Conservation/Protection Initial Inspection — Installation of all required Erosion & Sediment Controls to include Stabilization

Authorization to Clear/Grade — Upon written approval of Initial Inspection, okay to enter clearing/grading phase

Authorization to Remove Sediment Controls — Obtain written authorization from Inspector prior to removal of any E&S controls

FAILURE TO OBTAIN THESE INSPECTIONS WILL RESULT IN VIOLATIONS, STOP WORK ORDERS, AND FINES UP TO \$1,000 PER DAY.

FOLLOW THE PLAN SEQUENCE OF CONSTRUCTION! Observe the requirements as they relate between the Woodland Conservation Plan — Type II, the Erosion and Sediment Control Plan, Storm Drain—Stormwater Management Plan, and the Grading/Site Development Plan. Obtain clarification from the Site Development Inspector as to which work items can be done simultaneously, if any,

EROSION & SEDIMENT CONTROLS STANDARDS. Adhere closely to plan details for each erosion and sediment control device. Observe all relative methods, specifications, elevations and dimensions. Each device required should have detail in the plan. Refer to the latest edition of the Maryland Standards and Specifications for Erosion and Sediment Control. These are the MINIMUM requirements — NO EXCEPTIONS.

DO NOT GO BEYOND THE APPROVED LIMITS OF DISTURBANCE! Buffer areas, wetland/floodplain areas and tree/vegetative save areas are to be protected to prevent disturbance. If unauthorized disturbance has occurred, notify the Site Development Inspector immediately to resolve the matter. Note: It is the responsibility of the owner/permittee to utilize the necessary resources to verify the location of tree save areas and to ensure limits of disturbance are in full compliance with the approved plans. INITIAL CLEARING WORK ONLY FOR EROSION AND SEDIMENT CONTROLS.

INITIAL INSPECTION APPROVAL, Mandatory Inspection. After erosion and sediment controls have been installed and stabilized, obtain written inspection approval prior to any further disturbance or grading and subsequent site development.

EXCAVATIONS. The sides of temporary excavations and trenches made for foundations, buildings and utility installations shall be protected, shored or sloped as required by regulations of the Maryland State Department of Labor and Industry. The toll-free number in Maryland is 1-800-492-6226.

STABILIZATION. Very important. Seed, Lime Fertilizer, Mulch, & Tack. Hydro-seeding or Sod. STABILIZATION IS THE BEST DEFENSE AGAINST EROSION — AND REDUCES MAINTENANCE COSTS. Erosion and Sediment Controls must be stabilized within 3 days. Areas that have been disturbed and are not actively being worked as well as areas that are on final grade must be stabilized within 7 days. Stabilization requirements are detailed in the plan. Unless otherwise indicated, areas to be stabilized shall require four inches of topsoil and other soil amendments as necessary. Refer to Stabilization Notes and Details on Plans.

KEEP STREETS, CURBS, GUTTERS, AND SIDEWALKS CLEAN AT ALL TIMES. If mud is tracked onto a street, do not hose into any storm drain unless the storm drain outfalls into an approved erosion and sediment control device. Sediment tracked onto streets is subject to immediate issuance of a civil citation up to \$1,000 per day.

TRANSITION FROM ROUGH GRADE TO FINAL GRADE, Sites that are opened and mass graded under a Rough Grading Permit are required to revise the GradingPermit to a Fine Grade/Site Development Permit prior to initiating other site work such as house construction. recreational areas, athletic fields, tot-lots and hiker/biker trails or other site amenities pursuant to an approved Site Plan.

SCD (EROSION & SEDIMENT CONTROL PLANS) PLANS/UPDATE & RENEWAL, Approved SCD plans remain valid for two (2) years, (except surface mines and landfill plans, which remain valid for five (5) years). It is the responsibility of the Permittee to maintain current SCD plans until Final acceptance of the permit. (Subtitle 4, Division 3, 4-299, & COMAR 26.17.01.08F.09C)

MAINTENANCE OF EROSION & SEDIMENT CONTROLS/SELF-DIRECTED REPAIRS. Very Important. Maryland State Law (COMAR 26.09.01.06) requires "responsible personnel" (i.e., owner, contractor, foreman, superintendent, project engineer, etc.) who is in charge of on-site clearing and grading operations or sediment control associated with a project shall hold a current State Certificate of Training in Erosion & Sediment Control. It is further required that "Self-Directed Repairs" of on-site erosion & sediment controls be implemented by the Permittee. This person shall inspect the erosion and sediment controls on a daily basis and make self-directed repairs in accordance with the approved plans and specifications. Consult with the Inspector if there are any questions or necessary changes to the plans. FAILURE TO MAINTAIN E&S CONTROLS WILL RESULT IN VIOLATIONS, STOP WORK ORDERS, AND FINES UP TO \$1,000 PER DAY.

SEPTIC SYSTEMS, Very Important. Sites utilizing Septic Systems must pay particular attention to the proposed limits of disturbance of septic areas. Encroachment or disturbance in these areas may result in significant delays or suspension of permit. It is the responsibility of the permittee to obtain all necessary inspections from the Health Department. Any questions regarding septic systems may be referred to the Health Department at (301) 883-7681.

PERMITS/PLANS, All work must be performed in accordance with the approved plans, Code, Standards and Specifications, and completed within the time frame of the Permit. It is the responsibility of the Permittee to maintain current plans, to include all applicable revisions and permits.

FILLS. Areas receiving FILL under a grading permit, which are shown on the approved plan as supporting structures or pavement, must be properly placed and compacted as required for that class of fill and be certified by a Maryland Registered Professional Engineer. Fill must be placed in locations as noted on the approved permitted grading and/or site development plan — any changes require plan/permit revision.

CERTIFICATIONS & REPORTS. Certifications shall be signed and sealed by a Maryland Registered Professional Engineer. Any work requiring Certification and/or Reports pursuant to Code and/or at the discretion of the Director shall be submitted within thirty (30) days of completion, including but not limited to: Fills, Grading, Storm Drain & SWM Systems, Pipes, Structures, Embankment/Core Trench, Anti-Seep Collars, Concrete, Retaining Structures, Reforestation, CBCA, Landscaping ADA/Handicap, and Site Development. Certifications shall attest that all work has been completed in accordance with the approved plan, specifications, and the Prince George's County Code.



INSPECTIONS DIVISION

1801 McCormick Drive, Suite 120



Largo, Maryland 20774 (301) 883–3820 • FAX: (301) 883–3873

OCATION OF VIOLATION:			
ot/Liber:Block/Folio:			
ubdivision:	Tax Map #:		
wner:	Phone:		
ddress:	av.		avn a .
Street ontractor:	City Phone:	State	ZIP Code
ddress:			
Street	City	State	ZIP Code
I have inspected this site, and I have	CORRECTIVE AC	TION REQUIRED)
found the following violation(s) of			
county ordinances and/or approved plans and specifications as checked:			
CODE SECTION & TITLE:			
CODE SECTION & TITLE:			
· · · · · · · · · · · · · · · · · · ·			
			- I
You are hereby notified to comply			
with the provisions of the law and to			
correct the deficiencies on or before:			
Date of Compliance			

RIGHT OF APPEAL

Grading, Drainage and Erosion Ordinance

An APPEAL of a violation notice of the Grading, Drainage and Erosion Ordinance claiming the true intent of the Ordinance has been misconstrued must be filed WITHIN FIVE (5) DAYS OF THE RECEIPT OF THE NOTICE.

General Building Code

An APPEAL of a violation notice of the General Building Code claiming the true intent of the Code has been misconstrued must be filed WITHIN THIRTY (30) DAYS OF THE RECEIPT OF THE NOTICE.

The above APPEALS must be filed with the BOARD OF APPEALS for Prince George's County, County Administration Building, 14741 Governor Oden Bowie Drive, Room 2173, Upper Marlboro, Maryland 20772. Please call (301) 952–3220 for information.

Electrical Code

An APPEAL of a violation of the Electrical Code claiming the true intent of the Code has been misconstrued or inappropriately applied must be filed with the Electrical Code Official, Department of Permitting, Inspections and Enforcement, WITHIN THIRTY (30) DAYS FROM THE RECEIPT OF THE NOTICE. The second step in the electrical appeal procedure is the Board of Registration for Master Electricians and Electrical Contractors and must be filed WITHIN TEN (10) WORKING DAYS from the date of the Chief Electrical Inspector's decision.

Stop Work Order

An APPEAL of a Stop Work Order may be made to the Code Official WITHIN TWENTY-FOUR (24) HOURS as specified in accordance with Prince George's County Codes and Basic Building Codes.

FOR YOUR INFORMATION

Violation Penalties

Any person, firm, association, partnership, or corporation, or combination thereof, who shall violate a provision of the Basic Code, or of this Subtitle, or fail to comply with any of the requirements thereof, or violate a lawful order issued thereunder, or who shall erect, construct, alter, or repair a building or structure in violation of an approved plan or directive of the Building Official, or of a permit or certificate issued under the provisions of the Basic Code, shall be guilty of a misdemeanor punishable by a fine of not more than one thousand (\$1,000.00) dollars per day or by imprisonment for six (6) months, or by both fine and imprisonment. Each day that a violation continues shall be deemed a separate offense, in accordance with Prince George's County Codes and Basic Building Codes.

Investigation Fee

For information on Investigation Fees, please call (301) 883-3820.

Questions

If you have any questions concerning this notice, contact this office at (301) 883-3820 or the issuing inspector at the number on this notice.

REQUESTS FOR EXTENSION OF COMPLIANCE DATE OR WAIVER

All requests for extensions or waiver must be made in writing to the Code Official, Department of Permitting, Inspections and Enforcement, 1801 McCormick Drive, Suite 120, Largo, Maryland 20774. Reasons for request and time needed for compliance must be specified.



INSPECTIONS DIVISION

1801 McCormick Drive, Suite 120 Largo, Maryland 20774 (301) 883–3820 • FAX: (301) 883–3873



2 (g/L) N	NOTIO	CE OF VIOLA	ION	
			11 11 11 11 11	
wner/Permittee:				
		City:		
		0"		
		City:		
		SCD#:		
DU LIBOT.	BIOOKT ON.	000 #	1 011116 # .	
☐ Subtitle 28/28-261. Civ	nspection at the address ref vil Citation issued in the amoun CORRECTIVE ACTION REQ			
3				
Compliance Date:	have listed corrective actions	by the compliance data may be as	uso for: (1) a nanalhi ta ba	account against your
Section 23-107 of the Cou cilled to you; (3) the forwar permit from the County, a S	unty Code; (2) the performand rding of the matter to the OFF Stop Work Order will be issue	by the compliance date may be ca ce of the necessary corrective wo FICE of LAW for prosecution. Who d to the permittee for failure to imp g GRADING, DRAINAGE, EROSI	rk by the Department, with the ere the non-compliant work in the plement the corrective meas	the cost of this work to s performed under a va ures within the time fran
rdinances may result in section 28-253.	the issuance of a civil citation	on subjecting you to a FINE of \$2	50,00 or more for each da	y the violation continue
	Issuing Inspector	Person Notified —	Owner/Permittee/Contractor	Date
I.D. #	Inspector Telep			
	Office — Original	Responsible Party — Yellow	Inspector — Pink	

RIGHT OF APPEAL — Subtitle 23, Divisions 1, 2, 3,4 and 5:

Roads and Sidewalks Ordinance

Under County Code Section 23-108, the right to appeal this Notice of Violation is as follows:

- "(a) Prior to the commencement of any appeal, any person aggrieved, with the exception of a person aggrieved under Section 23-117(a), shall, within fifteen (15) days of a decision, action, or nonaction by an authorized representative of the Department, make known in writing the basis of his/her complaint to the individual responsible for the decision, action, or nonaction, together with a request for review. If a satisfactory resolution cannot be reached within fifteen (15) days of the receipt of the written complaint, the person aggrieved may request a review of the decision by the next higher level of authority (Division Chief, Associate Director, Director).
- (b) Any person may file an appeal to the Board of Administrative Appeals within thirty (30) days (except for a Notice of Violation which shall require the appeal to be filed within fifteen (15) days) after the resolution period provided for in Subsection (a), above, or within thirty (30) days after the expiration of a thirty (30) day period allowed for such resolution. No appeal (with the exception of a Notice of Violation) shall be considered by the Board of Administrative Appeals until the person aggrieved has obtained a decision by the Director, or the thirty (30) day period for resolution has passed without such decision."

RIGHT OF APPEAL — Subtitle 32, Divisions 2 and 4:

Floodplain Ordinance — Subtitle 32, Division 2-Section 4-264

An APPEAL of a Violation Notice of the Floodplain Ordinance claiming the true intent of the Ordinance has been misconstrued must be filed WITHIN TEN (10) DAYS OF RECEIPT OF THIS NOTICE.

Stormwater Management Ordinance — Subtitle 32, Division 4 – Section 4-339

An APPEAL of a violation notice of the Stormwater Management Ordinance claiming the true intent of the Ordinance has been misconstrued must be filed WITHIN TEN (10) DAYS OF RECEIPT OF THE NOTICE.

The above APPEALS must be filed with the BOARD OF APPEALS for Prince George's County, County Administration Building, 14741 Governor Oden Bowie Drive, Upper Marlboro, Maryland 20772. Please call (301) 952–3220 for information.

Stop Work Order

An APPEAL of a STOP WORK ORDER may be made to the Director or his/her designee within twenty-four (24) hours as specified in accordance with Prince George's County Code and Basic Codes.

If you have any questions concerning this notice, contact this office at (301) 883-3820 or the issuing Inspector at the number on this notice.

REQUESTS FOR EXTENSION OF COMPLIANCE — Subtitle 32, Division 3:

Grading, Drainage & Erosion Control

All requests for time extensions must be made in writing to the Associate Director, Inspections Division, Department of Permitting, Inspections and Enforcement, 1801 McCormick Drive, Suite 120, Largo, Maryland 20774. Detailed reason(s) for the waiver or request for time extension must be specified.



Prince George's County
Department of Permitting, Inspections and Enforcement
INSPECTIONS DIVISION
1801 McCormick Drive, Suite 120
Largo, Maryland 20774
(301) 883-3820 • FAX: (301) 883-3873



0.0000000000000000000000000000000000000	2000	an extremely v		A 200 CO. 10	VA 0300	
						1
		ECT	1017			3 3

Permit #:	Date:
Type of Inspection:	
	quire correction in order to pass inspection.
Reinspection Fee \$	
☐ Special Investigation Fee \$	
(Please note this may not be a co	mplete listing.)
For inspection requests, call our A System (AIRIS) at (301) 883–539	automated Inspection Request/Information 0.
Inspector:	
	(Signature & ID #)
Phone #:	(Retugan 7:00 a m and 0:00 a m anly)



INSPECTIONS DIVISION

Stormwater Management
1801 McCormick Drive, Suite 120
Largo, Maryland 20774
(301) 883–3820 ◆ FAX: (301) 883–3873



CONSTRUCTION COMPLETION FORM

Name of Project:		
	DPIE Permit No.:	
Project No.:	CIP No.:	
Location of Project:		
Owner or Agency Responsible for Maintenance:		
DESCRIPTION OF SITE Type of Development (i.e., ¼ Acre Residential, Commercial)	al, Industrial, etc.):	
STORMWATER MANAGEMENT PRACTICE(S): (Check Appropriate Practice(s) Constructed and List Quantity)		
☐ On-Site Facility	☐ Oil/Grit Separator	
☐ Off-Site Facility	Retention Basin	
☐ Infiltration Practices	☐ Extended Detention Basin	
☐ Infiltration Basin	☐ Detention Basin	
☐ Trench	☐ Underground Detention	
☐ Dry Well	☐ Storm Drain	
☐ Porous Pavement	☐ "As-Built" Plan on File	
☐ Vegetated Swale	Letter of Certification on File	
Other (Specify Type on Additional Sheet if Necessary):		
	Signature	



INSPECTIONS DIVISION

1801 McCormick Drive, Suite 120 Largo, Maryland 20774 (301) 883–3820 ◆ FAX: (301) 883–3873



INSPECTOR'S CHECKLIST FOR PAVING

Name of Project:		Permit #:
ving Contractor/Asphalt Producer: Plant Location:		Plant Location:
 3. Verify that grade is true to County approved of contamination, excess dust, stone larger than 4. Witness and approve of Proof-rolling but not of the stone of the stone paving, subgrade has to be still firmly 6. Unless otherwise specified, subbase material 7. Before tack-coating, the existing HMA course 8. Before applying tack-coat, utilities must be suited 9. Tack must be applied thinly but evenly on existing 	rs are all on the approxy and Procedures recross section and align 3 inches, mud, froz many days before pacompacted, unaffect I must be CR-6 stone must be free of pud officiently raised to a sting course and all	eceived from you in the pre-construction meeting. gnment. Subgrade soil has to be free of ruts, en materials, and recycled materials. aving, as approvals expire if it rains. ted by weather or construction traffic. e mix with 6• typical compacted thickness. Idled water, milling debris, defects, and trash. Illow for the approved HMA thickness.
During Paving: 1. Observe arriving loads for proper mix size, m 2. Collect and check asphalt delivery tickets for 3. Check HMA temperature while being loaded if 4. Paver to maintain correct line, grade, and cro 5. Paver to maintain calculated speed that minin 6. Rolling to be as continuous as possible, and if 7. Paving equipment and vehicles should be ad 8. Joints should be tight and FLUSH with adjace 9. Mat should have uniform appearance, free of 10. Technician must call Inspector prior to core of 11. Contractor must cut QA cores for the County 12. Contractors must provide 5 cores/mix/day w 13. QA cores shall come with Cores Lab-Analysis 14. Document on CTR & your report: weather co	correct information of into the paver, and/obss slope; and to mirmizes its stop/start rat a consistent "walk equate & sufficient for ent surfaces. Longit for visible marks and dutting & box sampling Inspector on site, and it in the noted locations of the surfaces of the surfaces.	project name, mix ID, tonnage, time, etc.). or behind the roller, after its first pass. simize automatic controls adjustment. novements without depleting its hopper. sing speed" during all compaction stages. or the weather and the job, and leakage free. udinal joints to be overlapped per MD SHA. efects, except for a line along longitudinal joints. g so Inspector can witness it, if available. nd cores for his own mandatory QC testing. unless otherwise instructed by Inspectorpaver box samples with a HMA-1 form.
COMMENTS:	L-16.4	de Control de la
This is to certify that suspected asphalt/paving probler then to the District Engineer and Lab Engineer at make adjustments that may correct, prevent, or reduced to the problem of th	a.m./p.m. of the	
Inspector's Name		Date



Department of Permitting, Inspections and Enforcement

INSPECTIONS DIVISION

1801 McCormick Drive, Suite 120 Largo, Maryland 20774 (301) 883-3820 • FAX: (301) 883-3873



FINAL INSPECTION REPORT Site: Date: Inspector: Permit #: ☐ Revision □ Renewal □ Required Expires: SCD #: Expires: ☐ Revision Renewal Required ☐ Required M-NCPPC Site Plan #: Type: SP DSP SDP Revision ☐ Renewal __ Contractor:____ Notified Owner:____ Other:_ Inspection Type:

Meeting Routine Final Partial Final Follow-up Responsible Party On Site: Yes No Site Activity: Clearing Grading Site Work SWM Utilities Bldg. Road Const. SITE WORK TYPE **APPROVED** CERTIFICATIONS **OBTAINED** Grading/Positive Drainage ☐ No □ N/A ☐ Yes ☐ Yes Site Certification ☐ No ☐ No ☐ N/A Permanent Stabilization ☐ Yes ☐ Yes ☐ No Fill Certification ☐ Yes ☐ No ☐ N/A Landscaping ☐ Yes ☐ No Landscape Certification □ N/A ☐ No ☐ No Retaining Walls ☐ Yes ☐ Yes Retaining Wall Certification ☐ No ☐ N/A ☐ Yes ☐ Yes ☐ No Stormwater Management Structure Certification ☐ No ☐ Yes Parking Lot(s) □ No □ N/A SWM Certification ☐ Yes ☐ Yes ☐ Yes Lighting ☐ No ☐ N/A SWM As-Built Approval ☐ No ☐ N/A Recreational Areas ☐ Yes ☐ No Pipe Certification ☐ Yes ☐ No Handicap Requirements ☐ Yes ☐ No □ N/A Core/Embankment Certification ☐ Yes □ No Street Signs ☐ Yes ☐ No □ N/A Operation Manual ☐ Yes ☐ No Street Trees ☐ Yes ☐ No □ N/A Property Corner Certification ☐ Yes ☐ No TCP II Area(s) ☐ Yes ☐ No ☐ N/A Proof of Payment ☐ Yes ☐ No ☐ Yes CBCA Protection Area(s) ☐ Yes ☐ No ☐ N/A Pepco/Street Lights ☐ No ☐ Yes ☐ No ☐ N/A M-NCPPC Approval ☐ Yes ☐ No NOTE: All work completed requiring certification, must be submitted within 30 days of completion, including but not limited to: ☐ Fills ☐ Pipe ☐ Structure ☐ Embankment/Core ☐ Anti-Seep Collar ☐ Landscaping ☐ Site ☐ ADA Requirements ☐ Retaining Walls ☐ FINAL REJECTED: Items checked above must be complete prior to final inspection approval. ☐ Inspector has no objection to the DPIE Building Inspector issuing a Temporary Occupancy for Units: FINAL INSPECTION APPROVAL REGARDING SEDIMENT CONTROLS ONLY. All areas have permanent stabilization. Final grades, landscaping, other site development building permit final and bond release are the responsibility of the DPIE Building Inspector regarding site development, final grades, landscaping, permanent stabilization, grading permit final and bond release. COMMENTS: All items in non-compliance must be repaired in accordance with all applicable codes, standards, specifications, and the approved plans by the compliance date shown. Failure to comply may result in any or all of the following actions being taken on this site: ENFORCEMENT ACTION TAKEN: ☐ Violation Notice ☐ Stop Work Order ☐ Civil Citation/Amount: \$_____ Compliance Date: ____ Extended From: ___ Permittee Representative Signature

FINAL ACCEPTANCE OF SITE AND BOND RELEASE.

NOTE: All Certifications, Reports, and As-Builts must be submitted within thirty (30) days of performance of work.

The majority of delays associated with final acceptance of site and bond release can be avoided if the following issues are addressed **prior** to final inspection. This "Memorandum of Understanding for Final Acceptance of Site and Bond Release" is **NOT** to be taken as a comprehensive list of permit and plan requirements and does **NOT** waive any provision thereof. **Review the conditions of the permit and approved plans completely!**

DRAINAGE. All graded/disturbed areas must have positive drainage. Surface runoff must discharge acceptably, i.e., across no more than one adjacent lot unless an approved surface drainage easement exists to accommodate its flow into a publicly maintained drainage system, street or continuously flowing natural watercourse. Springs, seeps, or groundwater having objectionable effects must be capped and conveyed into a piped outfall to a public drainage system or continuously flowing natural watercourse.

FILLS. All Class I & II fills or other structural fill soils placed on site shall be certified by a licensed Maryland Professional Engineer certifying acceptable placement and compaction including necessary supporting documentation. The certification shall include the permit number, address of the site, and P.E. seal with registration number.

FINAL REPORT/SITE CERTIFICATION. A certification must be submitted from a licensed Maryland Professional Engineer certifying, "all grading and site development has been completed in accordance with the plans and Subtitle 4, Division 3 of the Prince George's County ordinance." The certification shall include the permit number, address of the site, and P.E. seal with registration number. The Final Report shall include any and all approved waivers.

GRADING. All grades and final elevations must be in accordance with the approved Grading/Site Development Plans and Subtitle 4, Division 3, Grading Ordinance. Any modifications must be authorized by waiver or approved revisions to the plan.

LANDSCAPING/WOODLAND CONSERVATION. All requisite landscaping, reforestation, afforestation, and wetland plantings shall be completed in accordance with the approved Landscaping and/or TCP II plans, including location(s), size, type and quantity. Any substitutions shall be approved in writing by M-NCPPC. All landscaping shall be properly labeled for inspection. A Landscaping Certification shall be submitted by a licensed Maryland Professional Engineer.

STREETS, LIGHTING & PARKING LOT/MAC/ADA ACCESSIBILITY REQUIREMENTS. Are all lighting and surface pavings completed? Does the parking space layout and number of parking spaces agree with the approved plan? Are parking spaces properly sized (standard = 9.5 x 19 ·; compact = 8 · x 16.5 ·; handicapped = 13 · x 19 · or 5 · access lane with 8 · parking space)? Are the handicapped signs properly installed? Are the handicapped curb cuts/ramps installed for free access? Are all other MAC/ADA accessibility requirements met?

RECREATIONAL AREAS. Have all recreational areas, i.e., open play areas, tot-lots, hiker/biker trails been properly installed? Has the M-NCPPC given final inspection approval and acceptance of the recreational requirements? If yes, provide copies of written final inspection approval of all recreational areas to the inspector. If no, obtain M-NCPPC written final inspection approval.

REQUIRED REVISIONS TO PERMIT/PLANS. All plans and permits must reflect current and approved information. Any deviations from the plans must be approved through a waiver or appropriate plan revision. This applies to all plans and permits associated with the project, to include permit revisions/upgrades to incorporate the Site Development Plan, the Stormwater Management Plan, the Landscaping Plan, and others.

<u>SEDIMENT CONTROLS.</u> All storm drain systems and outfalls (riprap, grassed waterways, etc.) must be free of sediment. All areas must be permanently stabilized to prevent erosion. All erosion and sediment controls must be removed. *NOTE:* Obtain written authorization from the Inspector BEFORE removing any sediment controls.

SITE DEVELOPMENT. Site Development shall be completed in accordance with the approved plans prior to granting occupancy of any building or structure on site. Adequate and acceptable completion of recreational facilities, landscaping, parking, lighting, retaining walls, and other site work may occur with the progress of the development of any project as determined by the Director. Ensure any changes or deviations to the permit plans are approved and reflected on revised plans and permits.

STABILIZATION. All areas MUST have acceptable PERMANENT STABILIZATION well established prior to final acceptance. Poor soil areas may require a minimum of 4. of acceptable topsoil. NOTE: Excessive weeds throughout the grass cover is NOT acceptable.

STORMWATER MANAGEMENT. Refer to the approved plans and Prince George's County Stormwater Management Design Manual for Final Acceptance requirements on SWM facilities. Typical certifications and reports may include:

NOTE: All Certifications, Reports, and As-Builts must be submitted within thirty (30) days of performance of work.

TRASH/DEBRIS. All objectionable and/or waste materials (excess spoil material, dead trees, tree limbs, stumps, building trash/materials) must be removed from the site to an authorized disposal facility.

TREE SAVE AREAS/LIMITS OF DISTURBANCE. All tree save areas and limits of disturbance must be adhered to per the approved plan. Any deviations from the approved limits of disturbance must be reflected via approved plan revisions.

<u>VIOLATIONS/COMPLAINTS.</u> Any outstanding violations/complaints must be closed prior to final inspection approval and subsequent bond release.



INSPECTIONS DIVISION

1801 McCormick Drive, Suite 120 Largo, Maryland 20774 (301) 883–3820 • FAX: (301) 883–3873



SITE GRADING CERTIFICATION

Job Address:	
Lot:	Block:
Building Permit #:	
grading, drainage, erosion corwater quality facilities, woodlar have been completed in acc Maryland-National Capital Park	est of my knowledge, information and belief that all atrol facilities, landscaping, stormwater management, and conservation and other site work at this address cordance with the permit, approved plans, and the cand Planning Commission approved detailed site, tree plans dated () and revised on the permit as noted. Insert Date
SEAL	Signature
OLAL	Print Name
	Date



INSPECTIONS DIVISION

1801 McCormick Drive, Suite 120 Largo, Maryland 20774 (301) 883-3820 • FAX: (301) 883-3873



LANDSCAPING CERTIFICATION

Job Address:	
Lot:	Block:
Building Permit #:	
landscaping on the above-reference plans, and latest revision to the Commission approved detailed sit	t of my knowledge, information and belief that all ced site is in accordance with the permit, approved e Maryland-National Capital Park and Planning te, tree conservation, and landscaping plans dated ed on (), except as noted.
Exceptions:	
	Signature
SEAL	Print Name
	Date



INSPECTIONS DIVISION

1801 McCormick Drive, Suite 120 Largo, Maryland 20774 (301) 883-3820 • FAX: (301) 883-3873



STRUCTURE LOCATION CERTIFICATION

Job Address:				
Lot:	Block:			
Building Permit #:				
This is to certify to the best of my knowledge, information and belief that all property corner markers have been set in accordance with Section 24-120 of the Prince George's County Subdivision Code with regard to the above-referenced permit and that the structure(s) on said lot are in compliance with the permit, approved plans, and the Maryland–National Capital Park and Planning Commission approved detailed site, tree conservation, and landscaping plans dated () and revised on (), except as noted.				
Exceptions:				
-				
	Signature			
SEAL	Print Name			
	Date			



INSPECTIONS DIVISION

1801 McCormick Drive, Suite 120 Largo, Maryland 20774 (301) 883-3820 • FAX: (301) 883-3873



FILL/SOIL CERTIFICATION

Job Address:	
Lot:	Block:
Permit #:	
attached compaction test resul all Class #1 and/or Class #2 fill placed and compacted as req	of my knowledge, information and belief, and based on the stand documentation prepared by our representatives as delineated on the approved plans has been properly uired in accordance with Subtitle 32, Division 3 of the on the above referenced permit(s).
Exceptions:	
	Signature
SEAL	Print Name
	Date

CONSTRUCTION INSPECTION FLOW CHART

To Be Provided Later

SAMPLE PUNCHLIST

TO BE PROVIDED LATER

CONSTRUCTION INSPECTION CHECKLISTS

A-1	Green Roofs
A-2	Permeable Pavements
A-3	Reinforced Turf
F-1	Surface Sand Filter (Mostly Montgomery County
F-2	Underground Sand Filter
F-3	Perimeter Sand Filter
F-4	Organic Filter
F-5	Pocket Sand Filter
F-6	Bioretention
I-1	Infiltration Trench
M-1	Rainwater Harvesting
M-2	Submerged Gravel Wetlands
M-3	Landscape Infiltration
M-4	Infiltration Berms
M-5	Dry Wells
M-6	Micro-Bioretention
M-7	Rain Gardens
M-8	Swales
M-9	Enhanced Filters
N-1	Disconnection of Rooftop Runoff
N-2	Disconnection of Non-Rooftop Runoff
N-3	Sheet flow to Conservation Areas
P Series	MD-378 Ponds
W-1	Shallow Wetland
W-2	ED Shallow Wetland
W-3	Pond/Wetland System
W-4	Pocket Wetland
Z-1	Underground SWM
Z-2	Hydrodynamic Structures
Z-3	Oil Grit Separators
Z-4	Storm Drain



Department of Permitting, Inspections and Enforcement

SITE/ROAD PLAN REVIEW DIVISION

9400 Peppercorn Place Largo, Maryland 20774 301.636.2060 ◆ FAX: 301.925.8510

GREENROOF CONSTRUCTION INSPECTION CHECKLIST

This checklist serves as a guide for permittee and DPIE Site/Road Inspector to review construction progress verify acceptance before acceptance of device.

Site/Project Name:	Date:		
Field Engineer:	Permittee:		
Permit No:	Structure Number:		
DESCRIPTION OF STAGE		DPIE	PERMITTEE
Preconstruction Meeting: Inspection and approval of required at these points prior to proceeding with construction. Contact the DPIE Site/Road Inspector withours' notice (DPIE telephone: 301-883-3820 or the autorequest system at 301-883-5390). The DPIE Site/Rowaive an inspection and allow the permittee per a prior arrangement. Work completed without DPIE approval permittee having to remove and reconstruct the unapper of the steps listed below must be verified by either the Inspector and/or the Permittee.	the next step of th twenty-four (24) comated inspection ad Inspector may written scheduled may result in the roved work. Each the DPIE Site/Road		
	rly installed before		
2. The soil media, depth, and dimensions matches pla	an.		
3. Plant material conforms to approved plans.			
For SWM Certification Only.			
Total area of Green Roof installed for this inspection:		sf	
Required inspection by DPIF Site/Road Inspector			



Department of Permitting, Inspections and Enforcement

SITE/ROAD PLAN REVIEW DIVISION

9400 Peppercorn Place Largo, Maryland 20774

301.636.2060 ◆ FAX: 301.925.8510

PERMEABLE PAVEMENT CONSTRUCTION INSPECTION CHECKLIST

This checklist serves as a guide for permittee and DPIE Site/Road Inspector to review construction progress verify acceptance before acceptance of device.

Site/Project Name: _____ Date: ____

Field Engineer:	Permittee:		
Permit No:	Structure Numb	er:	
DESCRIPTION OF STAGE		DPIE	PERMITTEE
Preconstruction Meeting: Inspection and approval is required at these points prior to proceeding with construction. Contact the DPIE Site/Road Inspector (24) hours' notice (DPIE telephone: 301-883-3820 conspection request system at 301-883-5390). The Inspector may waive an inspection and allow the permitten scheduled arrangement. Work completed approval may result in the permittee having to remove the unapproved work. Each of the steps listed below by either the DPE Site/Road Inspector and/or the Passigns and their assign.	the next step of with twenty-four or the automated DPIE Site/Road mittee per a prior I without DPIE and reconstruct must be verified		
Contributing drainage area is stabilized.			
Excavation to subgrade of permeable pavements approved plans.	ent conforms to		
3. Scarify or till the bottom to a depth of 3-4"			
Install geo-textile fabric, if required by planPlacement of any drainage or distribution systems well conforms to approved plans.	and observation		
Placement of backfilling stone sub base, so conforms to approved plans. Compact using vibra			
Placement of surface permeable paving mate approved plans.	rial conforms to		
Final inspection of grading and permanent stabil to approved plans.	ization conforms		

Total area of Permeable Paving installed for this inspection:



Department of Permitting, Inspections and Enforcement

SITE/ROAD PLAN REVIEW DIVISION



9400 Peppercorn Place Largo, Maryland 20774 301.636.2060 ◆ FAX: 301.925.8510

REINFORCED TURF CONSTRUCTION INSPECTION CHECKLIST

This checklist serves as a guide for permittee and DPIE Site/Road Inspector to review construction progress verify acceptance before acceptance of device.

Site/Project Name: _____ Date: ____

Field E	Engineer: Permittee:		
Permit	No: Structure N	Number:	
DESC	CRIPTION OF STAGE	DPIE	PERMITTEE
require const (24) I inspe Inspe writte approach	datory Notification: Inspection and approval of each practice red at these points prior to proceeding with the next step truction. Contact the DPIE Site/Road Inspector with twenty-for hours 'notice (DPIE telephone: 301-883-3820 or the automatication request system at 301-883-5390). The DPIE Site/Road Ector may waive an inspection and allow the permittee per a prior scheduled arrangement. Work completed without DF oval may result in the permittee having to remove and reconstructional results in the permittee having to remove and reconstructional results in the permittee having to remove and reconstructional results in the permittee having to remove and reconstructional results in the permittee having to remove and reconstructional results in the permittee having to remove and reconstruction remove and reconstruction remove and reconstruction remove and reconstruction remove and reconstruction remove and reconstruction remove and reconstruction remove and reconstruction remove and reconstruction remove and reconstruction remove and reconstruction remove and reconstruction remove and reconstruction remove and reconstruction remove and remove and reconstruction remove and reconstruction remove and remove and remove remove and remove remove and remove remove remove and remove remov	of bur ted pad rior PIE uct	
_	Contributing drainage area is stabilized.		
а	xcavation to subgrade of permeable pavement site disturbar nd subgrade soil compaction conforms to approved plans.	nce	
	scarify or till the bottom to a depth of 3-4"		
	nstall geo-textile fabric, if required by plan		
	Placement of any drainage or distribution systems a bservation well conforms to approved plans.	ind	
	Placement of backfilling stone sub base, sand, and gra onforms to approved plans.	vel	
	Placement of surface material conforms to approved plans.		
	inal inspection of grading and permanent stabilizations confort paperoved plans.	ms	
Total a	area of Reinforced Turf installed for this inspection:		sf

Required inspection by DPIE Site/Road Inspector.

Date Issued: July 26, 2014



Department of Permitting, Inspections and Enforcement

SITE/ROAD PLAN REVIEW DIVISION

INSPECTIONS AND ENFORCEMENT

9400 Peppercorn Place Largo, Maryland 20774

301.636.2060 ◆ FAX: 301.925.8510

SURFACE SAND FILTER CONSTRUCTION INSPECTION CHECKLIST

This checklist serves as a guide for permittee and DPIE Site/Road Inspector to review construction progress verify acceptance before acceptance of device.

NOTE: PLANS SUBMITTED WITHOUT A COMPLETED CHECKLIST MAY BE RETURNED WITHOUT

REVIEW. Site/Project Name: _____ Date: ____ Field Engineer: Permittee: Permit No:______ Structure Number: _____ DESCRIPTION OF STAGE DPIE PERMITTEE

Preconstruction Meeting: Inspection and approval of each practice is	
required at these points prior to proceeding with the next step of	
construction. Contact the DPIE Site/Road Inspector with twenty-four (24)	
hours' notice (DPIE telephone: 301-883-3820 or the automated inspection	
request system at 301-883-5390). The DPIE Site/Road Inspector may	
waive an inspection and allow the permittee per a prior written scheduled	
arrangement. Work completed without DPIE approval may result in the	
permittee having to remove and reconstruct the unapproved work. Each of	
the steps must be verified by either the DPIE Site/Road Inspector and/or	
the Permittee and the completed form submitted with the as-built drawings.	
Clearing, grubbing and subgrade preparation.	
2. Core trench excavation and dewatering core trench installation with	
dimensions, location, backfill, and compaction testing.	
3. Construction of berm including lifts, compaction tests, and soil material,	
if required.	
4. Underdrain location, observation well(s) and/or cleanouts, pipe size,	
filter cloth, gravel, and field adjustments to materials.	
5. Installation of sand and/or any additional geotextiles required.**	
6. Installation of top soil, stone, and geotextiles, if required.**	
7. Installation of principal spillway riser and/or trash racks, if required.	
8. Channelization work and outlet protection, if required. Permanent	
vegetative stabilization.	
9. Unblock any storm drain draining to facility with DPIE inspector's written	
approval. Install any necessary trash racks with flow splitter structures.	
10. Final inspection and material delivery tickets provided to inspector.	

Total number of Surface Sand Filter(s) installed for this inspection:

^{**} Installation of an impermeable protective cover may be required by the County Inspector upon completion of filter media placement.



Department of Permitting, Inspections and Enforcement

SITE/ROAD PLAN REVIEW DIVISION

9400 Peppercorn Place Largo, Maryland 20774 301.636.2060 ◆ FAX: 301.925.8510



ORGANIC FILTER CONSTRUCTION INSPECTION CHECKLIST

This checklist serves as a guide for permittee and DPIE Site/Road Inspector to review construction progress verify acceptance before acceptance of device.

Site/Project Name:	Date:		
Field Engineer: Permitte			
Permit No:	Structure Number:		
DESCRIPTION OF STAGE		DPIE	PERMITTEE
Preconstruction Meeting: Inspection and approval	of each practice is		
required at these points prior to proceeding with			
construction. Contact the DPIE Site/Road Inspector w			
hours' notice (DPIE telephone: 301-883-3820 c			
inspection request system at 301-883-5390). The			
Inspector may waive an inspection and allow the pe			
written scheduled arrangement. Work completed with			
may result in the permittee having to remove ar			
unapproved workEach of the steps must be verified			
Site/Road Inspector and/or the Permittee and the	e completed form		
submitted with the as-built drawings			
 Clearing, grubbing and subgrade preparation. Core trench excavation and dewatering core tre 	nch installation with		
dimensions, location, backfill, and compaction testing.			
Construction of berm including lifts, compacting			
material, if required.	on tooto, and con		
4. Underdrain location, observation well(s) and/or c	leanouts, pipe size.		
filter cloth, gravel, and field adjustments to materia			
5. Installation of sand and/or any additional geotextile			
6. Installation of top soil, stone, and geotextiles, if red	quired.**		
7. Installation of principal spillway riser and/or trash r	acks, if required.		
8. Channelization work and outlet protection, if re-	equired. Permanent		
vegetative stabilization.			
9. Unblock any storm drain draining to facility wit			
written approval. Install any necessary trash rac	ks with flow splitter		
structures.			
10. Final inspection and material delivery tickets provi	ded to inspector.		
Notes:		. 41 0	to la sa saterio e e
1 .** Installation of an impermeable protective cov	er may be required by	tne Cour	ity inspector upon
completion of filter media placement.	-t:		
Total number of Organic Filter(s) installed for this inspe-	Cuon:		

Required inspection by DPIE Site/Road Inspector.

Date Issued: July 26, 2014



Department of Permitting, Inspections and Enforcement

SITE/ROAD PLAN REVIEW DIVISION

9400 Peppercorn Place Largo, Maryland 20774 301.636.2060 ◆ FAX: 301.925.8510

POCKET SAND FILTER CONSTRUCTION INSPECTION CHECKLIST

Site/Project Name:	Date:		
Field Engineer:	Permittee:		
Permit No:	Structure Numb	er:	
DESCRIPTION OF STAGE		DPIE	PERMITTEE
Preconstruction Meeting: Inspection and ap is required at these points prior to proceeding construction. Contact the DPIE Site/Road Ins (24) hours' notice (DPIE telephone: 301-883-inspection request system at 301-883-5390) Inspector may waive an inspection and allow the written scheduled arrangement. Work con approval may result in the permittee having to the unapproved work. Each of the steps must DPIE Site/Road Inspector and/or the Permitt form submitted with the as-built drawings. 1. Clearing, grubbing and subgrade preparations. 2. Core trench excavation and dewatering condimensions, location, backfill, and compact	g with the next step of spector with twenty-four 3820 or the automated. The DPIE Site/Road he permittee per a prior impleted without DPIE remove and reconstruct be verified by either the tee and the completed on.		
Construction of berm including lifts, commaterial, if required.	npaction tests, and soil		
Underdrain location, observation well(s) size, filter cloth, gravel, and field adjustments	its to materials.		
5. Installation of sand and/or any additional ge			
6. Installation of top soil, stone, and geotextile7. Installation of principal spillway riser and/or			
8. Channelization work and outlet protection vegetative stabilization.	, if required. Permanent		
Unblock any storm drain draining to facility written approval. Install any necessary tras			
structures.			

Total number of Pocket Sand Filter(s) installed for this inspection:_



Department of Permitting, Inspections and Enforcement

SITE/ROAD PLAN REVIEW DIVISION

N DEPARTMENT OF PERMITTING, INSPECTIONS AND ENFORCEMEN

9400 Peppercorn Place Largo, Maryland 20774 301.636.2060 ◆ FAX: 301.925.8510

RAINWATER HARVESTING CONSTRUCTION INSPECTION CHECKLIST

This checklist serves as a guide for permittee and DPIE Site/Road Inspector to review construction progress verify acceptance before acceptance of device.

Site/Project Name: _____ Date: ____

Field Engineer: Pe	ermittee:		
Permit No: St	ructure Numbe	r:	
DESCRIPTION OF STAGE		DPIE	PERMITTEE
Preconstruction Meeting: Inspection and approval of ear required at these points prior to proceeding with the construction. Contact the DPIE Site/Road Inspector with (24) hours' notice (DPIE telephone: 301-883-3820 or the inspection request system at 301-883-5390). The DPI Inspector may waive an inspection and allow the permitted written scheduled arrangement. Work completed without D may result in the permittee having to remove and required work. Each of the steps listed below must be either the DPIE Site/Road Inspector and/or the Permittee.	next step of n twenty-four e automated E Site/Road re per a prior PIE approval construct the		
Excavation conforms to plan, if applicable.			
 Placement of support base per plan. Distribution system installed per plan. All pipes from roof are directed to device 			
Mosquito screens and overflow device installed.			
Test of distribution system per specifications requirements.	and code		
Total number of Cistern(s) installed for this inspection:			



Site/Project Name:

Prince George's County

Department of Permitting, Inspections and Enforcement

SITE/ROAD PLAN REVIEW DIVISION



9400 Peppercorn Place Largo, Maryland 20774 36 2060 ◆ FAX: 301 925

301.636.2060 ◆ FAX: 301.925.8510

SUBMERGED GRAVEL WETLAND CONSTRUCTION INSPECTION CHECKLIST

This checklist serves as a guide for permittee and DPIE Site/Road Inspector to review construction progress verify acceptance before acceptance of device.

Date:

Field Engineer:	Permittee:		
Permit No:	Structure Number	er:	
DESCRIPTION OF STAGE		DPIE	PERMITTEE
Mandatory Notification: Inspection and approval of erequired at these points prior to proceeding with the construction. Contact the DPIE Site/Road Inspector w (24) hours' notice (DPIE telephone: 301-883-3820 or inspection request system at 301-883-5390). The DInspector may waive an inspection and allow the permit written scheduled arrangement. Work completed approval may result in the permittee having to remove at the unapproved work. Each of the steps must be verified DPE Site/Road Inspector and/or the Permittee on the their assign.	e next step of with twenty-four the automated PIE Site/Road ttee per a prior without DPIE and reconstructed by either the		
Excavation to subgrade conforms to approved plans	i.		
 Wetland construction within an access of wetlan shall be performed with lightweight, wide tracked minimize disturbance and compaction. Excavated be placed in a contained area. Any pumping of discharge filtered water to a stable outlet. 	equipment to materials shall perations shall		
Placement of backfill of perforated inlet pipe and of conforms to approved plans.	bservation well		
Placement of geotextile, filter fabric, and backfilling sand and gravel conforms to approved plans.	of filter media,		
Construction of any appurtenant conveyance sys diversion structures, inlets, outlets, and flow distribution conforms to approved plans.	ution structures		
6. Final inspection of grading and establishment stabilization conform to approved plans.	of permanent		
Total number of Submerged Gravel Wetland(s) installed f	or this inspection	:	sf



Department of Permitting, Inspections and Enforcement

SITE/ROAD PLAN REVIEW DIVISION

DPIE

DEPARTMENT OF PERMITTING, INSPECTIONS AND ENFORCEMENT

9400 Peppercorn Place Largo, Maryland 20774 301.636.2060 ◆ FAX: 301.925.8510

LANDSCAPE INFILTRATION CONSTRUCTION INSPECTION CHECKLIST

This checklist serves as a guide for permittee and DPIE Site/Road Inspector to review construction progress

/erif	fy acceptance before acceptance of device.			
Site/	/Project Name: Date:			
-ielo	d Engineer: Permitt	ee:		
	mit No: Structu			
DE	SCRIPTION OF STAGE		DPIE	PERMITTEE
is incorrection (24) insolated insol	required at these points prior to proceeding with the next sonstruction. Contact the DPIE Site/Road Inspector with twenth hours' notice (DPIE telephone: 301-883-3820 or the autopection request system at 301-883-5390). The DPIE Site spector may waive an inspection and allow the permittee per ten scheduled arrangement. Work completed without proval may result in the permittee having to remove and record unapproved work. Each of the steps listed below must be verified in the permittee of signs and their assign.	step of hty-four omated e/Road a prior DPIE nstruct /erified		
	Excavation to subgrade conforms to approved plans.			
2.	Placement of filter fabric, backfilling of sand, gravel, obse well, and soil filter media conforms to approved plans.	rvation		
	Construction of appurtenant conveyance structures conformapproved plans.			
4.	Final inspection of grading and establishment of pern stabilization and landscape installation conforms to applans			

Total number of Landscape Infiltration Device(s) installed for this inspection:_____sf



Site/Project Name:

Prince George's County

Department of Permitting, Inspections and Enforcement

SITE/ROAD PLAN REVIEW DIVISION

DPIE

DEPARTMENT OF PERMITTING, INSPECTIONS AND ENFORCEMENT

9400 Peppercorn Place Largo, Maryland 20774 301.636.2060 ◆ FAX: 301.925.8510

INFILTRATION BERM CONSTRUCTION INSPECTION CHECKLIST

Date:

This checklist serves as a guide for permittee and DPIE Site/Road Inspector to review construction progress verify acceptance before acceptance of device.

Field Engineer:	Permittee:		
Permit No:	Structure Number:	:	
DESCRIPTION OF STAGE		PIE	PERMITTEE
Mandatory Notification: Inspection and approval of expeditive required at these points prior to proceeding with the construction. Contact the DPIE Site/Road Inspector w (24) hours' notice (DPIE telephone: 301-883-3820 or inspection request system at 301-883-5390). The DI Inspector may waive an inspection and allow the permit written scheduled arrangement. Work completed approval may result in the permittee having to remove a the unapproved work. Each of the steps must be verified DPIE Site/Road Inspector and/or the Permittee on the their assign.	e next step of ith twenty-four the automated PIE Site/Road tee per a prior without DPIE nd reconstruct d by either the ir assigns and		
 Excavation to subgrade and soil compaction conform plans. 			
2. Placement of backfilling of sand, gravel, and soil m to approved plans.	edia conforms		
 Final inspection of grading and establishment stabilization, verify landscape installation conforms plans. 			
Total length of Infiltration Berm installed for this inspection	:		



Department of Permitting, Inspections and Enforcement

SITE/ROAD PLAN REVIEW DIVISION

DPIE

DEPARTMENT OF PERMITTING,
INSPECTIONS AND ENFORCEMENT

9400 Peppercorn Place Largo, Maryland 20774 301.636.2060 ◆ FAX: 301.925.8510

DRY WELL CONSTRUCTION INSPECTION CHECKLIST

This checklist serves as a guide for permittee and DPIE Site/Road Inspector to review construction progress verify acceptance before acceptance of device.

Site/Project Name: _____ Date: _____

Field Engineer: Permittee:	Permittee:	
Permit No: Structure N	Structure Number:	
DESCRIPTION OF STAGE	DPIE	PERMITTEE
Preconstruction Meeting: Inspection and approval of each pract	ice	
is required at these points prior to proceeding with the next step		
construction. Contact the DPIE Site/Road Inspector with twenty-fe		
(24) hours' notice (DPIE telephone: 301-883-3820 or the automatical control of the automatical control of the automatical control of the cont		
inspection request system at 301-883-5390). The DPIE Site/Ro		
Inspector may waive an inspection and allow the permittee per a pr		
written scheduled arrangement. Work completed without DF		
approval may result in the permittee having to remove and reconstrute unapproved work. Each of the steps must be verified by either the		
DPIE Site/Road Inspector and/or the Permittee on their assigns.	iiie	
Excavation to subgrade for Dry Well and verify size conforms	to	
approved plans.		
2. Placement of geotextile fabric, sand, gravel, pipe distribut	ion	
system, and observation well conforms to approved plans.		
3. Connecting pipes, including connection to downspout, construct	ted	
per the approved plans.		
4. Installation of final cover gravel surface to be completely cover	red	
with backfill and top soil.		
5. Final inspection of grading and permanent stabilization conformation	ms	
to approved plans.		

Required inspection by DPIE Site/Road Inspector.

Total number of Dry Well(s) installed for this inspection:



Department of Permitting, Inspections and Enforcement

SITE/ROAD PLAN REVIEW DIVISION



9400 Peppercorn Place Largo, Maryland 20774 301.636.2060 ◆ FAX: 301.925.8510

MICRO BIORETENTION/BIORETENTION CONSTRUCTION INSPECTION CHECKLIST

progress verify acceptance before acceptance of device		ispector to re	view construction
Site/Project Name:	_ Date:		
Field Engineer:	_ Permittee:		
Permit No:			
DESCRIPTION OF STAGE		DPIE	PERMITTEE
Preconstruction Meeting: Inspection and approval is required at these points prior to proceeding with a construction. Contact the DPIE Site/Road Inspector (24) hours' notice (DPIE telephone: 301-883-3820 of inspection request system at 301-883-5390). The Inspector may waive an inspection and allow the permitten scheduled arrangement. Work completed approval may result in the permittee having to remove the unapproved work. Each of the steps must be verift DPIE Site/Road Inspector and/or the Permittee on the their assign.	the next step of with twenty-four r the automated DPIE Site/Road nittee per a prior without DPIE and reconstruct ied by either the peir assigns and		
 Excavation for micro bioretention facility conformation plans. 	ns to approved		
2. Placement of stone backfill and underdrain dist observation well and cleanout conforms to approve			
Placement of sand, gravel, and soil filter media at filter fabric conforms to approved plans.	nd installation of		
4. Connecting pipes, and/or grading conveyance constructed per the approved plans.	to the facility		
Final inspection of grading mulch and permanent landscape installation conforms to approved plans.			

Total number of Micro Bioretention facilities installed for this inspection: _____s



Department of Permitting, Inspections and Enforcement

SITE/ROAD PLAN REVIEW DIVISION



9400 Peppercorn Place Largo, Maryland 20774 301.636.2060 ◆ FAX: 301.925.8510

RAIN GARDENS CONSTRUCTION INSPECTION CHECKLIST

Site/Project Name:	Date:		
Field Engineer:	Permittee:		
Permit No:	Structure Number	:	
DESCRIPTION OF STAGE	[PIE	PERMITTEE
is required at these points prior to proceeding construction. Contact the DPIE Site/Road Inspect24) hours' notice (DPIE telephone: 301-883-38 inspection request system at 301-883-5390). Inspector may waive an inspection and allow the written scheduled arrangement. Work compapproval may result in the permittee having to retthe unapproved work. Each of the steps must be DPIE Site/Road Inspector and/or the Permittee their assign. 1. Excavation to subgrade of rain garden facility 2. Placement of soil filter media conforms to ap soils are encountered beneath the rain gard washed gravel (1/4 to 3/4 -inch gravel preferred the planting soil mix.	ector with twenty-four 20 or the automated The DPIE Site/Road permittee per a prior eleted without DPIE move and reconstruct everified by either the on their assigns and proved plans. If poor den, a 4-inch layer of		
 Final inspection of grading and establish stabilization and landscape installation co plans. 	informs to approved		
 4. Connecting pipes, and/or grading convey constructed per the approved plans. 5. Final inspection of grading mulch and perma landscape installation conforms to approved provided the conforms of the conforms of the conforms of the conforms of the conforms of the conforms of the conforms of the conforms of the conforms of the conforms of the conforms of the conforms of the conformation	nent stabilization and		



Department of Permitting, Inspections and Enforcement

SITE/ROAD PLAN REVIEW DIVISION



9400 Peppercorn Place Largo, Maryland 20774 301.636.2060 ◆ FAX: 301.925.8510

SWALE CONSTRUCTION INSPECTION CHECKLIST

This checklist serves as a guide for permittee and DPIE Site/Road Inspector to review construction progress verify acceptance before acceptance of device.

Site/Project Name:	Date:		
Field Engineer:	Permittee:		
Permit No:	_ Structure Numbe	er:	
DESCRIPTION OF STAGE	1	OPIE	PERMITTEE
 Mandatory Notification: Inspection and approval of e required at these points prior to proceeding with the construction. Contact the DPIE Site/Road Inspector w (24) hours' notice (DPIE telephone: 301-883-3820 or inspection request system at 301-883-5390). The DInspector may waive an inspection and allow the permitwritten scheduled arrangement. Work completed approval may result in the permittee having to reconstruct the unapproved work. Each of the steps mby either the DPE Site/Road Inspector and/or the Perassigns and their assign. 1. Excavation to swale subgrade conforms to approve 2. Placement of underdrains and installation of obcleanout, check dams, or weirs conform to approve 3. Placement of backfill of sand, gravel and soil, if approved Installation of final cover surface to be completed backfill and top soil. 5. Final inspection of grading and permanent stabilize to approved plans. 	e next step of with twenty-four the automated PIE Site/Road ttee per a prior without DPIE remove and must be verified emittee on their ed plans. Servation well, ed plans. Dicable. y covered with		
Total length of Swale(s) installed for this inspection:		lf	
Required inspection by DPIE Site/Road Inspector.			

Date Issued: July 26, 2014



Department of Permitting, Inspections and Enforcement

SITE/ROAD PLAN REVIEW DIVISION



9400 Peppercorn Place Largo, Maryland 20774

207/4 301.636.2060 ♦ FAX: 301.925.8510

This checklist serves as a guide for permittee and DPIE Site/Road Inspector to review construction

DISCONNECT ROOFTOP & NON ROOFTOP CONSTRUCTION INSPECTION CHECKLIST

progress verify acceptance before acceptance of device.			
Site/Project Name:	_ Date:		
Field Engineer:	Permittee:		
Permit No:	Structure Numb	er:	
	_		
DESCRIPTION OF STAGE		DPIE	PERMITTEE
Preconstruction Meeting: Inspection and approval of is required at these points prior to proceeding with the construction. Contact the DPIE Site/Road Inspector of (24) hours' notice (DPIE telephone: 301-883-3820 or inspection request system at 301-883-5390). The Inspector may waive an inspection and allow the permitten scheduled arrangement. Work completed approval may result in the permittee having to remove the unapproved work. Each of the steps must be verification.	he next step of with twenty-four the automated DPIE Site/Road littee per a prior without DPIE and reconstruct		
NON-ROOFTOP DISCONNECTION "The constructed Non-Rooftop Disconnection(s) meet to plans."	the conditions spe	cified on the a	approved
Permittee Signature Date		_	
ROOFTOP DISCONNECTION			
"The constructed Rooftop Disconnection(s) meet the co	onditions specified	l on the appro	ved plans."
Permittee Signature Date			
Total number of Disconnect Rooftop or Non Rooftop inst	alled for this inspe	ection:	



Department of Permitting, Inspections and Enforcement

SITE/ROAD PLAN REVIEW DIVISION



9400 Peppercorn Place Largo, Maryland 20774 301.636.2060 ◆ FAX: 301.925.8510

SHEET FLOW TO CONSERVATION AREA CONSTRUCTION INSPECTION CHECKLIST

This checklist serves as a guide for permittee and DPIE Site/Road Inspector to review construction progress verify acceptance before acceptance of device.

Site/Project Name:	Date:		
Field Engineer:	Permittee:		
Permit No:	Structure Numb	er:	
DESCRIPTION OF STAGE		DPIE	PERMITTEE
Mandatory Notification: Inspection and approval of e required at these points prior to proceeding with the construction. Contact the DPIE Site/Road Inspector w (24) hours' notice (DPIE telephone: 301-883-3820 or inspection request system at 301-883-5390). The DInspector may waive an inspection and allow the permi written scheduled arrangement. Work completed approval may result in the permittee having to remove a the unapproved work. Each of the steps must be verified DPIE Site/Road Inspector and/or the Permittee on the their assign.	e next step of with twenty-four the automated PIE Site/Road ttee per a prior without DPIE and reconstructed by either the pir assigns and		
Site disturbance, tilling, and conservation area is clear the field prior to commencement of grading on the sapproved plan.			
Final inspection of grading and stabilization to wh approved plans.	ich conform to		
Total length of Sheet Flow installed for this inspection:			

❖ Required inspection by DPIE Site/Road Inspector.

Date Issued: July 26, 2014



Department of Permitting, Inspections and Enforcement

SITE/ROAD PLAN REVIEW DIVISION

DPIE

DEPARTMENT OF PERMITTING, INSPECTIONS AND ENFORCEMENT

9400 Peppercorn Place Largo, Maryland 20774 301.636.2060 ◆ FAX: 301.925.8510

MD-378 POND INSPECTION CHECKLIST

This checklist serves as a guide for permittee and DPIE Site/Road Inspector to review construction progress verify acceptance before acceptance of device.

Site/Project Name: _____ Date: ____

Field Engineer:	Permittee:		
Permit No:	Structure Numbe	r:	
DESCRIPTION OF STAGE		DPIE	PERMITTEE
Preconstruction Meeting: Inspection and approval is required at these points prior to proceeding with construction. Contact the DPIE Site/Road Inspector (24) hours' notice (DPIE telephone: 301-883-3820 conspection request system at 301-883-5390). The Inspector may waive an inspection and allow the permitten scheduled arrangement. Work completed approval may result in the permittee having to remove the unapproved work. Each of the steps must be verified the unapproved work. Each of the steps must be verified in the permittee. 1. Pre-construction meeting & field review of tree supprotection 2. Sediment control installation including dewater diversion 3. Clearing, grubbing, subgrade preparation 4. Core trench excavation and dewatering, if required immensions, location, backfill and compaction test construction of principal spillway and riser with Back C361), Pipe certification from supplier, Pipe assertions.	the next step of with twenty-four or the automated DPIE Site/Road mittee per a prior without DPIE and reconstruct fied by either the ave flagging/tree ring and stream ared. Core trench street class (ASTM mbled in place on		
acceptable subgrade with watertight joints, articular from riser, with proper lifts, compaction, soil mate dimensions.			
 Concrete cradle dimensions, concrete strength collars (location, collar dimensions and re-ba strength tests, riser footing subgrade and diaphragm gradation and dimensions (if applicable) 	r size), concrete limensions. Filter		



Department of Permitting, Inspections and Enforcement

SITE/ROAD PLAN REVIEW DIVISION

9400 Peppercorn Place Largo, Maryland 20774 301.636.2060 ◆ FAX: 301.925.8510



MD-378 POND INSPECTION CHECKLIST

 7a. Precast Riser Shop drawings approved by Design Consultant, accepted by County, visual inspection of riser (no cracks, spalling, exposed steel, incorrect dimensions, honeycombing, certification from supplier, watertight joints, and wall and opening dimensions per plan. 7b. Cast-In-Place Riser: Wall and opening dimensions per plan, re-bar size, number, spacing acceptable, concrete testing and certification, watertight joints, extreme weather provisions. 	
8. Valve/orifice plate installation. Note: may be delayed for Sediment Control purposes.	
Backfilling of principal spillway	
10. Underdrain (if applicable) location, pipe size, filter cloth, gravel, field adjustments	
11. Pond channelization work and pond outfall protection	
12. Diversion of stream through principal spillway	
13. Construction of embankment, lifts, compaction, soil material, location, and dimensions	
14. Construction of emergency spillway in cut	
15. Permanent vegetative stabilization, delivery tickets from supplier	
16. Other items. (Set valve(s) to design opening values, if required)	
17. Final inspection	

Total number of Pond(s) installed for this inspection:

Required inspection by DPIE Site/Road Inspector.

NOTES:

- Permittee to supply Design Engineer with delivery tickets for all materials used in Pond construction, for submission with the as-built package.
- See construction specifications this plan for detailed requirements.
- A copy of this completed checklist must be submitted as part of the stormwater management as-built package.

Date Issued: July 17, 2014



Department of Permitting, Inspections and Enforcement

SITE/ROAD PLAN REVIEW DIVISION



9400 Peppercorn Place Largo, Maryland 20774

301.636.2060 ◆ FAX: 301.925.8510

SHALLOW WETLANDS CONSTRUCTION INSPECTION CHECKLIST

This checklist serves as a guide for permittee and DPIE Site/Road Inspector to review construction progress verify acceptance before acceptance of device.

ite/Project Name: Date:			
Field Engineer: Permittee:			
Permit No:	_ Structure Number: _		
DESCRIPTION OF STAGE		DPIE	PERMITTEE
Preconstruction Meeting: Inspection and approval required at these points prior to proceeding with construction. Contact the DPIE Site/Road Inspector hours' notice (DPIE telephone: 301-883-3820 or the arequest system at 301-883-5390). The DPIE Site/F waive an inspection and allow the permittee per a priarrangement. Work completed without DPIE approvale permittee having to remove and reconstruct the unappet the steps must be verified by either the DPIE Site/Road that the permittee and the completed form submittee drawings	n the next step of with twenty-four (24) automated inspection Road Inspector may or written scheduled all may result in the proved work. Each of pad Inspector and/or		
Clearing, grubbing and subgrade preparation.	1 1 4 11 41 141		
Core trench excavation and dewatering core tre dimensions, location, backfill, and compaction test			
Construction of berm including lifts, compaction te if required.	,		
 Underdrain location, observation well(s) and/or filter cloth, gravel, and field adjustments to materia 	ıls.		
5. Installation of sand and/or any additional geotextile			
6. Installation of top soil, stone, and geotextiles, if red			
 Installation of principal spillway riser and/or trash r Channelization work and outlet protection, if vegetative stabilization. 	required. Permanent		
 Unblock any storm drain draining to facility w written approval. Install any necessary trash ra structures. 			
10. Final inspection and material delivery tickets provide	ded to inspector.		
Notes: ** Installation of an impermeable protective cover recompletion of filter media placement.	may be required by the	ne County	/ Inspector upon
Total number of Shallow Wetland(s) installed for this ins	pection:		



Department of Permitting, Inspections and Enforcement

SITE/ROAD PLAN REVIEW DIVISION



9400 Peppercorn Place Largo, Maryland 20774

301.636.2060 ◆ FAX: 301.925.8510

POCKET WETLANDS CONSTRUCTION INSPECTION CHECKLIST

This checklist serves as a guide for permittee and DPIE Site/Road Inspector to review construction progress verify acceptance before acceptance of device.

Site/Project Name: _____ Date: ____

Field	eld Engineer: Permittee:		
Perm	nit No: Structure Nun	nber:	
DES	SCRIPTION OF STAGE	DPIE	PERMITTEE
requence (DP at 3 and comment)	construction Meeting: Inspection and approval of each pra- uired at these points prior to proceeding with the next step of const- ntact the DPIE Site/Road Inspector with twenty-four (24) hours PIE telephone: 301-883-3820 or the automated inspection request 301-883-5390). The DPIE Site/Road Inspector may waive an ins- allow the permittee per a prior written scheduled arrangement. Inpleted without DPIE approval may result in the permittee had nove and reconstruct the unapproved work. Each of the steps of fied by either the DPIE Site/Road Inspector and/or the Permittee	ruction. ruction. ruction system spection Work ving to nust be	
	pleted form submitted with the as-built drawings		
2.	Clearing, grubbing and subgrade preparation. Core trench excavation and dewatering core trench installati dimensions, location, backfill, and compaction testing.		
	Construction of berm including lifts, compaction tests, and soil marequired.	aterial, if	
	Underdrain location, observation well(s) and/or cleanouts, pipe si cloth, gravel, and field adjustments to materials.	ize, filter	
5. 6.	Installation of sand and/or any additional geotextiles required.** Installation of top soil, stone, and geotextiles, if required.**		
7. 8.	Installation of principal spillway riser and/or trash racks, if required. Channelization work and outlet protection, if required. Pevegetative stabilization.		
	Unblock any storm drain draining to facility with DPIE inspector's approval. Install any necessary trash racks with flow splitter structure.		
10.	Final inspection and material delivery tickets provided to inspector.		
	es: installation of an impermeable protective cover may be required by the ilter media placement.	he County Inspector	upon completion o

Date Issued: July 26, 2014



Department of Permitting, Inspections and Enforcement

SITE/ROAD PLAN REVIEW DIVISION

9400 Peppercorn Place Largo, Maryland 20774 301.636.2060 ◆ FAX: 301.925.8510



UNDERGROUND SWM CONSTRUCTION INSPECTION CHECKL

progress verify acceptance before acceptance of device. Site/Project Name: _____ Date: _____ Field Engineer: _____ Permittee: _____ Permit No:______ Structure Number: _____

This checklist serves as a guide for permittee and DPIE Site/Road Inspector to review construction

DESCRIPTION OF STAGE	DPIE	PERMITTEE
Preconstruction Meeting: Inspection and approval of each practice is required at these points prior to proceeding with the next step of construction. Contact the DPIE Site/Road Inspector with twenty-four (24) hours' notice (DPIE telephone: 301-883-3820 or the automated inspection request system at 301-883-5390). The DPIE Site/Road Inspector may waive an inspection and allow the permittee per a prior written scheduled arrangement. Work completed without DPIE approval may result in the permittee having to remove and reconstruct the unapproved work. Each of the steps must be verified by either the DPIE Site/Road Inspector and/or the Permittee.		
Excavation for stormwater management structure (GEO).		
Install stormwater management control structure/storage structure and associated storm drainage.		
3. Backfilling of drainage structure (GEO).		
 Installation of stormdrain inlet protection or blocking on all inlets draining to structure which may receive silt-laden runoff. 		
5. Installation of final compacted cover and grade.		
 Stabilize drainage area to stormwater management structure and temporary blocking. 		
7. Removal of sediment and construction debris from structure.		
8. Final Inspection.		

- 1. Permittee to supply Design Engineer with delivery tickets for all materials used in SM structure
- 2. See construction specifications for detailed requirements.
- 3. A copy of this completed checklist must be submitted as part of the stormwater management as-built package.
- Required inspection by DPIE Site/Road Inspector.



Department of Permitting, Inspections and Enforcement

SITE/ROAD PLAN REVIEW DIVISION

DEPARTMENT OF PERMITTING, INSPECTIONS AND ENFORCEMENT

9400 Peppercorn Place Largo, Maryland 20774

301.636.2060 ◆ FAX: 301.925.8510

HYDRODYNAMIC SEPARATOR CONSTRUCTION INSPECTION CHECKLIST

This checklist serves as a guide for permittee and DPIE Site/Road Inspector to review construction progress verify acceptance before acceptance of device.

Site/Project Name:	Date:		
Field Engineer:	Permittee:	Permittee:	
Permit No:	Structure Number:		
DESCRIPTION OF STAGE		DPIE	PERMITTEE
Preconstruction Meeting: Inspection and approval of each practice is required at these points prior to proceeding with the next step of construction. Contact the DPIE Site/Road Inspector with twenty-four (24) hours' notice (DPIE telephone: 301-883-3820 or the automated inspection request system at 301-883-5390). The DPIE Site/Road Inspector may waive an inspection and allow the permittee per a prior written scheduled arrangement. Work completed without DPIE approval may result in the permittee having to remove and reconstruct the unapproved work. Each of the steps must be verified by either the DPIE Site/Road Inspector and/or the Permittee.			
Total number of Hydrodynamic Separator(s) installed for	this inspection:		



Department of Permitting, Inspections and Enforcement

SITE/ROAD PLAN REVIEW DIVISION



9400 Peppercorn Place Largo, Maryland 20774 301.636.2060 ◆ FAX: 301.925.8510

OIL GRIT SEPARATOR CONSTRUCTION INSPECTION CHECKLIST

This checklist serves as a guide for permittee and DPIE Site/Road Inspector to review construction progress verify acceptance before acceptance of device.

Site/Project Name:	Date:		
Field Engineer:	Permittee:		
Permit No:	Structure Number:		
DESCRIPTION OF STAGE		DPIE	PERMITTEE
Preconstruction Meeting: Inspection and approval or is required at these points prior to proceeding with the construction. Contact the DPIE Site/Road Inspector with (24) hours' notice (DPIE telephone: 301-883-3820 or inspection request system at 301-883-5390). The Diffusion inspector may waive an inspection and allow the permit written scheduled arrangement. Work completed approval may result in the permittee having to remove at the unapproved work. Each of the steps must be verified DPE Site/Road Inspector and/or the Permittee.	e next step of with twenty-four the automated PIE Site/Road ttee per a prior without DPIE and reconstruct		
Total number of Oil Grit Separator(s) installed for this inst	pection:		

THIS PAGE INTENTIONALLY LEFT BLANK