


- FASTEN WOVEN SLIT FILM GEOTEXTILE AS SPECIFIED IN SECTION H-1 MATERIALS, SECURELY TO THE UPSLOPE SIDE OF CHAIN LINK FENCE WITH TIES SPACED EVERY 24 INCHES AT THE TOP AND MID SECTION. EMBED GEOTEXTILE AND CHAIN LINK FENCE A MINIMUM OF 8 INCHES INTO THE GROUND.
- . WHERE ENDS OF THE GEOTEXTILE COME TOGETHER, THE ENDS SHALL BE OVERLAPPED BY 6 INCHES, FOLDED, AND STAPLED TO PREVENT SEDIMENT BY PASS. EXTEND BOTH ENDS OF THE SUPER SILT FENCE A MINIMUM OF FIVE HORIZONTAL FEET UPSLOPE AT 45 DEGREES TO THE MAIN FENCE ALIGNMENT TO PREVENT RUNOFF FROM GOING AROUND THE ENDS
- PROVIDE MANUFACTURER CERTIFICATION TO THE INSPECTION/ENFORCEMENT AUTHORITY SHOWING THAT GEOTEXTILE USED MEETS THE REQUIREMENTS IN SECTION H-1 MATERIALS. . REMOVE ACCUMULATED SEDIMENT AND DEBRIS WHEN BULGES DEVELOP IN FENCE OR WHEN SEDIMENT REACHES 25% OF FENCE HEIGHT. REPLACE GEOTEXTILE IF TORN. IF UNDERMINING OCCURS, REINSTALL CHAIN LINK FENCING AND GEOTEXTILE.

MARYLAND STANDARDS AND SPECIFICATIONS FOR SOIL EROSION AND SEDIMENT CONTROL MARYLAND DEPARTMENT OF ENVIRONMENT URAL RESOURCES CONSERVATION SERVICE WATER MANAGEMENT ADMINISTRATION



DUE TO FIELD CONDITIONS AS NECESSARY TO MAINTAIN POSITIVE DRAINAGE. 5. PROVIDE OUTLET PROTECTION AS REQUIRED ON APPROVED PLAN.

6. STABILIZE EARTH DIKE WITHIN THREE DAYS OF INSTALLATION. STABILIZE FLOW CHANNEL FOR CLEAR WATER DIVERSION WITHIN 24 HOURS OF INSTALLATION. MAINTAIN LINE, GRADE, AND CROSS SECTION. REMOVE ACCUMULATED SEDIMENT AND DEBRIS, AND MAINTAIN POSITIVE DRAINAGE, KEEP EARTH DIKE AND POINT OF DISCHARGE FREE OF EROSION, AND CONTINUOUSLY MEET REQUIREMENTS FOR ADEQUATE VEGETATIVE ESTABLISHMENT IN ACCORDANCE WITH SECTION B-4 VEGETATIVE STABILIZATION.

8. UPON REMOVAL OF EARTH DIKE, GRADE AREA FLUSH WITH EXISTING GROUND. WITHIN 24 HOURS OF


REMOVAL STABILIZE DISTURBED AREA WITH TOPSOIL, SEED, AND MULCH, OR AS SPECIFIED ON APPROVED

JRAL RESOURCES CONSERVATION SERVICE

MARYLAND STANDARDS AND SPECIFICATIONS FOR SOIL EROSION AND SEDIMENT CONTROL

MARYLAND DEPARTMENT OF ENVIRONMENT


WATER MANAGEMENT ADMINISTRATION



FINAL GRADING, EROSION AND SEDIMENT CONTROL PLAN FOR DEMOLITION ON PARCELS D & G AND INSTALLATION OF CONTRACTOR'S LAYDOWN AREA ON LOTS 1-8, 11, SUITLAND - 1st ADDITION LOTS 2-10, PARCELS B-D, F, G, AND LOT 1 - RESUBDIVISION OF PARCEL D

TOWNE SQUARE AT SUITLAND FEDERAL CENTER, PHASE FOUR

SPAULDING DISTRICT No. 6 PRINCE GEORGE'S COUNTY, MARYLAND



MITCHELLVILLE, MARYLAND 20721 BEN DYER ASSOCIATES, INC. COPYRIGHT © 2018 BEN DYER ASSOCIATES, INC. LCC DRAWN BY: DESIGNED BY: CHECKED BY MWM MMW 1"=30' 40.010-Z **REVISIONS** JUNE, 2019