GLENARDEN APARTMENTS GEOTECHNICAL INVESTIGATION PRINCE GEORGE'S COUNTY, MARYLAND June 10, 2016

Project No.: 16163

Pennrose Properties, LLC 575 S. Charles Street, Suite 140 Baltimore, MD 21201

Attention:

Mr. Patrick Bateman

Reference: Geotechnical Investigation

Glenarden Apartments - Phase 1 Prince George's County, Maryland

Dear Mr. Bateman:

In accordance with your request, we have completed a geotechnical investigation for the above referenced project. Transmitted herein is a report of our findings and recommendations regarding foundation support, slab support, site grading, pavements, utility construction, retaining walls, stormwater management facilities, and related geotechnical considerations.

We appreciate the opportunity to assist you in this project. Please call us if you have any questions concerning geotechnical aspects of this site.

Very truly yours,

HARDIN-KIGHT ASSOCIATES, INC.

Justin A. Frizzell, P.E.

Stephen E. Kight, P.E.

R:\2016\16163 - Glenarden Apartments\16163 Glenarden Report .docx

GEOTECHNICAL INVESTIGATION

for

GLENARDEN APARTMENTS PRINCE GEORGE'S COUNTY, MARYLAND

June 10, 2016

TABLE OF CONTENTS

OVEF	RVIEW	OF CONCLUS	IONS & RECOMMENDATIONS	3		
1.	INTR	ODUCTION		5		
2.						
3.	PRO	POSED CONS	TRUCTION	6		
4.		INVESTIGATION				
5.	SUBSURFACE CONDITIONS					
	5.1					
	5.2					
	5.3		ncountered			
6.	ANALYSIS					
•	6.1 Earthwork					
	6.2					
	6.3					
	6.4		de			
	6.5					
	6.6					
	6.7	Retaining Walls				
	6.8					
7.	RECOMMENDATIONS					
	7.1 Earthwork					
	7.2	Foundations				
	7.3	3 Seismic Information				
	7.4	.4 Slab on Grade				
	7.5					
	7.6					
	7.7	Retaining Walls				
	7.8	Stormwater Management				
	7.9					
8.	LIMIT					
A DDE	NDICE	e				
AI I L		ndix A - Figure	ae			
		e No. 1	Site Location Map			
			Boring and Test Pit Location Plan			
	Figure No. 2 Boring and Test Pit Location Plan Figures No. 3 to 5 Subsurface Profiles					
	Figures No. 6 & 7 Lateral Earth Pressure Diagrams					
	Figure No. 8 Optional Foundation Underdrain Detail					
	Appendix B –Boring and Test Pit Logs					
	Hardin-Kight Records of Soil Exploration (Soil Boring and Test Pit Logs)					
	Appendix C – Laboratory Test Results					
	whhe	IIGIA O - Labor	ratory i Cot i Coulto			

GEOTECHNICAL INVESTIGATION for GLENARDEN APARTMENTS Prince George's County, Maryland

June 10, 2016

OVERVIEW OF CONCLUSIONS & RECOMMENDATIONS

The following is a summary of conclusions and recommendations regarding improvements for the proposed Glenarden Apartments in Prince George's County, Maryland.

- 1. The site is suitable for the proposed development. Building foundations may be supported on normal shallow spread footings proportioned for an allowable soil pressure of 3,000 psf. However, existing fill associated with the demolished buildings was encountered at many of the boring and test pit locations to depths of up to approximately 8 feet below existing grade. In addition, older fills were encountered in isolated areas to as deep as 16.5 feet below the existing ground surface. We recommend that, at most locations, the existing fill be compacted to improve the density and consistency of the fill soils, and proof rolled to identify soft areas, prior to the placement of new fill. If soft areas are encountered during the compaction and proof roll procedures they will need to be removed and replaced.
- 2. Due to the presence of existing fill, the footing excavations must be closely inspected and tested by the geotechnical engineer or his representative. Soft or loose areas encountered during the inspection will require removal and replacement or lowering of the footing excavation.
- 3. The southern portion of the building located along Brightseat Road (eastern side of site), labeled as the "Senior" building, will require controlled fill of up to approximately 9 feet to achieve slab subgrade. Approximately 4 to 8 feet of rubble fill, above up to 12 feet of older fill, was encountered in that area. The loads applied by the weight of the fill and the new building will cause unacceptable settlement. We recommend that settlement monitoring points be installed prior to and during fill placement, and that an additional surcharge be added. Foundation construction must not begin until we have confirmed that the settlement is complete. Alternatively, the rubble fill may be removed and replaced with controlled, compacted fill, prior to the construction of new fills. The methodology for surcharge and settlement monitoring is described in the *Recommendations* section of this report.

Page 4

- 3. The on-site fill soils are generally acceptable for re-use as controlled, compacted fill. However, the clayey fill soil is generally wet of the optimum moisture content and may require drying during re-use. High plasticity clays were encountered in some of the borings. High plasticity clay should not be used within 2 feet of foundation bottoms, or within 1 foot of pavement or slab subgrade.
- 4. Existing foundations and slabs were generally not encountered during the investigation. However, one column footing was observed. Therefore, it should be anticipated that some intact foundations will be encountered. In addition, existing utilities were observed. Existing foundations, utilities, and other structures must be completely removed and replaced with controlled fill. Some existing structures may remain in place, if approved by the owner, site engineer, and this office.
- 5. We anticipate that clayey soils will be encountered at roadway subgrade in some areas. These soils are considered to be low-strength with respect to pavement support. The low-strength soils will require removal and replacement if they are encountered in the top foot below pavement subgrade, or treatment with hydrated lime or soil cement.
- 6. Very dense materials will be encountered at some locations within the existing fill. Very dense materials were generally not encountered in the natural soils. Although blasting is very unlikely to be required, the contractor should be prepared for difficult excavations in some areas, particularly within the existing fill.
- 7. Perched water was observed in many of the borings and test pits, particularly within the existing fill. The contractor must be prepared for conventional construction dewatering, particularly for excavations deeper than 4 feet below existing grades.
- 8. Due to the presence of clay, fill, or water at, or near the bottom of the proposed SWM facilities, the site is generally not suitable for infiltration. The SWM facilities design should exclude infiltration.

REPORT OF GEOTECHNICAL INVESTIGATION

GLENARDEN APARTMENTS LANHAM, MARYLAND JUNE 10, 2016

1.0 INTRODUCTION

Submitted herein is our report of subsurface investigation for the proposed new townhome and multi-family unit condo residential site to be constructed in the Lanham area of Prince George's County, Maryland. In conjunction with the proposed improvements, this investigation was undertaken in accordance with your request to evaluate the subsurface conditions and to make recommendations for design and construction of foundations, slabs, pavements, retaining walls, utilities, site grading and stormwater management. This report includes the results of exploratory drilling, test pit excavations, engineering analysis, and recommendations.

We were provided with a site plan entitled *Glenarden Apartments – Soil Boring Plan, Parcels 'A' & 'B'*, dated March 2016, prepared by Ben Dyer Associates, Inc., (BDA). The site plan provides existing and proposed topography, and the layout of the proposed buildings with first floor slab grades, stormwater management facility locations and paved areas with proposed pavement grades. The plan also includes the proposed boring locations and their tabulated depths. The Boring and Test Pit Location Plan is found in Appendix A. The site engineer and the structural engineer chose the locations for the proposed borings.

2.0 SITE CONDITIONS

The site is located just west of Brightseat Road, immediately south of Hamlin Street and north of Ewarts Street, in Lanham, Prince George's County, Maryland. The site is bounded by wooded areas to the west and southeast, and residential areas in all other directions. The Site Location Map is included as Figure 1, in Appendix A.

The site was formerly occupied by a residential community, which, based on historical photographs, was built in the mid to late 1970's. The majority of the site is cleared, with isolated wooded areas located throughout the site in former landscape areas, between the old building and pavement areas. The previous buildings and roadways have been demolished and there is gravel and crushed concrete spread over the ground at the former building locations. A swimming pool was located on the eastern/central portion of the site. Although the pavements and buildings have been removed, the abandoned utilities seem, for the most part, to be still in place.

The site is rolling, with site topography generally sloping in all directions from a knoll located towards the southern/central portion of the site. Based on the site plan, ground surface elevations range from a low elevation of approximately 100 feet above Mean Sea

Page No. 6

Project No.: 16163

Level (MSL) on the southwestern corner of the site, to a high elevation of approximately 144 feet above MSL, on the knoll. The ground surface was generally stable throughout the site at the time of the drilling, with isolated wet spots at depressed areas around the site.

3.0 PROPOSED CONSTRUCTION

Based on the previously referenced site plan, the proposed construction will consist primarily of slab-on-grade townhomes, with one 4-story, light frame structure (the Senior building) and a 1-story community building, with associated paved areas and utilities. The Phase 1 portion of the construction will consist of a total of 7 townhome buildings (labeled as TH-A thru TH-F), with 4 to 7 units in each building, the community building, and the northern half of the Senior building. The southern half of the Senior building is part of the Phase 2 portion of the construction. The townhome buildings are to be located on the northeastern portion of the overall site, the Senior building is to be located on the eastern portion of the site, and the community building is to be located on the eastern/central portion, just west of the Senior building. Access to the Phase 1 buildings will be from various proposed roadways, which are unnamed at this time, from Hamlin Street.

Based on conversations with Wolfman & Associates, the structural engineer, we understand that the Senior building will be light frame construction and that the maximum column and wall loads will be 85 kips and 6 kips per linear foot, respectively. The townhomes will have maximum column loads of 20 kips and wall loads of 3.5 kips per linear foot.

Based on the design drawings and discussions with BDA, we understand that there will be at least 11 stormwater management facilities scattered across the site, and are presumably mainly micro-bio-retention facilities. The details were not available at the time of the writing of this report. Two (2) of the proposed facilities are located within the Phase 1 portion of the construction.

We understand that the proposed buildings will not have basements. Based on the site plan, the townhome slabs are to range in elevation from approximately El. 117 to El. 132 feet above MSL. Controlled fill, up to approximately 8 feet in height, and excavations of up to approximately 3 feet will be required to achieve proposed townhome slab sub-grade elevations. For the Phase 1 (northern) portion of the Senior building, controlled fill of up to 3 feet will be required. The Phase 2 (southern) portion of the Senior building will require controlled fill of up to approximately 9 feet. The community building will require excavations of up to approximately 4 feet. The proposed roadways will require controlled fill of up to approximately 8 feet and excavations of up to approximately 2 feet, to reach proposed pavement subgrade elevations.

Page No. 7

Project No.: 16163

The recommendations and conclusions contained in this report are based on the proposed construction as described above. If actual conditions vary from those described above, this office should be contacted to review this report and prepare alternate recommendations if needed.

4.0 INVESTIGATION

Thirty-four (34) borings and 23 test pits were conducted as a part of this investigation. They are identified as B-34 thru B-42, B-48 thru B-58, R-13 thru R-24, R-26, SWM-8 and SWM-10. The borings were staked in the field by BDA. The borings were drilled to depths of 10 to 23 feet below the ground surface. The test pits are identified as TP-1 through TP-22 (and R-16). The test pits were located by this office using the existing site features and the staked boring locations and should be considered approximate. The elevations at the test pit locations were estimated from the topographic map, and the boring elevations were provided by BDA.

Standard Penetration Testing was performed in the borings as per ASTM Test Designation D 1586 Standard Test Method for Penetration Test and Split-Barrel Sampling of Soils, and soil samples were retrieved at 2.5-foot intervals to 10 feet and at 5-foot intervals, thereafter. Standard Penetration Testing involves driving a 2-inch O.D., 1 \(^3\)\% - inch I.D. split-spoon sampler with a 140-pound hammer free-falling 30 inches. The SPT N-value, given as blows per foot (bpf), is defined as the total number of blows required to drive the sampler from 6 to 18 inches.

Soil samples were returned to the laboratory for testing. Laboratory testing was performed upon representative samples recovered during the subsurface exploration. Conclusions and recommendations regarding site development were derived from engineering analysis of field and laboratory data, and review of the site plan.

The soils have been visually classified in general accordance with the Unified Soil Classification System (ASTM D 2488). The soils in the SWM borings were also classified in accordance with USDA. Descriptions as provided on the logs are visual, supplemented by the laboratory test results. The recent boring and test pit logs are included in Appendix B. The laboratory test results are included in Appendix C.

Groundwater levels were generally recorded in the borings during drilling, at the completion of the soil sampling, and at approximately 24 hours after the completion of drilling. In addition, groundwater-monitoring standpipes were installed in all of the SWM borings and in select building and roadway borings, to prevent caving and allow for a more accurate 24 hour water level reading.

Page No. 8

Project No.: 16163

5.0 SUBSURFACE CONDITIONS

5.1 Geology

According to the *Prince George's County Geologic Map*, (Heather Quinn, 2003; revised 2006), based on the *Prince George's County Geologic Map* (Glaser 1996), with *Distribution of Silt Loam Soils in Upland Deposits* (Hack, 1977), the geologic units underlying the site are both the sand-gravel facies and the silt-clay facies of the Potomac Group. The Potomac Group includes the Patapsco, Arundel and Patuxent Formations. In Prince George's County these units have not been mapped separately at the county scale; instead sediments of the Potomac Group have been mapped according to dominant lithology: sand-gravel facies (Kps) or silt-clay facies (Kpc). The maximum thickness of the Potomac Group is about 1000 feet.

The sand-gravel facies is largely the lower Potomac Group (Patuxent Formation), but the upper portion (Patapsco Formation) also contains considerable sand and some gravel, which is included in this map unit. The lithology is essentially fine- to coarse-grained sand, grading to pebbly sand and gravel, coarse to very coarse in places, which is arranged in thin to very thick lenticular beds. The sands and gravels are typically white, buff, and yellow to brown. Clay clasts are common, as are ironstone pods and limonitic layers. Interbedded with these coarser clastics are scattered thin lenticular bodies of tough massive silt-clay. The silt-clay is white, pale gray, or variegated; dark-gray, where highly organic. As is typical of fluvial sediments, few beds are laterally continuous for any great distance; consequently, great variability in outcrop lithology is common.

The silt-clay facies of the Potomac Group, comprised of the Arundel Clay and much of the lower Patapsco Formation. The lithology is predominantly compact red and dark-gray clay containing large and small lenses and pods of sand and minor gravel. Some of the clay is strikingly variegated in color. Dark-gray lignitic clay is most characteristic of the Arundel but occurs at other stratigraphic levels as well. Much of the clay is internally massive and weathers hackly. Silt-clay lenses in the uppermost portion of the unit tend to be whitish or pale-gray, and thinner.

5.2 Soils

The USDA Natural Resources Conservation Service (NRCS) Web Soil Survey for Prince George's County, Maryland indicates the site is underlain by Russett-Chrisiana-Urban Land soils, 0-5% slopes (RuB), Sassafras-Urban land complex, 5-15% slopes (SnD) and Woodstown-Urban land complex, 0-5% slopes (WuB). The following is a brief summary of the NRCS information:

Page No. 9

Project No.: 16163

The Russett soils consist of moderately well drained soils located on drainhead complexes, swales, broad interstream divides and interfluves. The parent material is clayey fluviomarine deposits. The depth to the water table is more than 80 inches. The frequency of flooding and ponding is described as none.

The Christiana soils consist of moderately well drained soils located on hillslopes, interfluves, swales, and drainhead complexes. The parent material is clayey fluviomarine deposits. The depth to the water table is about 20 to 40 inches. The frequency of flooding and ponding is described as none.

The Sassafras soils consist of well drained soils located on knolls, fluviomarine terraces, ravines and interfluves. The parent material is loamy fluviomarine deposits. The depth to the water table is more than 80 inches. The frequency of flooding and ponding is described as none.

The Woodstown soils consist of moderately well drained soils located on broad interstream divides, swales, fluviomarine terraces, depressions, interfluves, and drainhead complexes. The parent material is loamy fluviomarine deposits. The depth to the water table is more than 80 inches. The frequency of flooding and ponding is described as none.

The Urban Land soils consist of man-made fill and must be characterized with an on-site investigation.

Please refer to the above referenced publication for a more detailed description of the site soils.

5.3 Conditions Encountered

The conditions encountered are suitable for the proposed development. Existing fill associated with the previous construction was encountered in 28 of the borings. The majority of the fill was approximately 2 to 5 feet in depth, but deeper fill of up to approximately 9.5 feet was encountered in 6 of the borings. The existing fill associated with the demolished buildings varies from fine to coarse grained soils with varying amounts of construction debris including concrete, brick and pavement fragments. In some areas the fill has significant amounts of organics. The recent existing fill soils are loose/soft to medium dense/very stiff, referencing SPT resistance values ranging from 4 blows per foot (bpf) to 21 bpf.

In addition to the fill associated with the demolition, there also appears to be areas that were filled prior to the previous construction. These fills have been in place for a relatively long period of time, and are difficult to discern from the natural soils. In some cases they

Page No. 10

Project No.: 16163

are labeled as "possible fill." The older fill or possible fill was observed in 10 of the borings. The older fill is primarily clayey in nature, but is more coarse-grained in some cases (2 borings). The older fill is medium stiff to very stiff, referencing SPT values ranging from 6 bpf to 14 bpf.

The natural soils generally consist of interbedded fine- and coarse-grained soils. High plasticity clay was observed in 8 of the borings. The natural soils are loose/soft to very dense/hard, referencing SPT values ranging from 5 bpf to 50 blows for 4 inches of penetration. However, the natural soils are primarily medium dense/stiff.

Groundwater was encountered in the borings during drilling, or observed after the completion of drilling, in 24 of the borings. Many of the borings in which water was not observed were caved at a relatively shallow depth. The water is perched in the existing fill, and in the interbedded sandy natural strata. Water monitoring standpipes were installed in all of the stormwater management borings, and in select building and roadway borings, to accurately determine water table elevations.

The laboratory tests conducted on representative soil samples from the recent investigation indicate that the soil moisture contents range from 5.1% to 32.7%, with an average moisture content of 15.7%. Moisture density relationship tests (proctors) were performed on bulk samples from Borings R-14 and R-16. The clayey soils were found to have a maximum dry density of 116.2 pcf, at an optimum moisture content of 12%. The sandy soils have a maximum dry density of 104.0, at an optimum moisture content of 13.9%. Therefore, the site soils are generally somewhat wet of optimum. Typical fill soil is classified as sandy lean clay with a liquid limit of 25 and a plasticity index of 8. The test on the representative natural fat clay indicated that the liquid limit is 54 and the plasticity index is 29. The granular natural soils were also tested and found to be silty fine to very fine sand, which ranged from being non plastic to slightly plastic, with a liquid limit of 21 and a plasticity index of 3. The laboratory test results are included as Appendix D. CBR testing is currently underway. The results will be presented as an addendum to the report, under a separate cover.

Detailed records of the conditions encountered are included on the boring and test pit logs, included in Appendix B. Boring profiles are included as Figures 3 through 5 in Appendix A.

6.0 ANALYSIS/DISCUSSION

In our opinion, the subsurface conditions on this site are suitable for the proposed development. However, existing fill soils were encountered in the borings and test pits. The existing fill soils will need to be inspected, compacted and proof rolled prior to the

placement of new, controlled fill. Special consideration will need to be given to the fill located on the southern, Phase 2 portion of the Senior building.

6.1 Earthwork

Controlled fills, up to approximately 9 feet in height, and excavations of up to approximately 4 feet, will be required to achieve the proposed slab and roadway subgrades. The largest fills will be located on the Phase 2 portion of the Senior building, and for townhome buildings TH-C and TH-D. The on-site existing fill may be used as controlled, compacted structural fill, provided it is constructed in accordance with the recommendations in this report.

The site contains existing fill in many areas, particularly at the locations of the previous buildings and pool. While the fill appears generally medium stiff to very stiff, it will be necessary to carefully compact, inspect, and improve isolated soft conditions that may be present in the inherently variable uncontrolled fill, prior to the placement of new, controlled fill. Compaction should be implemented to improve the density and consistency of the fill soils. The soils must be compacted using a large smooth drum vibratory compactor with a minimum gross drum weight in excess of 10,000 pounds, and capable of imparting a force equal to 30,000 pounds at a minimum of 1,000 vpm (note: Ingersol Rand models SD 100 through SD 180 meet this criteria). In areas where clayey fill soils are present at the surface, a sheep foot or rubber tire roller must be used. In addition, the fill subgrade should be proofrolled using a loaded tandem dump truck, or a rubber tire roller, with a gross weight in excess of 30 tons. If debris or isolated soft areas are encountered during the compaction or proof roll procedures, they should be removed and replaced under the direction of the geotechnical engineer.

Due to the loads applied by the new fills and the Senior building, unacceptable settlement is anticipated in the larger existing fills on the southern portion of the proposed building. Settlement monitoring points must be established at the bottom, mid-point, and top of the new fill. The settlement points must be monitored at least 3 times a week, and up to once a day. The foundation construction on that side of the building must not begin until the geotechnical engineer has confirmed that the settlement is complete.

We recommend that at least 4 additional feet of surcharge be placed on the Phase 2 portion of the Senior building pad to simulate the building loads and decrease the time required for settlement. We anticipate that the settlement will take on the order of 30 days or less.

A surcharge fill is not required on the northern half of the Senior building, where less new fill is required. However, we anticipate that some of the fill on the northern portion of the building, on the order of 1 to 2 feet, will require removal and replacement, due to organic

Page No. 12

Project No.: 16163

material observed in the fill. The geotechnical engineer or his qualified representative may determine the over-excavation required based on the compaction, proof roll and penetration testing process.

The on-site existing fill soils are acceptable for re-use as controlled, compacted fill. However, large pieces of concrete and other types of debris must be removed from the existing fill prior to its re-use as controlled, compacted fill. It may be necessary to dry some of the clayey fill soils in order to achieve the required compaction. High plasticity clayey soils must not be used within 2 feet of proposed foundation bottoms, or within 1 foot of pavement or slab subgrade. It is important that fill be placed in accordance with the *Recommendations* section of this report.

Intact foundations and slabs were generally not observed in the test pits, and are not expected to be encountered during construction on a widespread basis. However, one column footing, approximately 9 feet long, with a drop of a few inches towards the middle of the footing, was encountered in Test Pits TP-13 and TP-14, located on the southeastern portion of the Senior building. It is possible that other isolated foundations or slabs may be encountered. In addition, existing utilities such as storm drain pipes and structures were observed. Existing foundations, utilities, and other structures must be completely removed and replaced with controlled fill under the supervision of the geotechnical engineer. It is possible that some structures may be left in place, if approved by the owner, geotechnical engineer and structural engineer.

Very loose, saturated rubble was observed at the location of the demolished swimming pool. This material is completely saturated due to the voids in the rubble and clayey, impermeable nature of the underlying natural clays. It will be necessary to completely remove this rubble fill and replace it with controlled, compacted fill under the supervision of the geotechnical engineer.

Perched groundwater was encountered in the majority of the borings and test pits, at depths ranging from approximately 4 to 18.5 feet below existing grade. Therefore, groundwater will be encountered during site grading in some areas, particularly where larger excavations are required to achieve proposed grades. The contractor should be prepared for typical construction dewatering.

Very dense materials may be encountered at some isolated locations, particularly within the existing fill. Although blasting is very unlikely to be required, the contractor should be prepared for difficult excavations in some areas. In particular, very dense rubble fill was encountered in Test Pit TP-4, located in proposed Building TH-F. Excavations of up to 3 feet are required for that building.

Project No.: 16163

Page No. 13

6.2 Foundations

Based on the results of the borings, the existing fill (after compaction and proof roll for the majority of the site) and controlled, compacted fill on this site are suitable for support of spread footings proportioned for an allowable bearing pressure of 3,000 psf. Settlement on the order of 1 inch total and ½ inch differential can be anticipated based upon this design. Soft/loose soils and pieces of debris may be encountered for foundations that are in the inherently variable existing fill. The footing excavations should be closely inspected and tested by the geotechnical engineer or his representative. These footing areas must be tested by the geotechnical engineer with a Modified Penetrometer Test (MPT) or Dynamic Cone Penetrometer (DCP) to a depth of at least 3 feet below the bottom of the foundation. Soft or loose areas will require removal and replacement in accordance with the *Recommendations* section of this report. Large pieces of debris may also be encountered in the existing fill during foundation excavations. The larger debris will require removal and replacement at the direction of the geotechnical engineer.

Water was observed either during drilling or at 24 hours after the completion of drilling in most of the borings at depths of 4 feet or more below existing grades. The water appears to be in a perched condition in the existing fill and interbedded sandy soils. Perched groundwater may be encountered during footing excavations, particularly where cuts are required to achieve slab subgrade. Standard construction dewatering techniques should be utilized when groundwater is encountered.

6.3 Seismic Information

Utilizing the SPT data from the field exploration and the guidelines set forth by the 2012 International Building Code (IBC 2012 – Table 1613.5.2), the subsurface soil at the site is classified as "Site Class D".

6.4 Slab on Grade

Floor slabs for the building can be designed as concrete slabs on grade. The slab can be designed based on a modulus of subgrade reaction of 120 pci. Controlled, compacted fill of up to approximately 9 feet, and excavations of up to approximately 4 feet will be required to reach proposed slab sub-grades. The slabs should be designed and constructed in accordance with the *Recommendations* section of this report.

6.5 Subsurface Utilities

The natural and fill soils are generally considered to be suitable for the support of the utility pipe systems. The soils encountered during utility installation can be generally used

Page No. 14

Project No.: 16163

for trench backfill. However, moisture conditioning is likely to be required for the clayey fill soils. In addition, the very hard clay soils may be excavated in chunks that must be pulverized prior to reuse as compacted backfill.

Very dense materials were encountered in the borings within the existing fill. The contractor should be prepared for difficult excavations in the existing fill in some areas. Very dense materials were encountered in the natural soils in Boring B-53 at a depth of 6 feet, and in Boring B-54 at a depth of 9 feet. Therefore, we do not anticipate that difficult excavations will be encountered in the natural soils on a widespread basis, but may be encountered in isolated areas during the deeper utility excavations.

Groundwater was encountered during drilling, or was observed after the completion of drilling, in 24 of the borings at depths ranging from approximately 4 to 18.5 feet below existing grades. The water was perched, either within the existing fill, or in the interbedded granular natural soils. We anticipate that perched water will be encountered during utility excavations in many areas. The contractor should be prepared for routine construction dewatering. The materials removed during construction are likely to be wet of optimum, and drying may be required to achieve compaction specifications for the backfill, particularly for the clayey soils.

6.6 Pavements

The soils encountered are generally suitable for use in construction of compacted fill for the pavement areas. CBR testing is currently underway. The results will be submitted as an addendum to this report. Based on the site plans, controlled fills of up to approximately 8 feet are required and excavations of up to approximately 2 feet will be required in the proposed roadway areas.

The soils encountered are generally suitable for use in construction of compacted fill for the pavement areas. However, low-strength fine-grained soils were encountered in many of the borings and test pits. Although the CBR test results are not available at this time, we anticipate that the granular soils will have a CBR on the order of 7 or greater. This is considered to be fair to good with respect to pavement support. We anticipate that the fine-grained, clayey natural and fill soils have a CBR on the order of 7 or less. This is considered to be poor with respect to pavement support. When the low-strength soils are encountered at the proposed roadway subgrade, they must either be over-excavated and replaced with soils that have a CBR greater than 7, or improved by chemical stabilization. We recommend that chemical stabilization using hydrated lime, cement or Calciment® be strongly considered, particularly if the construction is to be conducted during the winter months. The pavement section detailed in the *Recommendations* section of this report can be used if the low strength soils are replaced or improved.

Page No. 15

Project No.: 16163

If a granular base course is used in the pavement section, as proposed, it is important that completed portions of the base be positively drained and protected from construction traffic, particularly after precipitation. Surface water which is trapped in the completed stone base may contribute to deterioration of the subgrade if construction traffic is allowed to traverse a saturated granular base. We suggest that the pavement areas be paved as soon as practical to reduce the potential for subgrade softening due to surface water, and to reduce the possibility of disturbance due to traffic on an exposed pavement subgrade (even automobile traffic).

Standard Prince George's County pavement sections may be utilized for this project. The pavement designs are based on a CBR value of 6. If the soils used to fill the site are found to have a CBR value of less than 6, or if the assumed traffic loading is not as stated above, the pavement design should be re-evaluated.

6.7 Retaining Walls

The building will contain foundation walls that retain earth on one side. The retaining walls will restrict the lateral movement of soil backfill, and the full internal resistance of the soil will not be mobilized. The use of "at rest" lateral earth pressure criteria, which assumes a non-yielding wall for the building walls is applicable for design purposes. Any site retaining walls that are not restrained at the top can be designed using active soil pressure. Lateral Earth Pressure Diagrams are included as Figures 6 and 7 in Appendix A.

Coarse-grained granular soils are recommended for the backfill of the retaining walls, particularly for any modular block, geogrid type walls. It is very important that only free-draining material be utilized in the reinforced area behind the block walls. The underlying granular soils found throughout the site may be used for constructing the reinforced area behind the wall.

It is important that water not be allowed to accumulate behind the retaining wall for the southern portion of the Senior building during construction. The grading must prevent water from flowing to or ponding adjacent to the wall to prevent hydrostatic pressure. Alternately, the wall may be drained using conventional foundation systems including a drainage layer adjacent to the wall and a foundation drain at the base. A detail for the optional foundation wall drain is included as Figure 8 in Appendix A.

6.8 Stormwater Management

Infiltration is not feasible due to the presence of shallow perched groundwater and clayey soils. Perched water was observed in the water monitoring standpipe at 24 hours after the completion of drilling in Boring SWM-8 at a depth of 6 feet (El. 115.1), and in Boring

Page No. 16

Project No.: 16163

SWM-10 at a depth of 12.7 feet (El. 121.2). The SWM facilities must include underdrains for dewatering.

Typically micro-bioretention type SWM facilities are excavated and filled with a very loose soil mixture to facilitate seepage and ostensibly filtering stormwater. If micro-bioretention facilities are planned, these very loose conditions must be located beyond a 1 horizontal to 1 vertical (1H:1V) projection from the edge of pavement or back of curb to prevent possible settlement. Similarly, the loosely filled facilities must be located beyond a minimum projected line of 2H:1V when adjacent to structures.

The on-site fine-grained soils are suitable if impervious soils are required for SWM facility core trenches or liners. The Soil Conservation Service, Maryland Standards and Specifications - Code 378, states that the soils used in construction of an impervious core must meet the requirements for USCS designations SC, or CL. Soils designated as CL were found in the recent borings and test pits.

The undisturbed natural soils are suitable for support of foundations proportioned for an allowable soil pressure of 3,000 psf. Slopes may be constructed to a maximum gradient of 2H:1V.

7.0 RECOMMENDATIONS

7.1 Earthwork

- 1. We recommend that structural fill areas be compacted using a large vibratory drum roller (or sheep's foot or rubber tire roller where clay is at the surface) with a minimum gross drum weight in excess of 10,000 pounds, and capable of imparting a force equal to 30,000 pounds at a minimum of 1,000 vpm, and proof rolled using a loaded tandem dump truck or a rubber tire roller with a gross weight in excess of 30 tons, prior to the placement of controlled fill or construction of the new pavement section. We recommend that the geotechnical engineer also perform penetration testing to 3 feet below the existing surface prior to fill placement. We recommend that soft or loose subgrade soils identified during this process be removed and replaced. The compaction and proof roll shall be performed in the presence of a geotechnical engineer or his representative.
- 2. We recommend that settlement monitoring points be installed on the southern half (Phase 2) of the Senior building before and during the placement of the new fill, as described in the *Analysis/Discussion* section of this report. We recommend that the settlement points be monitored on a regular basis, and that foundation construction not begin on the southern side until the geotechnical engineer has confirmed that the settlement is complete.

- We recommend that at least 4 feet of surcharge fill be placed on the southern portion of the Senior building pad. We anticipate that settlement will be complete in 30 days or less.
- 4. We recommend that the rubble that was used to backfill the swimming pool be completely removed and replaced with controlled, compacted fill.
- We recommend that structural fills in building areas be compacted to a minimum of 95% of the maximum dry density as determined by the modified moisture density relationship test (AASHTO T-180, ASTM D1557). Fill in the pavement and retaining wall areas may be compacted to 92%, with the exception of the top foot below pavement subgrade, which must be compacted to 97%.
- 6. We recommend that fill be placed in layers of 8 inches or less. We recommend that each layer of fill be tested and approved prior to placement of the succeeding layer. We recommend that fill which fails to meet the minimum compaction requirements be compacted and reworked until satisfactory compaction is obtained.
- 7. We recommend that off-site borrow soils proposed for use as structural fills meet the requirements for soil classifications GM, GP, GW, SM, SP, SW in accordance with the Unified Soil Classification System (D-2487). We recommend that the off-site borrow soils contain no more than 30% material passing the U.S. standard #200 sieve with a maximum plasticity index (PI) equal to 10.
- 8. We recommend that difficult excavations be anticipated in isolated areas within the existing fill.
- 9. We recommend that the contractor be prepared for standard construction dewatering for excavations deeper than approximately 4 feet below the existing ground surface.

7.2 Foundations

1. We recommend that the proposed structures be founded on spread footings bearing on existing fill subsoils, or suitably compacted structural fill, and designed for an allowable soil bearing pressure of 3,000 psf. Settlement on the order of 1 inch total and ½ inch differential can be anticipated based upon this design. We recommend that footings be at least 16 inches in width for continuous strip footings, and 24 inches for isolated column footings.

- 2. We recommend that the footing excavation bottoms be compacted using a trench compactor to provide a uniform compacted surface.
- 3. We recommend that the footing excavations be closely inspected and tested by the geotechnical engineer using a Modified Penetrometer Test (MPT) or Dynamic Cone Penetrometer (DCP) to a depth of at least 3 feet below the bottom of the foundation.
- 4. We recommend that soft or loose soils encountered during the footing inspections be removed and replaced with controlled fill compacted to a minimum of 95% of the maximum dry density, as determined by the modified moisture density relationship test (AASHTO T-180, ASTM D1557). Alternatively, the footing may be lowered through the soft or loose soils.
- 5. We recommend that large pieces of debris (4"+) encountered during the footing excavations be removed and replaced at the direction of the geotechnical engineer.
- 6. We recommend that the footings be completed the same day they are excavated. We recommend that footings that are not poured the same day be re-inspected and tested.
- 7. We recommend that exterior footings be located a minimum of 30 inches below the lowest adjacent exposed grade for frost protection. Interior footings in permanently heated areas may be located at minimum depths below slab level.
- 8. We recommend that the contractor be prepared to encounter groundwater for foundation excavations at depths greater than approximately 4 feet below the existing surface. We recommend that typical construction dewatering be implemented when groundwater is encountered.

7.3 Seismic Information

1. We recommend that the site be classified as "Site Class D".

7.4 Slab on grade

1. We recommend that ground floor slabs be designed as floating slabs, not rigidly connected to bearing walls or foundations to accommodate differential settlement between foundations and the slab. The slabs may rest on footing projections. The slabs may be rigidly connected to the foundation if the design takes into

consideration the potential for differential settlement between the slab and the foundation.

- 2. We recommend that the slab be designed based on a modulus of subgrade reaction of 120 pci.
- 3. We recommend that a minimum 4-inch thick layer of free draining granular material be placed beneath floor slabs to improve drainage and provide a firm level surface for concrete placement. We recommend that a plastic vapor barrier be provided between the concrete and drainage layer to prevent dampness.
- 4. Prior to placement of the drainage layer, we recommend that the slab subgrade be inspected, tested, and approved by a soils testing agency. We recommend that loose or wet areas that yield under construction traffic be either compacted in place, or removed and replaced with suitably compacted fill.

7.5 Subsurface Utilities

- 1. We recommend that a 6-inch granular bedding be placed beneath the pipe to provide uniform support when the pipe is supported on clayey soil, rock, or when groundwater is encountered.
- 2. We recommend that the contractor provide construction dewatering devices and adequate earth support systems during utility installation when groundwater is encountered.
- 3. We recommend that the contractor be prepared for difficult excavations due to concrete rubble and other debris located within the existing fill.
- 4. We recommend that utility backfill be compacted in accordance with the *Earthwork Recommendations* section of this report.

7.6 Pavements

- 1. We recommend that the pavement subgrade preparation be conducted in the presence of the geotechnical engineer or his representative. The completed work shall be tested and approved by the geotechnical engineer prior to construction of the succeeding work.
- 2. We recommend that the geotechnical engineer or his qualified representative inspect the soil type at pavement subgrade prior to paving. If materials with low strength characteristics (i.e. CBR<6) are identified by the inspector, we

recommend that they be removed and replaced with controlled, compacted fill. Alternatively, we recommend that the low-strength soils be treated with 3 to 5% hydrated lime or Portland cement. The final lime or cement application can be established based on the subgrade soils. For 4% cement, 12 inches thick, the estimated application rate is 40 pounds per square yard.

- 3. We recommend that pavement subgrade be proof rolled using a loaded tandem dump truck or a rubber tire roller with a gross weight in excess of 30 tons. We recommend that soft, loose or wet conditions identified during the proof roll be corrected in accordance with the following procedures:
 - a. materials may be removed and replaced with suitable fill materials compacted to the required density.
 - b. the materials may be reworked and re-compacted until satisfactorily compacted to the required density.
 - c. unsatisfactory subgrade may be improved by installation of ground stabilization cloth and additional thickness of base material.
 - d. longitudinal underdrains shall be installed in poorly drained areas as directed.
- 4. We recommend that the standard Prince George's County pavement section be utilized for preliminary design purposes, based on a design CBR of 7.0 or more.
- 5. We recommend that the top foot of soil at the pavement subgrade be compacted to 97% of the maximum dry density, as determined by the modified moisture density relationship test (AASHTO T-180, ASTM D1557). Underlying soils may be compacted to 92%.
- 6. We recommend that the contractor proceed with the placement of pavement aggregate base course within twenty four hours after subgrade approval, and proceed with the construction of the HMA binder course within twenty four hours of the satisfactory construction of the base course. If precipitation occurs during the course of these operations, a re-evaluation by the geotechnical engineer is recommended prior to proceeding.
- 7. We recommend that the contract documents include provisions for placement for extra work associated with preparation of the pavement subgrade on a unit price basis for the following items:
 - a. for undercut of unsuitable materials and removal to an on-site storage area; per cubic yard
 - b. for undercut of unsuitable materials and off-site removal; per cubic yard

- c. for replacement fill using on-site soils; per cubic yard
- d. for replacement fill using off-site soils; per cubic yard
- e. for ground stabilization cloth; per square yard
- f. for longitudinal underdrain; per linear foot
- 8. We recommend that large debris (4"+) encountered in the pavement areas in the existing fill, be removed and replaced at the discretion of the geotechnical engineer.

7.7 Retaining Walls

- We recommend the use of "at-rest" lateral earth pressure criteria for the below grade foundation walls, which assumes a non-yielding wall. For retaining walls that are not fixed at the top of the wall, including the above grade foundation walls and the site retaining walls, we recommend that the "active" earth pressure criteria be utilized.
- 2. We recommend that the foundation and retaining walls be backfilled with on-site granular materials, or granular borrow, which meet the following requirements:

20 percent maximum passing a U.S. Standard #200 sieve 60 percent minimum passing a U.S. Standard #40 sieve Angle of Internal Friction = 32 degrees (minimum) Bulk (wet) Density = 130 pcf (maximum) Plasticity = Non-Plastic

- 3. We recommend that fill placed behind the walls be constructed in 6-inch loose lifts and compacted to a minimum of 92% of the maximum dry density as determined by the modified moisture density relationship test (AASHTO T-180, ASTM D1557).
- 4. We recommend that only granular backfill be used behind the foundation walls and retaining walls. For computation of design pressures, we recommend the following design parameters:

Angle of Internal Friction = 32 Degrees
Bulk (wet) Density = 130 PCF
Coefficient of At-Rest Earth Pressure = 0.47
Equivalent At-Rest Pressure = 61 PSF/FT
Coefficient of Active Earth Pressure = 0.31
Equivalent Active Earth Pressure = 40 PSF/FT

Project No.: 16163

5. We recommend that exterior granular backfill be capped with pavement or 12 inches of impervious soil in the area of the walls, where possible.

6. We recommend that the slab subgrade drain away from the retaining wall on the southern side of the Senior building during construction. The grading must prevent water from flowing to or ponding adjacent to the wall to prevent hydrostatic pressure during construction. Alternately, the wall may be drained using conventional foundation systems including a drainage layer adjacent to the wall and a foundation drain at the base. A detail for the optional foundation wall drain is included as Figure 8 in Appendix A.

7.8 Stormwater Management

These preliminary recommendations are provided as a guide to assist in consideration of the stormwater management facility design.

- 1. We recommend that SWM Facilities be designed and constructed as conventional detention or retention facilities. The site is not suitable for infiltration. Microbioretention facilities are acceptable provided that they include bottom drainage.
- 2. We recommend that SWM Facilities be designed in accordance with Maryland Stormwater Design Manual.
- 3. We recommend that micro-bioretention facilities adjacent to pavements and site structures be located beyond a 1 horizontal to 1 vertical projection from the structure or back of curb to prevent settlement of the pavement or structure.
- 4. We recommend that micro-bioretention facilities adjacent to buildings be located beyond a 2 horizontal to 1 vertical projection from the foundation to prevent settlement of the building.
- 5. We recommend that the foundations for SWM structures be proportioned for an allowable soil pressure of 3,000 psf, and that foundation soils be tested and confirmed during construction.
- 6. We recommend that the earth slopes be constructed to a maximum gradient of 2H:1V or flatter. Flatter slopes are recommended, where possible, to facilitate maintenance and to reduce the potential for erosion.
- 7. We recommend that the earth pressure against structures be computed based on an angle of internal friction of 32 degrees, and unit weight of 130 pounds per cubic foot.

8. We recommend that the proposed final stormwater management design be reviewed by this office. A final review with modified final recommendations, if deemed necessary, will be prepared.

9. We recommend that the stormwater management facility installation be monitored by the geotechnical engineer, in addition to the certifying engineer, to confirm the satisfactory completion of geotechnical aspects of the installation.

7.9 Construction Inspection and Testing

We recommend that the owner retain the services of a geotechnical engineer to:

- 1. Monitor earthwork operations including topsoil removal, approval of the ground surface prior to placement of fill, proofrolling, and performance of compaction tests.
- Observe foundation construction including inspection of the footing excavations, and performance of modified penetration tests to confirm subfoundation soil suitability.
- Test and inspect subgrade preparation for pavements including monitoring, proofrolling, and confirming subgrade suitability prior to placement of base or surface courses.

8.0 LIMITATIONS

This report was prepared in accordance with generally accepted practice for geotechnical engineering in this area. It is intended for the use of the client for the specific site, as shown on Figure 2, for design purposes. The recommendations are based on the general description of the structures and site development as characterized above. If the project is substantially modified, this office should be notified so that we can review our recommendations to determine what impact the changes will have. We request the opportunity to review the site development and structural drawings as they become available.


The soil and water conditions discussed herein represent the conditions encountered at the locations of the exploratory borings and test pits, as shown on the location plan. Variations in the soils between the boring and test pit locations, and below the depths explored, should be anticipated.


June 10, 2016


Page No. 24


Attached are copies of our boring and test pits logs, a boring and test pit location plan, site location map, soil profiles, lateral earth pressure diagrams, an optional foundation wall drain detail, and laboratory test results for your reference. If you have any questions concerning this report, please call our office.


APPENDIX A FIGURES


















ACTIVE CASE FOR UNRESTRAINED RETAINING WALLS

NDTES:

- 1) FOR HORIZONTAL BACKFILL ONLY
- 2) COHESION IS NEGLECTED FOR ALL MATERIAL
- 3) ASSUMES NO HYDROSTATIC PRESSURE

FIGURE 7

HARDIN-KIGHT ASSOCIATES, INC. **GLENARDEN APARTMENTS** Consulting Engineers LATERAL EARTH PRESSURE DIAGRAM 7524 WB&A Road, Suite 100 Glen Burnie, Maryland 21061 (410) 553-0802 PRINCE GEORGE'S COUNTY, MARYLAND Fax (410) 553-0808 SCALE DATE SOURCE **REVIEWED BY** PROJECT NO. NTS **JUNE 2016 HKA JAF** 16163



APPENDIX B BORING AND TEST PIT LOGS

Record of Soil Exploration

Project Name: Glenarden Apartments Contracted With: Pennrose Properties

Project Location: Prince George's County, Maryland

N: 458643 E: 1352272 Boring Location: Hammer Wt. 140 lb. Surf. Elev.: 129.36

Elev. from: Survey Hammer Drop: 30" Sampler Size: 2" split spoon Offset Elev: Offset Dist.: Offset Direction:

JOB NO. 16163 Page 1 of 1

BORING NO. B-34

Office: (410) 553-0802

Fax #: (410) 553-0808

Rock Core Dia.: Foreman: Allied Hole Diameter: 8" Inspector: JAF Boring Method: HSA Date Started: 5/18/16 Date Finished: 5/18/16

Sample Data Elev. Soil Description Condition Boring & Sample Blow Depth Lype Color, Moisture, Density Plasticity, Size Proportions Notes 129.36 -0.0 10 D Tan brown, moist, loose, nonplastic, silty SAND and GRAVEL including asphalt and brick PP > 4.5 TSF fragments (FILL) 18 _USC: (SP-SM)* Tan brown, mottled gray, dry, 125 5 medium dense, medium plastic, 14 clayey, silty fine SAND (Natural) _USC: (_SC-SM_)*_ Gray, moist, very stiff, medium _-7.5plastic, silty lean CLAY, little fine 10 sand 120 USC: (CL)* 10 Gray to tan, wet, medium dense, non-plastic, silty coarse to fine SAND USC: (SM)* ---, layer of black, wet, highly 14 115 plastic CLAY (CH) @ 13.5' 15 110 18 20 -20.5 Gray, moist, medium stiff, Temporary water monitoring medium plastic, fine sandy lean pipe installed to 21.0' **CLAY** USC: (CL)* Boring Terminated at 21 Ft. 105 25 100 30

* Visual Description	 in general accordance with 	ASTM D 2488 and AASHTO M145

* Visual Description - in general accordance with ASTM D 2488 and AASHTO M145		Water	Caved
Notes: Surface elevations provided by Ben Dyer Associates, Inc.	Encountered	8.5'	
	Completion	Dry	12.0'
	On at		
	On 5/19 at	4.0'	Pipe

Project Name: Glenarden Apartments Contracted With: Pennrose Properties

Project Location: Prince George's County, Maryland

Boring Location: N:

Surf. Elev.: 137.78 Hammer Wt. 140 lb.

Elev. from: Survey Hammer Drop: 30"

Offset Elev: Sampler Size: 2" split spoon

Offset Dist.: 20' Offset Direction: S

Rock Core Dia.:
Hole Diameter: 8"
Boring Method: HSA

Foreman: Allied
Inspector: JAF

BORING NO. B-35

Page 1 of 1

JOB NO. 16163

Date Started: 5/19/16
Date Finished: 5/19/16

Office: (410) 553-0802

Fax #: (410) 553-0808

Oliset Dist.: 20	Oliset Direction: 3							Date Finished: 3/13/10
Elev.	Soil Description			Sample	Data		ion	
137.78	Color, Moisture, Density Plasticity, Size Proportions	Depth	Type	Blow Counts	#	Recovery	Condition	Boring & Sample Notes
	Gray tan, moist, medium dense, non-plastic, silty medium to fine SAND and GRAVEL including	0 - 4.3.5.	**	7 10 11	1	14	I	Offset 20' South in old pool area, still in new building footprint
135 —	brick fragments (FILL) USC: (SP-SM)*, medium dense, brick and	- □ ****		8 5 5	2	12	I	-
	concrete fragments, water in tip of spoon @ 2.5' , moist @ 5.0'	5 — (111) - (111) - (111) - (111) - (111)		4 5 5	3	4	D	
130 -	Gray to orange brown, mottled pink, moist, medium stiff, medium plastic, lean CLAY, little fine sand (Natural) USC: (CL)*	10 -		5 5 5	4	18	I	PP = 1.7 TSF
125 — - - - -	Red to gray, moist, medium dense, medium plastic, clayey fine SAND USC: (SC)* 11.7- 14.5-	-		3 4 8	5	18	ı	
120	Gray, moist, medium dense, non- plastic, silty medium to fine SAND USC: (SM)*	- 10000 - 10000 - 10000 - 10000 - 10000 - 10000	1					
- - - -	, wet @ 19.5' Boring Terminated at 21 Ft.	20 - 11111		4 5 6	6	18	I	
115 —		-						
<u> </u>		25 —						_
110 —								
 - -		30 —						_
105								1

* Visual Description - in general accordance with ASTM D 2488 and AASHTO M145 Notes: Surface elevations provided by Ben Dyer Associates, Inc.

Enco	untered	4.0'	
Comp	letion		
On	at		
On 5/20	at	Dry	2.2'

Water

Caved

Project Name: Glenarden Apartments Contracted With: Pennrose Properties

Project Location: Prince George's County, Maryland

Boring Location:

Surf. Elev.: 136.94 Hammer Wt. 140 lb. Elev. from: Survey Hammer Drop: 30" Sampler Size: 2" split spoon Offset Elev: Offset Dist :

Rock Core Dia.: Hole Diameter: 8" Boring Method: HSA Foreman: Allied Inspector: JAF Date Started: 5/19/16

BORING NO. **B-36**

Page 1 of 1

JOB NO. **16163**

Date Finished: 5/19/16

Office: (410) 553-0802

Fax #: (410) 553-0808

Offset Dist.:	Offset Direction:									Date Finished: 5/19/16
Elev.	Soil Description				S	ample [Data		Ę	
136.94	Color, Moisture, Density Plasticity, Size Proportions		Depth	Type		Blow Counts	#	Recovery	Condition	Boring & Sample Notes
135 — -	Tan brown, moist, medium dense, non-plastic, silty SAND ¬ and GRAVEL including asphalt	0 -	4 14 4 14 4 14 4 14 4 14 4 14 4 14 4 1		4 4 8		1	2	D	
- - -	\and concrete fragments (FILL) \\ \ USC: (SP-SM)* \\ Gray, mottled orange brown, \\ moist, very stiff, medium plastic,\\\	5 -	7.7.7.		4 7 9 4			18	ı	PP = 4.0 TSF
130	lean CLAY with fine sand USC: (CL)* Tan, moist, medium dense, medium plastic, clayey medium	-	XXX XXX 111111 1111111 1111111		4 5 5 5		4	18	1	-
125	to fine SAND USC: (SC)* Tan to gray, moist, medium dense, non-plastic, silty medium to fine SAND USC: (SM)*	10 -			5 6 7		4	10	•	- - - -
120 —		15 -	11000000000000000000000000000000000000		8 10 11		5	18		- - -
	, orange, brown, wet @ 19.5'	- 20 —			8 16		6	18		
115 —	Boring Terminated at 21 Ft.		31:16 f f f		16					-
110		25 -								- -
110		30 —								
105 —		- - -								-

* Visual Description	 in general accordance with 	ASTM D 2488 and AASHTO M145

* Visual Description - in general accordance with ASTM D 2488 and AASHTO M145		Water	Caved
Notes: Surface elevations provided by Ben Dyer Associates, Inc.	Encountered	19.5'	
	Completion		
	On at		
	On 5/20 at	Dry	10.4'

Project Name: Glenarden Apartments Contracted With: Pennrose Properties

Contracted With: Pennrose Properties
Project Location: Prince George's County, Maryland

Boring Location: N: 458522 E: 1352172

Surf. Elev.: 134.50
Elev. from: Survey
Offset Elev:

Offset Dist.:

Hammer Wt. 140 lb.
Hammer Drop: 30"
Sampler Size: 2" split spoon

Offset Direction:

Rock Core Dia.:
Hole Diameter: 8"
Boring Method: HSA

JOB NO. 16163
Page 1 of 1
Foreman: Allied

BORING NO. **B-37**

Office: (410) 553-0802

Fax #: (410) 553-0808

Inspector: JAF
Date Started: 5/18/16
Date Finished: 5/18/16

Oliset Dist.:	Oliset Direction.									Date Finished: 3/10/10	
Elev.	Soil Description				1	Sample [Data		on		
134.50	Color, Moisture, Density Plasticity, Size Proportions		Depth	Type	:	Blow Counts	#	Recovery	Condition	Boring & Sample Notes	
135	Tan brown to gray, moist, loose, slightly plastic, silty medium to		# 12 % 1 # 12 % 1 # 12 % 1 # 15 % 1		5 3 2		1	12	I		-
130	¬ fine SAND and GRAVEL √including brick, concrete and √asphalt fragments (FILL) √ USC: (SP-SM)* /4.5-		11.0.01 11.0.01 11.0.01 11.0.01		4 4 4		2	18	I		- -
-	Tan brown, moist, loose, slightly plastic, silty fine SAND with gravel including brick fragments, trace organics (FILL)	5 -			5 4 3		3	8	I	PP = 1.8 TSF	- - -
125	Orange to gray brown, moist, medium stiff, medium plastic, fine sandy lean CLAY (Possible FILL)	10 -			3 4 3		4	18	I	PP = 0.7 TSF	
120 -	Gray, mottled orange brown, moist, medium stiff, high plastic, fat CLAY, with fine to very fine sand (Natural) USC: (CH)* Gray to tan brown, wet, medium	15 -			4 3 5		5	18	I		
115 —	stiff, medium plastic, fine sandy lean CLAY USC: (CL)* Red, mottled orange brown and	20 –	₩		7 5 8		6	18	I	PP = 2.5 TSF	
-	gray, moist, stiff, medium plastic, lean CLAY, little fine sand USC: (CL)* , very stiff @ 21.5'	-			6 8 8		7	18	I	PP = 3.1 TSF	-
110	Boring Terminated at 23 Ft.	25 -	-								_
105			- -								- - -
105		30 -	-								
			+								-

* Visual Description - in general accordance with ASTM D 2488 and AASHTO M145	
Notes: Surface elevations provided by Ben Dyer Associates, Inc.	Encountere

Encour	ntered	18.0'	
Comple	etion	Dry	6.0'
On	at		
On 5/19	at	Dry	5.0'

Water

Caved

Office: (410) 553-0802


Fax #: (410) 553-0808

Page 1 of 1

Project Name: Glenarden Apartments BORING NO. B-38 Contracted With: Pennrose Properties JOB NO. 16163

Project Location: Prince George's County, Maryland N: 458508 E: 1352028 Boring Location:

Surf. Elev.: 126.06 Hammer Wt. 140 lb. Rock Core Dia.: Foreman: Allied Elev. from: Survey Hammer Drop: 30" Hole Diameter: 8" Inspector: JAF Sampler Size: 2" split spoon Boring Method: HSA Date Started: 5/18/16 Offset Elev: Date Finished: 5/18/16 Offset Dist.: Offset Direction:



* Visual Description - in general accordance with ASTM D 2488 and AASHTO M145		Water	Caved
Notes: Surface elevations provided by Ben Dyer Associates, Inc.	Encountered		
	Completion		
	On at	5.3'	6.5'
	On 5/19 at	12.8'	Pipe

Project Name: Glenarden Apartments Contracted With: Pennrose Properties

вогіng no. **B-39** јов no. 16163 Page 1 of 1


111-4--

Office: (410) 553-0802

Fax #: (410) 553-0808

Project Location: Prince George's County, Maryland
Boring Location: N: 458491 E: 1351889

Surf. Elev.: 117.65 Hammer Wt. 140 lb. Rock Core Dia.: Foreman: Allied
Elev. from: Survey Hammer Drop: 30" Hole Diameter: 8" Inspector: JAF
Offset Elev: Sampler Size: 2" split spoon Boring Method: HSA Date Started: 5/18/16



Visual Description - in general accordance with ASTM D 2466 and AASHTO MT45			vvater	Caved
Notes: Surface elevations provided by Ben Dyer Associates, Inc.	Encou	ıntered		
	Comp	letion	Dry	17.0'
	On	at		
	On 5/19	at 24 hrs	9.8'	16.0'

Project Name: Glenarden Apartments Contracted With: Pennrose Properties

BORING NO. B-40 JOB NO. 16163

Project Location: Prince George's County, Maryland


Page 1 of 1

Office: (410) 553-0802

Fax #: (410) 553-0808

N: 458632 E: 1351875 Boring Location:

Surf. Elev.: 111.22 Hammer Wt. 140 lb. Rock Core Dia.: Foreman: Allied Elev. from: Survey Hammer Drop: 30" Hole Diameter: 8" Inspector: JAF Sampler Size: 2" split spoon Boring Method: HSA Date Started: 5/18/16 Offset Elev: Date Finished: 5/18/16 Offset Dist.: Offset Direction:



Visual Description - in general accordance with ASTM D 2488 and AASTTO MT45		vvater	Caved
Notes: Surface elevations provided by Ben Dyer Associates, Inc.	Encountered	Dry	
	Completion	Dry	9.0'
	On at		
	On 5/19 at	7.3'	8.0'

Project Name: Glenarden Apartments Contracted With: Pennrose Properties

Project Location: Prince George's County, Maryland

N: 458636 E: 1351999 Boring Location: Surf. Elev.: 124.29 Hammer Wt. 140 lb.

Elev. from: Survey Hammer Drop: 30" Sampler Size: 2" split spoon Offset Elev: Offset Dist.: Offset Direction:


JOB NO. 16163 Page 1 of 1 Rock Core Dia.: Foreman: Allied

Hole Diameter: 8" Inspector: JAF Boring Method: HSA Date Started: 5/18/16 Date Finished: 5/18/16

Office: (410) 553-0802

Fax #: (410) 553-0808

BORING NO. **B-41**



* Visual Description -	· in general accordance with	ASTM D 2488 and AASHTO M145

* Visual Description - in general accordance with ASTM D 2488 and AASHTO M145		Water	Caved
Notes: Surface elevations provided by Ben Dyer Associates, Inc.	Encountered	Dry	
	Completion	16.0'	17.0'
	On at		
	On 5/19 at	8.4'	13.0'

Project Name: Glenarden Apartments Contracted With: Pennrose Properties

BORING NO. B-42 JOB NO. **16163**

Project Location: Prince George's County, Maryland


Page 1 of 1

Office: (410) 553-0802

Fax #: (410) 553-0808

N: 458654 E: 1352112 Boring Location:

Hammer Wt. 140 lb. Surf. Elev.: 124.16 Rock Core Dia.: Foreman: Allied Hammer Drop: 30" Hole Diameter: 8" Inspector: JAF Elev. from: Survey Sampler Size: 2" split spoon Boring Method: HSA Date Started: 5/18/16 Offset Elev: Date Finished: 5/18/16 Offset Dist.: Offset Direction:



Visual Description - in general accordance with ASTM D 2488 and AASHTO M145 Water Caved Notes: Surface elevations provided by Ben Dyer Associates, Inc. Encountered Dry Dry Completion 17.5' On On 5/19 15.5' Dry

Project Name: Glenarden Apartments Contracted With: Pennrose Properties

BORING NO. **B-48** JOB NO. 16163

Project Location: Prince George's County, Maryland


Page 1 of 1

Office: (410) 553-0802

Fax #: (410) 553-0808

Boring Location: N: 458123 E: 1352432

Surf. Elev.: 129.35 Hammer Wt. 140 lb. Rock Core Dia.: Foreman: Allied
Elev. from: Survey Hammer Drop: 30" Hole Diameter: 8" Inspector: JFD
Offset Elev: Sampler Size: 2" split spoon Boring Method: HSA Date Started: 5/20/16
Offset Dist.: Date Finished: 5/20/16



* Visual Description - in general accordance with ASTM D 2488 and AASHTO M145

Encou	ntered	2.5'	
Compl	etion		7.0'
On	at		
On 5/24	at	Dry	0.0'

Water

Caved

Г	Notes:	Surface	elevations	provided by	Ben Dyer	Associates, Inc.	

Rock Core Dia.:

Project Name: Glenarden Apartments
Contracted With: Pennrose Properties

Project Location: Prince George's County, Maryland
Boring Location: N: 458133 E: 1352494

Surf. Elev.: 125.50 Hammer Wt. 140 lb.

Elev. from: Survey Hammer Drop: 30"

Offset Elev: Sampler Size: 2" split spoon

Offset Dist.: Offset Direction:


Office: (410) 553-0802

Fax #: (410) 553-0808

BORING NO. B-49

Foreman: Allied

Hole Diameter: 8" Inspector: JFD
Boring Method: HSA Date Started: 5/20/16
Date Finished: 5/20/16



Visual Description - in general accordance with ASTM D 2488 and AASHTO M145	
Notes: Surface elevations provided by Ben Dyer Associates, Inc.	Encountered
	Completion

Enco	ounterea	DIY	
Com	pletion	Dry	6.0'
On	at		
On 5/2	4 at	4.0'	4.5'

Water

Caved

Project Name: Glenarden Apartments Contracted With: Pennrose Properties


BORING NO. B-50 JOB NO. 16163 Page 1 of 1

Office: (410) 553-0802

Fax #: (410) 553-0808

Project Location: Prince George's County, Maryland N: 458169 E: 1352449 Boring Location:

Hammer Wt. 140 lb. Surf. Elev.: 129.98 Rock Core Dia.: Foreman: Allied Hammer Drop: 30" Hole Diameter: 8" Inspector: JAF Elev. from: Survey Sampler Size: 2" split spoon Boring Method: HSA Date Started: 5/19/16 Offset Elev: Date Finished: 5/19/16 Offset Dist.: Offset Direction:



* Visual Description - in general accordance with ASTM D 2488 and AASHTO M145		Water	Caved
Notes: Surface elevations provided by Ben Dyer Associates, Inc.	Encountered	Dry	
	Completion		
	On at		
	On 5/20 at	11.5'	13.0'

Project Name: Glenarden Apartments Contracted With: Pennrose Properties


BORING NO. B-51 JOB NO. 16163 Project Location: Prince George's County, Maryland Page 1 of 1

Office: (410) 553-0802

Fax #: (410) 553-0808

N: 458239 E: 1352482 Boring Location:

Hammer Wt. 140 lb. Surf. Elev.: 132.16 Rock Core Dia.: Foreman: Allied Elev. from: Survey Hammer Drop: 30" Hole Diameter: 8" Inspector: JAF Sampler Size: 2" split spoon Boring Method: HSA Date Started: 5/19/16 Offset Elev: Date Finished: 5/19/16 Offset Dist.: Offset Direction:



* Visual Description - in general accordance with ASTM D 2488 and AASHTO M145		Water	Caved
Notes: Surface elevations provided by Ben Dyer Associates, Inc.	Encountered	13.5'	
	Completion		
	On at		
	On 5/20 at	10.2'	14.5'

Project Name: Glenarden Apartments Contracted With: Pennrose Properties


BORING NO. **B-52** JOB NO. 16163 Project Location: Prince George's County, Maryland Page 1 of 1

Office: (410) 553-0802

Fax #: (410) 553-0808

N: 458233 E: 1352410 Boring Location:

Hammer Wt. 140 lb. Surf. Elev.: 132.16 Rock Core Dia.: Foreman: Allied Elev. from: Survey Hammer Drop: 30" Hole Diameter: 8" Inspector: JFD Sampler Size: 2" split spoon Boring Method: HSA Date Started: 5/20/16 Offset Elev: Date Finished: 5/20/16 Offset Dist.: Offset Direction:



* Visual Description - in general accordance with ASTM D 2488 and AASHTO M145	5	Water	Caved
Notes: Surface elevations provided by Ben Dyer Associates, Inc.	Encountered	8.5'	
	Completion	6.0'	11.0'
	On at		
	On 5/31 at	Drv	4.3'

Office: (410) 553-0802

Fax #: (410) 553-0808

BORING NO. B-53

Water

Caved

Page 1 of 1


JOB NO. 16163

Project Name: Glenarden Apartments Contracted With: Pennrose Properties

Contracted With: Pennrose Properties
Project Location: Prince George's County, Maryland

Boring Location: N: 458313 E: 1352517

Surf. Elev.: 132.47 Hammer Wt. 140 lb. Rock Core Dia.: Foreman: Allied
Elev. from: Survey Hammer Drop: 30" Hole Diameter: 8" Inspector: JAF
Offset Elev: Sampler Size: 2" split spoon Boring Method: HSA Date Started: 5/19/16
Offset Dist.: Date Finished: 5/19/16



Notes: Surface elevations provided by Ben Dyer Associates, Inc.	Encountered	13.5'	
	Completion		
	On at		
	On 5/20 at 24 h	rs 10.5'	15.0'

Project Name: Glenarden Apartments Contracted With: Pennrose Properties

JOB NO. 16163 Project Location: Prince George's County, Maryland Page 1 of 1


Office: (410) 553-0802

Fax #: (410) 553-0808

BORING NO. B-54

N: 458367 E: 1352439 Boring Location:

Hammer Wt. 140 lb. Surf. Elev.: 136.18 Rock Core Dia.: Foreman: Allied Hammer Drop: 30" Hole Diameter: 8" Inspector: JAF Elev. from: Survey Sampler Size: 2" split spoon Boring Method: HSA Date Started: 5/19/16 Offset Elev: Offset Direction: E Date Finished: 5/19/16 Offset Dist.: 10'



* Visual	D	esc	riptior	ı - in	genera	l acco	ordar	nce	with A	STM [D 248	8 ar	nd A	ASHTO	M145
	$\overline{}$	-					- 1 -			_					

" Visual Description - In general accordance with ASTM D 2488 and AASHTO M145		Water	Caved
Notes: Surface elevations provided by Ben Dyer Associates, Inc.	Encountered	13.5,	
	Completion	12.3'	12.5'
	On at		
	On 5/20 at	12.4'	13.4'

Office: (410) 553-0802

Fax #: (410) 553-0808

BORING NO. B-55

Page 1 of 1


JOB NO. 16163

Project Name: Glenarden Apartments Contracted With: Pennrose Properties

Project Location: Prince George's County, Maryland

N: 458420 E: 1352504 Boring Location:

Surf. Elev.: 138.42 Hammer Wt. 140 lb. Rock Core Dia.: Foreman: Allied Hammer Drop: 30" Hole Diameter: 8" Inspector: JAF Elev. from: Survey Sampler Size: 2" split spoon Boring Method: HSA Date Started: 5/19/16 Offset Elev: Date Finished: 5/19/16 Offset Dist.: Offset Direction:



* Visual Description - in general accordance with ASTM D 2488 and AASHTO M145		Water	Caved
Notes: Surface elevations provided by Ben Dyer Associates, Inc.	Encountered	Dry	
	Completion	Dry	14.0'
	On at		
	On 5/20 at	Dry	14 2'

Project Name: Glenarden Apartments Contracted With: Pennrose Properties

Project Location: Prince George's County, Maryland N: 458476 E: 1352459

Surf. Elev.: 139.92 Elev. from: Survey Offset Elev:

Boring Location:

Hammer Wt. 140 lb. Hammer Drop: 30" Sampler Size: 2" split spoon Rock Core Dia.: Hole Diameter: 8" Boring Method: HSA Foreman: Allied Inspector: JAF Date Started: 5/19/16

BORING NO. **B-56**

Page 1 of 1

JOB NO. **16163**

Office: (410) 553-0802

Fax #: (410) 553-0808

ffset Dist.:	Offset Direction:	poon		ornig	Metriou.	110/			Date Started: 5/19/16
Elev.	Soil Description				Samp	le Data		E	
39.92	Color, Moisture, Density Plasticity, Size Proportions	[Depth	Type	Blow	#	Recovery	Condition	Boring & Sample Notes
140	Gray to orange brown, moist, medium stiff, medium plastic, lean CLAY with fine sand	0 -		7	1 3 5	1	15	I	PP > 4.5 TSF
- - -	USC: (CL)*, mottled black, medium to fine sandy lean CLAY @ 2.5'	-			3 4 7	2	18	1	PP = 1.7 TSF
135 —	Tan to orange brown to gray, moist, loose, medium plastic, clayey medium to fine SAND, — layers of sandy lean clay	5 - -	7.2.2 7.2.4 7.2.2 7.2.2 7.2.2 TITT		2 3 5	3	12	I	- - -
130	Tan to orange brown, moist, medium dense, non-plastic, silty medium to fine SAND USC: (SM)*	10 —	00000 0000 0000 0000 0000 0000 0000 0000		3 5 6	4	18	I	- - -
125 —		15 —			4 5 7	5	17	I	- - -
120	Red to orange brown, wet, stiff, medium to high plastic, lean to fat CLAY, trace to little fine sand USC: (CL/CH)* Boring Terminated at 20 Ft.				3 5 8	6	15	I	- - - - -
115		25 — -							- - - -
110 —		30 —							- - -
<u>†</u>		-							-

* Visual Description - in general accordance with ASTM D 2488 and AASHTO M145		Water	Caved
Notes: Surface elevations provided by Ben Dyer Associates, Inc.	Encount	ered 18.	5'
	Comple	tion	
	On	at	
	On 5/20	at Dry	15.3'

Surf. Elev.: 132.43

Record of Soil Exploration

Rock Core Dia.:

Hole Diameter: 8"

Project Name: Glenarden Apartments Contracted With: Pennrose Properties

Project Location: Prince George's County, Maryland

Hammer Wt. 140 lb.

N: 458583 E: 1352286 Boring Location:

Elev. from: Survey Hammer Drop: 30" Sampler Size: 2" split spoon Offset Elev:


BORING NO. B-57 JOB NO. 16163

Page 1 of 1

Office: (410) 553-0802

Fax #: (410) 553-0808

Foreman: Allied Inspector: JFD Boring Method: HSA Date Started: 5/20/16 Date Finished: 5/20/16



* Visual Description - in general accordance with ASTM D 2488 and AASHTO M145		Water	Caved
Notes: Surface elevations provided by Ben Dyer Associates, Inc.	Encountered	8.5'	
	Completion		
	On at		
	On 5/24 at	6.7'	6.7'

Surf. Elev.: 136.82

Record of Soil Exploration

Project Name: Glenarden Apartments Contracted With: Pennrose Properties

Project Location: Prince George's County, Maryland

Boring Location:

Hammer Drop: 30" Elev. from: Survey Sampler Size: 2" split spoon Offset Elev: Offset Dist.: Offset Direction:

Hammer Wt. 140 lb.

BORING NO. B-58 JOB NO. 16163 Page 1 of 1

Office: (410) 553-0802

Fax #: (410) 553-0808

Rock Core Dia.: Foreman: Allied Hole Diameter: 8" Inspector: JAF Boring Method: HSA Date Started: 5/19/16

Date Finished: 5/19/16 Sample Data Elev. Soil Description Condition Boring & Sample Blow Depth Color, Moisture, Density Plasticity, Size Proportions Notes 136.82 -0.0 18 Tan to gray, dry, very loose, medium plastic, clayey fine 135 SAND with gravel including concrete fragments (FILL) PP > 1.0 TSF 18 Tan gray mottled orange brown, _ 5 moist, soft, medium plastic, silty 18 lean CLAY, little fine sand (Natural) 130 USC: (CL)* Orange brown to tan, moist, 18 loose, slightly to medium plastic, silty fine SAND, lumps of sandy 10 clay USC: (SM)* 125 ---, medium dense @ 8.5' 18 15 120 18 ---, tan, wet @ 18.5' 20 Boring Terminated at 20 Ft. 115 25 110 30 105

* Visual Description - in general accordance with ASTM D 2488 and AASHTO M145		Water	Caved
Notes: Surface elevations provided by Ben Dyer Associates, Inc.	Encountered		
	Completion		
	On at		
	On 5/20 at	Dry	11.1'

Surf. Elev.: 132.38

Elev.

Record of Soil Exploration

Project Name: Glenarden Apartments Contracted With: Pennrose Properties

Project Location: Prince George's County, Maryland

Boring Location:

Hammer Drop: 30" Elev. from: Survey Sampler Size: 2" split spoon Offset Elev: Offset Dist.: Offset Direction:

Soil Description

Hammer Wt. 140 lb.


BORING NO. R-13 JOB NO. 16163 Page 1 of 1

Office: (410) 553-0802

Fax #: (410) 553-0808

Rock Core Dia.: Foreman: Allied Inspector: JAF

Hole Diameter: 8" Boring Method: HSA Date Started: 5/18/16 Date Finished: 5/18/16 Sample Data Condition Boring & Sample Blow Depth Notes -0.0



* Visual Description - in general accordance with ASTM D 2488 and AASHTO M145		Water	Caved
Notes: Surface elevations provided by Ben Dyer Associates, Inc.	Encountered	8.5'	
	Completion	Dry	11.0'
	On at		
	On 5/19 at	8.2'	9.0'

Project Name: Glenarden Apartments Contracted With: Pennrose Properties

Project Location: Prince George's County, Maryland

Boring Location:

Surf. Elev.: 141.39 Hammer Wt. 140 lb. Elev. from: Survey Hammer Drop: 30" Sampler Size: 2" split spoon Offset Elev: Offset Dist.: Offset Direction:

Rock Core Dia.: Hole Diameter: 8" Boring Method: HSA

Foreman: Allied Inspector: JAF Date Started: 5/19/16

Date Finished: 5/19/16


BORING NO. R-14

Page 1 of 1

JOB NO. 16163

Office: (410) 553-0802

Fax #: (410) 553-0808



* Visual Description - in general accordance with ASTM D 2488 and AASHTO M145		Water	Caved
Notes: Surface elevations provided by Ben Dyer Associates, Inc.	Encounte	red Dry	
	Completion	on	
	On a	t	
	On 5/20 a	t Dry	3.2'

Office: (410) 553-0802


Fax #: (410) 553-0808

Project Name: Glenarden Apartments Contracted With: Pennrose Properties

BORING NO. R-15 JOB NO. 16163 Project Location: Prince George's County, Maryland Page 1 of 1

Boring Location:

Surf. Elev.: 135.65 Hammer Wt. 140 lb. Rock Core Dia.: Foreman: Allied Elev. from: Survey Hammer Drop: 30" Hole Diameter: 8" Inspector: JAF Sampler Size: 2" split spoon Boring Method: HSA Date Started: 5/20/16 Offset Elev: Date Finished: 5/20/16 Offset Dist.: Offset Direction:



* Visual Description - in general accordance with ASTM D 2488 and AASHTO M145		Water	Caved
Notes: Surface elevations provided by Ben Dyer Associates, Inc.	Encountered	5.0'	
	Completion		
	On at		
	On 5/24 at	9.0'	Pipe

Project Name: Glenarden Apartments Contracted With: Pennrose Properties

Project Location: Prince George's County, Maryland

Test Pit Location: N:

Offset Elev:

Surf. Elev.: $127.0\pm$ Hammer Wt. Elev. from: Topo Hammer Drop: Sampler Size:

Pit Width: 3.5 Pit Length: 25'

Orientation: E-W Excavator:

TEST PIT NO. R-16 JOB NO. 16163


Page 1 of 1


Office: (410) 553-0802

Fax #: (410) 553-0808

Foreman: Allied Inspector: JFD

Date Started: 6/8/2016 Date Finished: 6/8/2016





١	Notes: Surface elev	ations from topographic map provided by Ben Dyer	
	Associates,	Inc.	

Enc	ountered	Dry	
Con	npletion		
On	at		
On	at		

Water

Caved

Surf. Elev.: 133.54

Record of Soil Exploration

Project Name: Glenarden Apartments Contracted With: Pennrose Properties

Project Location: Prince George's County, Maryland

Boring Location: N:

Elev. from: Survey Hammer Drop: 30"
Offset Elev: Sampler Size: 2" split spoon
Offset Dist.: Offset Direction:

Hammer Wt. 140 lb.

BORING NO. **R-17** JOB NO. 16163 Page 1 of 1

Office: (410) 553-0802


Fax #: (410) 553-0808

Rock Core Dia.: Foreman: Allied
Hole Diameter: 8" Inspector: JFD
Boring Method: HSA Date Started: 5/20/16

Date Finished: 5/20/16

Water

Caved



Notes: Surface elevations provided by Ben Dyer Associates, Inc.	Encount	tered	Dry	
	Comple	tion	Dry	7.0'
	On	at		
	On	at		

Project Name: Glenarden Apartments Contracted With: Pennrose Properties

Project Location: Prince George's County, Maryland

Boring Location: N:

Surf. Elev.: 142.24 Hammer Wt. 140 lb.

Elev. from: Survey Hammer Drop: 30"

Offset Elev: Sampler Size: 2" split spoon

Offset Dist.: Offset Direction:

вокінд но. **R-18** јов но. 16163 Page 1 of 1

Office: (410) 553-0802

Fax #: (410) 553-0808

Rock Core Dia.: Foreman: Allied
Hole Diameter: 8" Inspector: JAF
Boring Method: HSA Date Started: 5/19/16
Date Finished: 5/19/16

Sample Data Elev. Soil Description Boring & Sample Blow Counts Depth Color, Moisture, Density Plasticity, Size Proportions Notes 142.24 -0.0 18 Bulk sample obtained Tan, moist, loose, slightly to from 0-8' medium plastic, clayey, silty medium to fine SAND 140 ___USC: (SC-SM)* PP > 4.5 TSF Gray to red, dry, very stiff, medium plastic, fine sandy lean 5 CLAY 12 PP > 4.5 TSF USC: (CL)* 135 Orange brown to gray, dry, medium dense, medium plastic, 12 clayey fine SAND 10 USC: (SC)* Tan, dry, medium dense, non-12 plastic, silty medium to fine 130 SAND USC: (SM)* Boring Terminated at 13 Ft. 15 125 20 120 25 115 30 110

" Visual Description - In general accordance with ASTM D 2488 and AASHTO M145		Water	Caved
Notes: Surface elevations provided by Ben Dyer Associates, Inc.	Encountered	Dry	
	Completion	Dry	7.0'
	On at		
	O= F/20 =+	Dmi	C 4!

Project Name: Glenarden Apartments Contracted With: Pennrose Properties

Project Location: Prince George's County, Maryland

Boring Location: N:

Surf. Elev.: 132.40

Elev. from: Survey

Offset Elev:

Offset Dist.:

Hammer Wt. 140 lb.

Hammer Drop: 30"

Sampler Size: 2" split spoon

Offset Direction:

Rock Core Dia.:
Hole Diameter: 8"
Boring Method: HSA

Foreman: Allied
Inspector: JAF

BORING NO. R-19

Page 1 of 1

JOB NO. 16163

Date Started: 5/18/16

Date Finished: 5/18/16

Water

Caved


8.0'

7.0'

Office: (410) 553-0802

Fax #: (410) 553-0808

Sample Data Elev. Soil Description Condition Boring & Sample Blow Counts Depth Color, Moisture, Density Plasticity, Size Proportions Notes 132.40 10 Light brown to gray brown, moist, loose, slightly to medium plastic, clayey, silty fine SAND 130 ____UŚC: (_SC-SM_)* 10 Tan brown to orange brown, moist, medium dense, non-5 plastic, silty medium to fine 10 SAND USC: (SM)* ---, loose @ 5.0' 125 Red, mottled orange and gray, moist, medium stiff, medium 12 PP = 2.0 TSF plastic, lean CLAY, trace to little 10 fine sand Boring Terminated at 11 Ft. 120 15 115 20 110 25 105 30 100



Notes: Surface elevations provided by Ben Dyer Associates, Inc.	Enc	countered		
	Cor	npletion	Dry	8
	On	at		
	0 5/4		0.51	_

Project Name: Glenarden Apartments
Contracted With: Pennrose Properties

BORING NO. **R-20** JOB NO. 16163

Project Location: Prince George's County, Maryland

Page 1 of 1


111-4--

Office: (410) 553-0802

Fax #: (410) 553-0808

Boring Location: N: 458650 E: 1352211

Surf. Elev.: 129.26 Hammer Wt. 140 lb. Rock Core Dia.: Foreman: Allied
Elev. from: Survey Hammer Drop: 30" Hole Diameter: 8" Inspector: JAF
Offset Elev: Sampler Size: 2" split spoon Boring Method: HSA Date Started: 5/18/16
Offset Dist.: Date Finished: 5/18/16



Visual Description - In general accordance with ASTM D 2466 and AASHTO WIT45			vvater	Caved
Notes: Surface elevations provided by Ben Dyer Associates, Inc.	Encoun	tered	Dry	
	Comple	tion	8.5'	
	On	at		
	On 5/19	at 24 hrs	8.2'	8.5'

Project Name: Glenarden Apartments Contracted With: Pennrose Properties


BORING NO. R-21 JOB NO. 16163 Project Location: Prince George's County, Maryland Page 1 of 1

Office: (410) 553-0802

Fax #: (410) 553-0808

Boring Location:

Hammer Wt. 140 lb. Surf. Elev.: 126.01 Rock Core Dia.: Foreman: Allied Hammer Drop: 30" Hole Diameter: 8" Inspector: JAF Elev. from: Survey Sampler Size: 2" split spoon Boring Method: HSA Date Started: 5/18/16 Offset Elev: Date Finished: 5/18/16 Offset Dist.: Offset Direction:



* Visual Description - in general accordance with ASTM D 2488 and AASHTO M145		Water	Caved
Notes: Surface elevations provided by Ben Dyer Associates, Inc.	Encountered	Dry	
	Completion	Dry	13.0'
	On at		
	On 5/19 at 24 hr	rs 7.0'	9.0'

Project Name: Glenarden Apartments
Contracted With: Pennrose Properties


BORING NO. **R-22** JOB NO. 16163 Page 1 of 1

Office: (410) 553-0802

Fax #: (410) 553-0808

Project Location: Prince George's County, Maryland Boring Location: N: E:

Surf. Elev.: 116.24 Hammer Wt. 140 lb. Rock Core Dia.: Foreman: Allied
Elev. from: Survey Hammer Drop: 30" Hole Diameter: 8" Inspector: JAF
Offset Elev: +1.0' Sampler Size: 2" split spoon Boring Method: HSA Date Started: 5/18/16
Offset Dist.: 30' Offset Direction: NE Date Finished: 5/18/16



* Visual Description - in general accordance with ASTM D 2488 and AASHTO M145		Water	Caved
Notes: Surface elevations provided by Ben Dyer Associates, Inc.	Encountered	Dry	
	Completion	Dry	7.5'
	On at		
	On 5/19 at 24 h	rs Drv	7 9'

Surf. Elev.: 121±

Record of Soil Exploration

Project Name: Glenarden Apartments Contracted With: Pennrose Properties

Hammer Wt. 140 lb.

Project Location: Prince George's County, Maryland Boring Location:

Hammer Drop: 30" Elev. from: Topo Sampler Size: 2" split spoon Offset Elev: Offset Dist.: Offset Direction:

Rock Core Dia.: Hole Diameter: 8" Boring Method: HSA

Foreman: Allied Inspector: JAF Date Started: 5/18/16

Date Finished: 5/18/16


BORING NO. R-23

Page 1 of 1

JOB NO. 16163

Office: (410) 553-0802

Fax #: (410) 553-0808



* Visual Description - in general accordance with ASTM D 2488 and AASHTO M145		Water	Caved
Notes: Surface elevations provided by Ben Dyer Associates, Inc.	Encountered		
	Completion		
	On at		
	On 5/19 at 24 h	rs Dry	2.5'

Office: (410) 553-0802

Fax #: (410) 553-0808


BORING NO. R-24

Project Name: Glenarden Apartments Contracted With: Pennrose Properties

JOB NO. 16163 Project Location: Prince George's County, Maryland Page 1 of 1

Boring Location:

Hammer Wt. 140 lb. Surf. Elev.: 136.91 Rock Core Dia.: Foreman: Allied Hammer Drop: 30" Hole Diameter: 8" Inspector: JAF Elev. from: Survey Sampler Size: 2" split spoon Boring Method: HSA Date Started: 5/19/16 Offset Elev: Date Finished: 5/19/16 Offset Dist.: Offset Direction:



* Visual Description - in general accordance with ASTM D 2488 and AASHTO M145		Water	Caved
Notes: Surface elevations provided by Ben Dyer Associates, Inc.	Encountered	Dry	
	Completion		
	On at		
	On 5/20 at 24 h	nrs Dry	4.9'

Rock Core Dia.: Hole Diameter: 8"

Project Name: Glenarden Apartments Contracted With: Pennrose Properties

Project Location: Prince George's County, Maryland

Boring Location:

Surf. Elev.: 128.90 Hammer Wt. 140 lb. Elev. from: Survey Hammer Drop: 30"

Sampler Size: 2" split spoon Offset Elev: Offset Dist.: Offset Direction:

BORING NO. R-26 JOB NO. **16163**

Page 1 of 1

Office: (410) 553-0802

Fax #: (410) 553-0808

Foreman: Allied Inspector: JAF Date Started: 5/18/16 Boring Method: HSA

Date Finished: 5/18/16

Offset Dist.:	Offset Direction:								Date Finished: 5/18/16
Elev.	Soil Description					ple Data	1 >	ioi	
128.90	Color, Moisture, Density Plasticity, Size Proportions		Depth	Туре	Blow	Counts	Recovery	Condition	Boring & Sample Notes
- - - -	Tan brown, moist, medium dense, medium plastic, clayey fine SAND, little gravel, trace	0 -	7.7.7.7 7.7.7.7 7.7.7.7 7.7.7.7		4 5 5	1		I	-
125 —	\asphalt fragments (FILL) / \(\subseteq \subs	-	C		2 3 5	2	15	I	PP = 4.4 TSF
† †	moist, medium stiff, medium plastic, lean CLAY little fine sand (Natural)	5 -			6 8 10	3	18	1	PP > 4.5 TSF
120	Tan to orange brown, moist, medium dense, medium plastic, clayey fine SAND USC: (SC)*	10 -	XXX XXX XXX XXX		7 9 16	4	18	I	
115 —	Boring Terminated at 10 Ft.	-							
†- †- †-		15 -							-
110 -		20 -							- -
- - - -		-							-
105 -		25 -							- - -
100 -		-							
		30 -							
+		-	-						-

* Visual Description - in general accordance with ASTM D 2488 and AASHTO M145 Notes: Surface elevations provided by Ben Dyer Associates, Inc.

Encou	Dry		
Compl	etion	Dry	5.0'
On	at		
On 5/19	at 24 hrs	Dry	3.8'

Water

Caved

Project Name: Glenarden Apartments Contracted With: Pennrose Properties

Project Location: Prince George's County, Maryland

Boring Location: N:

Surf. Elev.: 121.06 Hammer Wt. 140 lb.

Elev. from: Survey Hammer Drop: 30"

Offset Elev: Sampler Size: 2" split spe

Hammer Wt. 140 lb. Rock Core Dia.:
Hammer Drop: 30" Hole Diameter: 8"
Sampler Size: 2" split spoon Boring Method: HSA

ЈОВ NO. **16163** Page 1 of 1

BORING NO. SWM-8


Office: (410) 553-0802

Fax #: (410) 553-0808

Foreman: Allied
Inspector: JFD
Date Started: 5/20/16
Date Finished: 5/20/16

Water

Caved



Notes: Surface elevations provided by Ben Dyer Associates, Inc.	Encountered	2.5'	
	Completion		3.0'
	On at		
	On 5/24 at	6.0'	Pipe

Project Name: Glenarden Apartments Contracted With: Pennrose Properties

Project Location: Prince George's County, Maryland

Boring Location: N:

Surf. Elev.: 133.90 Hammer Wt. 140 lb.

Elev. from: Survey Hammer Drop: 30"

Offset Elev: Sampler Size: 2" split spoon

BORING NO. SWM-10


JOB NO. **16163**

Page 1 of 1

Office: (410) 553-0802

Fax #: (410) 553-0808

Rock Core Dia.: Foreman: Allied
Hole Diameter: 8" Inspector: JAF
Boring Method: HSA Date Started: 5/19/16



Nisual Description - in general accordance with ASTM D 2488 and AASHTO M145		Water
Notes: Surface elevations provided by Ben Dyer Associates, Inc.	Encountered	Dry
	Completion	

Compl	etion		
On	at		
On 5/20	at 24 hrs	12.7'	Pipe

Caved

KEY TO SYMBOLS

Symbol Description

Misc. Symbols

₩ater encountered during

drilling

24 hr water reading

Depth to caving

₩ater level at completion

Soil Samplers

Standard penetration test

Bag Sample

Monitor Well Details

temporary screened water
monitoring pipe, removed after
24 hour water reading

Strata

Poorly graded SAND with silt

Silty clayey SAND

//// Lean CLAY

Silty SAND

Clayey SAND

Notes:

- 1. Borings were performed from May 18, 2016 through May 20, 2016. Test pits were performed from June 1, 2016 through June 8, 2016.
- 2. These logs are subject to the limitations, conclusions, and recommendations in this report.
- 3. PP indicates results of pocket penetrometer, used to estimate the unconfined compressive strength of fine-grained soils.



Fat CLAY

Symbol Description



Poorly graded SAND with clay



Medium to highly plastic CLAY



Poorly graded GRAVEL



Poorly graded SAND

Office: (410) 553-0802

Fax #: (410) 553-0808

Water

Caved

Project Name: Glenarden Apartments

Contracted With: Pennrose Properties

Project Location: Prince George's County, Maryland


TEST PIT NO. TP-1

JOB NO. 16163

Page 1 of 1

Test Pit Location: N: E:

Surf. Elev.: $108\pm$ Pit Width: 3.5 Foreman: Allied Hammer Wt. Elev. from: Topo Pit Length: 10' Inspector: JFD Hammer Drop: Date Started: 6/1/2016 Offset Elev: Orientation: E-W Sampler Size: Date Finished: 6/1/2016 Offset Dist.: Offset Direction: Excavator:



* Visual Description - in general accordance with AST

Notes: Surface elevations from topographic map provided by Ben Dyer	Encountered	Dry
Associates, Inc.	Completion	7.0'
	On at	
	On at	

Office: (410) 553-0802

Fax #: (410) 553-0808

Water


Caved

TEST PIT NO. TP-2 Project Name: Glenarden Apartments Contracted With: Pennrose Properties JOB NO. 16163 Page 1 of 1

Project Location: Prince George's County, Maryland Test Pit Location:

Surf. Elev.: $124\pm$ Pit Width: 3.5 Hammer Wt. Foreman: Allied Elev. from: Topo Pit Length: 12' Inspector: JFD Hammer Drop:

Date Started: 6/1/2016 Offset Elev: Orientation: E-W Sampler Size: Date Finished: 6/1/2016 Offset Dist.: Offset Direction: Excavator:



* Visual Description - in general accordance with AST

Notes: Surface elevations from topographic map provided by Ben Dyer	Encountered	3.0'
Associates, Inc.	Completion	9.0'
	On at	
	On at	

Office: (410) 553-0802

Fax #: (410) 553-0808

Water

Caved

Project Name: Glenarden Apartments

Contracted With: Pennrose Properties

Project Location: Prince George's County, Maryland


TEST PIT NO. TP-3

JOB NO. 16163

Page 1 of 1

Test Pit Location: N: E:

Surf. Elev.: $131\pm$ Pit Width: 3.5 Foreman: Allied Hammer Wt. Elev. from: Topo Pit Length: 15' Inspector: JFD Hammer Drop: Date Started: 6/1/2016 Offset Elev: Orientation: N-S Sampler Size: Date Finished: 6/1/2016 Offset Dist.: Offset Direction: Excavator:



* Visual Description - in general accordance with AST

Notes: Surface elevations from topographic map provided by Ben Dyer	Encountered	Dry
Associates, Inc.	Completion	7.0'
	On at	
	On at	

Office: (410) 553-0802

Fax #: (410) 553-0808


Water

Caved

TEST PIT NO. TP-4 Project Name: Glenarden Apartments Contracted With: Pennrose Properties JOB NO. 16163 Page 1 of 1

Project Location: Prince George's County, Maryland Test Pit Location:

Surf. Elev.: $132\pm$ Pit Width: 3.5 Foreman: Allied Hammer Wt. Elev. from: Topo Pit Length: 12' Inspector: JFD Hammer Drop: Date Started: 6/1/2016 Offset Elev: Orientation: E-W Sampler Size:



* Visual Description - in general accordance with AST

Notes: Surface elevations from topographic map provided by Ben Dyer	Enco	untered	3.0'	
Associates, Inc.	Comp	oletion	10.0'	
	On	at		
	On	at		

Project Name: Glenarden Apartments

Contracted With: Pennrose Properties

Project Location: Prince George's County, Maryland


TEST PIT NO. TP-5

JOB NO. 16163

Page 1 of 1

Test Pit Location: N: E:

Surf. Elev.: $134\pm$ Hammer Wt. Pit Width: 3.5' Foreman: Allied Elev. from: Topo Hammer Drop: Pit Length: 15' Inspector: JFD Offset Elev: Sampler Size: Orientation: E-W Date Started: 6/1/2016 Offset Dist.: Offset Direction: Excavator: Date Finished: 6/1/2016



* Visual Description - in general accordance with ASTM D 2488

Notes: Surface elevations from topographic map provided by Ben Dyer
Associates, Inc.

Encountered		Dry	
Cor	npletion	11.0'	
On	at		
On	at		

Water

Caved

Office: (410) 553-0802

Fax #: (410) 553-0808

Office: (410) 553-0802

Fax #: (410) 553-0808

Water

Caved

Project Name: Glenarden Apartments

Contracted With: Pennrose Properties

Project Location: Prince George's County, Maryland


TEST PIT NO. TP-6

JOB NO. 16163

Page 1 of 1

Test Pit Location: N: E:

Surf. Elev.: $132\pm$ Pit Width: 3.5 Hammer Wt. Foreman: Allied Elev. from: Topo Pit Length: 15' Inspector: JFD Hammer Drop: Date Started: 6/1/2016 Offset Elev: Orientation: N-S Sampler Size: Date Finished: 6/1/2016 Offset Dist.: Offset Direction: Excavator:



* Visual Description - in general ac	ccordance with ASTM D 2488
--------------------------------------	----------------------------

Notes: Surface elevations from topographic map provided by Ben Dyer	En	ncountered	Dry
Associates, Inc.	Co	ompletion	11.0
	On	at	

Office: (410) 553-0802

Fax #: (410) 553-0808

Water

Caved

Project Name: Glenarden Apartments

Contracted With: Pennrose Properties


Project Location: Prince George's County, Maryland

TEST PIT NO. TP-7

JOB NO. 16163

Page 1 of 1

Project Location: Prince George's County, Maryland
Test Pit Location: N: E:



* Visual Description - in general accordance with AST

Notes: Surface elevations from topographic map provided by Ben Dyer	Enco	untered	Dry	
Associates, Inc.	Completion		Dry	9.0'
	On	at		
	On	at		

Office: (410) 553-0802

Fax #: (410) 553-0808


Water


Caved

TEST PIT NO. TP-8 Project Name: Glenarden Apartments Contracted With: Pennrose Properties JOB NO. 16163 Page 1 of 1

Project Location: Prince George's County, Maryland Test Pit Location:

Surf. Elev.: $138\pm$ Pit Width: 3.5 Hammer Wt. Foreman: Allied Elev. from: Topo Pit Length: 15' Inspector: JFD Hammer Drop: Date Started: 6/1/2016 Offset Elev: Orientation: E-W Sampler Size:





Notes: Surface elevations from topographic map provided by Ben Dyer	Encountered Dry			
Associates, Inc.	Com	pletion	Dry	9.0'
	On	at		
	On	at		

Office: (410) 553-0802

Fax #: (410) 553-0808

Water

Caved

Project Name: Glenarden Apartments

Contracted With: Pennrose Properties

Project Location: Prince George's County, Maryland


TEST PIT NO. TP-9

JOB NO. 16163

Page 1 of 1

Test Pit Location: N: E:

Surf. Elev.: $132\pm$ Pit Width: 3.5' Hammer Wt. Foreman: Allied Elev. from: Topo Pit Length: 12 Inspector: JFD Hammer Drop: Date Started: 6/1/2016 Offset Elev: Orientation: N-S Sampler Size: Date Finished: 6/1/2016 Offset Dist.: Offset Direction: Excavator:



* Visual Description -	in general accordance	with ASTM D 2488

Notes: Surface elevations from topographic map provided by Ben Dyer	Encountered	10.0'
Associates, Inc.	Completion	10.0'
	On at	
	On at	

Project Name: Glenarden Apartments

Contracted With: Pennrose Properties

Project Location: Prince George's County, Maryland

TEST PIT NO. TP-10

JOB NO. 16163

Page 1 of 1


Test Pit Location: N: E:


 Surf. Elev.: 138±
 Hammer Wt.
 Pit Width: 3.5'
 Foreman: Allied

 Elev. from: Topo
 Hammer Drop:
 Pit Length: 15'
 Inspector: JFD

 Offset Elev:
 Sampler Size:
 Orientation: E-W
 Date Started: 6/1/2016

 Offset Dist.:
 Offset Direction:
 Excavator:
 Date Finished: 6/1/2016





Notes: Surface elevations from topographic map provided by Ben Dye	;1
Associates, Inc.	

Enc	ountered	Dry	
Cor	npletion	Dry	6.0'
On	at		
On	at		

Water

Caved

Office: (410) 553-0802

Fax #: (410) 553-0808

Pit Width: 3.5

Orientation: N-S

Pit Length: 60'

Project Name: Glenarden Apartments
Contracted With: Pennrose Properties

Project Location: Prince George's County, Maryland

Test Pit Location: N: Surf. Elev.: $125.5\pm$

Elev. from: Topo

Offset Elev:

Hammer Wt. Hammer Drop:

Sampler Size:
Offset Direction:

јов no. 16163 Page 1 of 1

Foreman: Allied Inspector: JFD

Date Started: 6/8/2016
Date Finished: 6/8/2016

TEST PIT NO. TP-11

Office: (410) 553-0802

Fax #: (410) 553-0808

Offset Dist.: Excavator: Elev. Sample Soil Description Boring & Sample Depth Color, Moisture, Density Plasticity, Size Proportions 125.5± Notes 126 -0.0 0 Pit starts 27' South of B-49 Tan brown, moist, non-plastic, fine SAND and GRAVEL, some silt (Brick, concrete, and cinder blocks) (FILL) (Rubble) `USC:´(`SP-SM)^{*} 124 2 122 \subseteq 4 -Fill starts 9.0' North of start of pit Orange, wet, non to low plastic, silty fine SAND (Natural) Bulk sample obtained from 4.5' to 5.0' USC: (SM)* 120 6 Test Pit Terminated at 6 Ft. 118 8 116 10 114 12

	* Visual Description -	in general accordance	with ASTM D 2488
--	------------------------	-----------------------	------------------

Notes:	Surface elevations from topographic map provided by Ben Dyer
	Associates, Inc.

		Water	Caved
Enc	ountered	4.0'	
Con	npletion		
On	at		
On	at		

Project Name: Glenarden Apartments
Contracted With: Pennrose Properties

Contracted With: Pennrose Properties
Project Location: Prince George's County, Maryland

Test Pit Location: N:

Surf. Elev.: $129.0\pm$

Elev. from: Topo

Offset Elev:

E:

Hammer Wt.
Hammer Drop:
Sampler Size:

Pit Width: 3.5' Pit Length: 45'

Orientation: E-W
Excavator:

TEST PIT NO. **TP-12** JOB NO. **16163**

Page 1 of 1


Office: (410) 553-0802

Fax #: (410) 553-0808

Foreman: Allied Inspector: JFD

Date Started: 6/8/2016

Date Finished: 6/8/2016



ı	Notes: Surface elevations from topographic map provided by Ben Dyer	
	Associates, Inc.	

Enc	ountered	8.0'	
Con	npletion		
On	at		
On	at		

Water

Project Name: Glenarden Apartments Contracted With: Pennrose Properties

Project Location: Prince George's County, Maryland

Test Pit Location: N:

Surf. Elev.: $130.0\pm$

Elev. from: Topo

Offset Elev:

Hammer Wt. Hammer Drop: Sampler Size:

Pit Width: 3.5 Pit Length: 18' Orientation: N-S Foreman: Allied Inspector: JFD Date Started: 6/8/2016

Date Finished: 6/8/2016

TEST PIT NO. TP-13

Page 1 of 1

JOB NO. 16163

Office: (410) 553-0802

Fax #: (410) 553-0808

Offset Dist.: Offset Direction: Excavator: Elev. Soil Description Sample Boring & Sample Depth Color, Moisture, Density Plasticity, Size Proportions 130.0± Notes 130 -0.0 0 Pit starts 15.0' South of B-51 Orange brown, moist, medium plastic, sandy lean CLAY with gravel up to cobble (1.0' Diameter) (Cinder Blocks) (FILL) ÙSC: (CL)* 128 2 126 @ 5.0' Encountered Buried Concrete slab from Orange, wet, non to low plastic, start of pit to 9.0' South of start (Column footing) silty fine SAND (Natural) USC: (`SM)* 124 6 Test Pit Terminated at 6 Ft. 122 8 120 10 118 12

١	Notes: Surface elev	ations from topographic map provided by Ben Dyer	
	Associates,	Inc.	

		Water	Caved
Enc	ountered	4.0'	
Con	npletion		
On	at		
On	at		

Project Name: Glenarden Apartments
Contracted With: Pennrose Properties

Project Location: Prince George's County, Maryland

Test Pit Location: N:

Surf. Elev.: $130.0\pm$

Elev. from: Topo

Offset Elev:

□.

Hammer Wt.
Hammer Drop:
Sampler Size:

Pit Width: 3.5'
Pit Length: 15'
Orientation: E-W

TEST PIT NO. **TP-14**JOB NO. 16163

Page 1 of 1


Office: (410) 553-0802

Fax #: (410) 553-0808

Foreman: Allied Inspector: JFD

Date Started: 6/8/2016

Date Finished: 6/8/2016



* Visual Description - in general accord	dance with ASTM D 2488
--	------------------------

Notes: Surface elevations from topographic map provided by Ben Dyer
Associates, Inc.

Encountered		Dry	
Cor	npletion		
On	at		
On	at		

Water

Office: (410) 553-0802

Fax #: (410) 553-0808

Water

Caved

Project Name: Glenarden Apartments

Contracted With: Pennrose Properties

Project Location: Prince George's County, Maryland


TEST PIT NO. TP-15

JOB NO. 16163

Page 1 of 1

Test Pit Location: N: E:

Surf. Elev.: $136.0\pm$ Pit Width: 3.5' Foreman: Allied Hammer Wt. Elev. from: Topo Pit Length: 22' Inspector: JFD Hammer Drop: Date Started: 6/8/2016 Offset Elev: Orientation: N-S Sampler Size: Date Finished: 6/8/2016 Offset Dist.: Offset Direction: Excavator:



* Visual Description - in general accordance with AST

Notes: Surface elevations from topographic map provided by Ben Dyer	Encountered Dry
Associates, Inc.	Completion
	On at
	On at

Project Name: Glenarden Apartments
Contracted With: Pennrose Properties

Project Location: Prince George's County, Maryland
Test Pit Location: N: E:

est Pit Location: IN:

TEST PIT NO. **TP-16**JOB NO. 16163
Page 1 of 1


Office: (410) 553-0802

Fax #: (410) 553-0808

Foreman: Allied Inspector: JFD

Date Started: 6/8/2016

Date Finished: 6/8/2016



* Visual Description - in general accordance with ASTM D 2488

-	Notes: Surface elevations fr	om topographic map provided by Ben Dyer
	Associates, Inc.	

Encountered		Dry	
Cor	npletion		
On	at		
On	at		

Water

Pit Width: 3.5

Orientation: NE-SW

Pit Length: 15'

Project Name: Glenarden Apartments
Contracted With: Pennrose Properties

Project Location: Prince George's County, Maryland

Test Pit Location: N:

теѕт ріт no. **ТР-17** јов no. 16163 Page 1 of 1

Foreman: Allied


rageroni


Office: (410) 553-0802

Fax #: (410) 553-0808

Inspector: JFD

Date Started: 6/8/2016





Notes: Surface elevations from topographic map provided by Ben Dyer
Associates, Inc.

Enc	ountered	2.5'	
Completion			
On	at		
On	at		

Water

Project Name: Glenarden Apartments

Contracted With: Pennrose Properties

TEST PIT NO. TP-18

JOB NO. 16163

Project Location: Prince George's County, Maryland
Test Pit Location: N: E:

Foreman: Allied
Inspector: JFD
Date Started: 6/8/2016

Page 1 of 1

Office: (410) 553-0802

Fax #: (410) 553-0808

Date Finished: 6/8/2016 Offset Dist.: Offset Direction: Excavator: Elev. Sample Soil Description Boring & Sample Depth Color, Moisture, Density Plasticity, Size Proportions 132.0± Notes 132 0 Gray mottled orange, moist, non to low plastic, fine SAND with silt, some gravel (Natural) (Iron Cemented Sand) USC: (SM)* 130 2 @ 3.5' Encountered Buried Storm Drain (Fill with asphalt around Storm Drain) 128 4 -126 6 Test Pit Terminated at 7 Ft. 124 8 122 10 120 12

* Visual Description - in general ac	accordance with ASTM D 2488
--------------------------------------	-----------------------------

Notes: Surface elevations from topographic map provided by Ben Dyer
Associates, Inc.

End	ountered	Dry	
Cor	npletion		
On	at		
On	at		

Water

Project Name: Glenarden Apartments

Contracted With: Pennrose Properties

TEST PIT NO. TP-19

JOB NO. 16163

Project Location: Prince George's County, Maryland
Test Pit Location: N: E:


Page 1 of 1


Office: (410) 553-0802

Fax #: (410) 553-0808

Inspector: JFD
Date Started: 6/8/2016
Date Finished: 6/8/2016

Foreman: Allied





1	Notes: Surface elevations from topogra	aphic map provided by Ben Dyer
	Associates, Inc.	

Encountered 3.0'								
Con	npletion							
On	at							
On	at							

Water

Project Name: Glenarden Apartments Contracted With: Pennrose Properties

Project Location: Prince George's County, Maryland

Test Pit Location: N:

Surf. Elev.: $130.0\pm$

Elev. from: Topo

Offset Elev:

Hammer Wt.

Hammer Drop: Sampler Size: Pit Width: 3.5'
Pit Length: 60'

Orientation: E-W Excavator:

TEST PIT NO. **TP-20** JOB NO. 16163

Page 1 of 1


Office: (410) 553-0802

Fax #: (410) 553-0808

Foreman: Allied Inspector: JFD

Date Started: 6/8/2016

Date Finished: 6/8/2016



* Visual Description - in general accordance with ASTM D 2488

Notes: Surface elevations from topographic map provided by Ben Dyer Associates, Inc.

Encountered Dry								
Con	npletion							
On	at							
On	at							

Water

Project Name: Glenarden Apartments
Contracted With: Pennrose Properties

Project Location: Prince George's County, Maryland

Test Pit Location: N:

Offset Elev:

Hammer Wt. Pit Width: 3.5'
Hammer Drop: Pit Length: 30'
Sampler Size: Orientation: N-S

TEST PIT NO. **TP-21**JOB NO. 16163
Page 1 of 1

Office: (410) 553-0802


Fax #: (410) 553-0808


Foreman: Allied

Date Started: 6/8/2016

Date Finished: 6/8/2016

Inspector: JFD





1	Notes: Surface elevations from topogra	aphic map provided by Ben Dyer
	Associates, Inc.	

Encountered 6.0'								
Con	npletion							
On	at							
On	at							

Water

Project Name: Glenarden Apartments
Contracted With: Pennrose Properties

Project Location: Prince George's County, Maryland
Test Pit Location: N: E:

Surf. Elev.: 105.0± Hammer Wt. Pit Width: 3.5' Elev. from: Topo Hammer Drop: Pit Length: 40' Offset Elev: Sampler Size: Orientation: E-W

TEST PIT NO. **TP-22**JOB NO. 16163
Page 1 of 1

Office: (410) 553-0802

Fax #: (410) 553-0808

Inspector: JFD
Date Started: 6/8/2016

Foreman: Allied

Date Finished: 6/8/2016 Offset Dist.: Offset Direction: Excavator: Elev. Soil Description Sample Boring & Sample Depth Color, Moisture, Density Plasticity, Size Proportions 105.0± Notes 0 -0.0 Dark brown, moist, low plastic, fine SAND with silt and gravel and organics (Brick and 104 concrete) (Topsoil) (FILL) ÙSĊ: (SM`)* 2 102 Orange, moist, non to low plastic, silty fine SAND, some gravel (Natural) 4 -USC: (SM)* 100 Test Pit Terminated at 5 Ft. 6 98 8 96 10 94 12

Notes: Surface elevations from topographic map provided by Ben Dyer
Associates, Inc.

Encountered Dry								
Con	npletion							
On	at							
On	at							

Water

KEY TO SYMBOLS

Symbol Description

Misc. Symbols

Water level at completion

₩ater encountered during drilling

Soil Samplers

Bag Sample

Strata

Poorly graded SAND with silt

Medium to highly plastic CLAY

Silty SAND

Clayey SAND

Lean CLAY

Silty clayey SAND

// Fat CLAY

Poorly graded SAND

Topsoil

Notes:

- 1. Borings were performed from May 18, 2016 through May 20, 2016. Test pits were performed from June 1, 2016 through June 8, 2016.
- 2. These logs are subject to the limitations, conclusions, and recommendations in this report.
- 3. PP indicates results of pocket penetrometer, used to estimate the unconfined compressive strength of fine-grained soils.

APPENDIX C LABORATORY TEST RESULTS

Project: Glenarden Apartments

Job #: 16163

Report Date: 6/9/2016 Report Status: Final

						1100			- BI .:				
Lab				Moisture		USC	Liquid	Plastic	Plastic	%	%	%	
Number	Boring	Sample	Depth	Content	Description	Class.	Limit	Limit	Index	Gravel	Sand	Fines	Notes
160251	B-34	S-1	0.0'-1.5'	8.2%									
160252	B-34	S-2	2.5'-4.0'	12.5%									
160253	B-34	S-3	5.0'-6.5'	19.5%									
160254	B-34	S-4	8.5'-10.0'	22.2%									
100201	50.	•	0.0 10.0										
160255	B-36	S-1	0.0'-1.5'	12.3%									
160256	B-36	S-2	2.5'-4.0'	15.7%									
160257	B-36	S-3	5.0'-6.5'	12.6%									
160258	B-36	S-4	8.5'-10.0'	7.0%									
400000	D 07	C 4	0.51.40.01	20.00/	Brownish yellow, fat CLAY with fine to	CLI	5 4	0.5	00	0	00	00	
160206	B-37	S-4	8.5'-10.0'	30.6%	very fine sand	СН	54	25	29	0	20	80	
160259	B-38	S-1	0.0'-1.5'	12.5%									
160260	B-38	S-2	2.5'-4.0'	16.5%									
160261	B-38	S-3	5.0'-6.5'	14.5%									
160262	B-38	S-4	8.5'-10.0'	16.8%									
160263	B-40	S-1	0.0'-1.5'	19.6%									
160264	B-40	S-2	2.5'-4.0'	19.7%									
160265	B-40	S-3	5.0'-6.5'	21.1%									
160266	B-40	S-4	8.5'-10.0'	25.6%									
				4= =0/									
160267	B-42	S-1	0.0'-1.5'	17.7%									
160268	B-42	S-2	2.5'-4.0'	13.6%									
160269	B-42	S-3	5.0'-6.5'	20.1%									
160270	B-42	S-4	8.5'-10.0'	18.1%									
160074	D 40	C 1	0.014.51	12.0%									
160271	B-49	S-1	0.0'-1.5'	18.6%									
160272	B-49	S-2	2.5'-4.0'	22.8%									
160273	B-49	S-3 S-4	5.0'-6.5'	22.8% 21.9%									
160274	B-49	5-4	8.5'-10.0'	۷۱.370									
160275	B-51	S-1	0.0'-1.5'	16.7%									
160275	B-51	S-1	2.5'-4.0'	18.8%									
160276	B-51	S-2 S-3	5.0'-6.5'	18.6%									
160277	B-51	S-3	8.5'-10.0'	15.2%									
100270	D 01	0 4	0.0 - 10.0	. 5.2 70									

Project: Glenarden Apartments

Report Date: 6/9/2016 Job #: 16163 Report Status: Final

Lab				Moisture		USC	Liquid	Plastic	Plastic	%	%	%	
Number	Boring	Sample	Depth	Content	Description	Class.	Limit	Limit	Index	Gravel	Sand	Fines	Notes
160279	B-53	S-1	0.0'-1.5'	12.9%	·								
160280	B-53	S-2	2.5'-4.0'	15.4%									
160281	B-53	S-3	5.0'-6.5'	12.4%									
160282	B-53	S-4	8.5'-10.0'	18.8%									
160283	B-55	S-1	0.0'-1.5'	13.0%									
160284	B-55	S-2	2.5'-4.0'	13.0%									
160285	B-55	S-3	5.0'-6.5'	7.5%									
160286	B-55	S-4	8.5'-10.0'	16.1%									
160287	B-57	S-1	0.0'-1.5'	16.1%									
160288	B-57	S-2	2.5'-4.0'	9.1%									
160289	B-57	S-3	5.0'-6.5'	7.6%									
160290	B-57	S-4	8.5'-10.0'	21.0%									
160291	R-13	S-1	0.0'-1.5'	15.1%									
160292	R-13	S-2	2.5'-4.0'	-							Е	Bit. Conc. in	sample, no moisture
160293	R-13	S-3	5.0'-6.5'	-							Е	Bit. Conc. in	sample, no moisture
160294	R-13	S-4	8.5'-10.0'	18.7%									-
160295	R-13	S-5	13.5'-15.'	22.1%									
160205	R-14	Bulk	0'-8'	17.4% Pink	x, very fine sandy lean CLAY	CL	25	17	8	6	39	55	
160296	R-14	S-1	0.0'-1.5'	23.6%									
160297	R-14	S-2	2.5'-4.0'	19.0%									
160298	R-14	S-3	5.0'-6.5'	20.4%									
160299	R-14	S-4	8.5'-10.0'	17.7%									
160300	R-14	S-5	13.5'-15.0'	9.5%									
160301	R-14	S-6	16.5'-18.0'	7.0%									
160302	R-15	S-1	0.0'-1.5'	15.0%									
160303	R-15	S-2	2.5'-4.0'	9.5%									
160304	R-15	S-3	5.0'-6.5'	19.7%									
160305	R-15	S-4	8.5'-10.0'	16.6%									
160358	R-16	S-1	0.5'-1.7'	9.7%									
160359	R-16	S-2	3.9'-4.0'	7.3%									
160360	R-16	S-3	5.0'-6.0'	9.9%									
160361	R-16	S-4	7.5'-8.0'	7.9%									
160362	R-16	S-5	9.5'-10.0'	25.6%									

Project: Glenarden Apartments

Report Date: 6/9/2016 Job #: 16163 Report Status: Final

Lab				Moisture		USC	Liquid	Plastic	Plastic	%	%	%	
Number	Boring	Sample	Depth	Content	Description	Class.	Limit	Limit	Index	Gravel	Sand	Fines	Notes
160306	R-17	S-1	0.0'-1.5'	21.4%	·								
160307	R-17	S-2	2.5'-4.0'	15.5%									
160308	R-17	S-3	5.0'-6.5'	7.9%									
160309	R-17	S-4	9.5'-11.0'	5.5%									
160310	R-18	S-1	0.0'-1.5'	11.9%									
160311	R-18	S-2	2.5'-4.0'	12.9%									
160312	R-18	S-3	5.0'-6.5'	15.0%									
160313	R-18	S-4	8.5'-10.0'	8.7%									
160314	R-18	S-5	11.5'-13.0'	5.1%									
160315	R-19	S-1	0.0'-1.5'	15.8%									
160316	R-19	S-1	2.5'-4.0'	6.4%									
160317	R-19	S-3	5.0'-6.5'	5.2%									
160317	R-19	S-4	9.5'-11.0'	23.3%									
100310	10 10	0 +	9.5-11.0	20.070									
160319	R-20	S-1	0.0'-1.5'	12.0%									
160320	R-20	S-2	2.5'-4.0'	14.0%									
160321	R-20	S-3	5.0'-6.5'	12.4%									
160322	R-20	S-4	80'-10.5'	23.1%									
160323	R-20	S-5	13.5'-15.0'	21.9%									
160324	R-21	S-1	0.0'-1.5'	17.6%									
160325	R-21	S-2	2.5'-4.0'	13.6%									
160326	R-21	S-3	5.0'-6.5'	13.4%									
160327	R-21	S-4	8.5'-10.0'	15.8%									
160328	R-21	S-5	13.5'-15.0'	19.9%									
100000	D 00	0.4	0.01.4.51	4E C0/									
160329	R-22	S-1	0.0'-1.5'	15.6%									
160330	R-22	S-2	2.5'-4.0'	19.8%									
160331	R-22	S-3	5.0'-6.5'	18.8%									
160332	R-22	S-4	8.5'-10.0'	15.8%									
160333	R-23	S-1	0.0'-1.5'	21.0%									
160334	R-23	S-2	2.5'-4.0'	17.4%									
160335	R-23	S-3	5.0'-6.5'	14.7%									
160336	R-23	S-4	8.5'-10.0'	20.9%									

Project: Glenarden Apartments

Job #: 16163


Report Date: 6/9/2016 Report Status: Final

	Lab				Moisture		USC	Liquid	Plastic	Plastic	%	%	%	
١	Number	Boring	Sample	Depth	Content	Description	Class.	Limit	Limit	Index	Gravel	Sand	Fines	Notes
	160337	R-24	S-1	0.0'-1.5'	13.5%	·								
	160338	R-24	S-2	2.5'-4.0'	12.9%									
	160339	R-24	S-3	5.0'-6.5'	9.7%									
	160340	R-24	S-4	8.5'-10.0'	9.6%									
	160341	R-24	S-5	10.0'-12.0'	16.0%									
•	160342	R-26	S-1	0.0'-1.5'	13.5%									
•	160343	R-26	S-2	2.5'-4.0'	20.4%									
•	160344	R-26	S-3	5.0'-6.5'	16.5%									
•	160345	R-26	S-4	8.5'-10.0'	15.8%									
		SWM-08	S-1	0.0'-1.5'	13.4%									
		SWM-08	S-2	2.5'-4.0'	28.4%									
	160348	SWM-08	S-3	5.0'-6.5'	20.0%									
•	160349	SWM-08	S-4	8.5'-10.0'	26.4%									
	160350	SWM-10	S-1	0.0'-1.5'	13.9%									
	160351	SWM-10	S-2	2.5'-4.0'	12.8%									
	160352	SWM-10	S-3	5.0'-6.5'	13.3%									
•	160353	SWM-10	S-4	8.5'-10.0'	18.4%									
•	160242	TP-01	S-1	0'-1'	19.0%									
•	160243	TP-02	S-1	1'-2'	17.9%									
	100011	TD 00	0.4	01.41	45.00/									
	160244	TP-03	S-1	3'-4'	15.8%									
	100015	TD 04	0.4	41.01	00.70/									
	160245	TP-04	S-1	1'-2'	32.7%									
	100040	TD 05	C 4	01.41	7.00/									
	160246	TP-05	S-1	0'-1'	7.8%									
	160247	TP-06	S-1	1'-2'	16.5%									
	160247	17-06	3-1	1 -2	10.5%									
	160240	TP-07	S-1	1'-2'	12.6% Stron	g brown, silty fine to very fine SAND	SM	21	18	3	9	58	33	
	160240	TP-07	S-1	4'-5'		g brown, silty fine to very fine SAND	SM	NP			5	78	33 17	
	100241	11-01	3-2	4-5	10.170 30011	g blown, silty line to very line SAND	Sivi	INF			3	70	17	
	160248	TP-08	S-1	1'-2'	14.3%									
	100270	11 -00	0 -1	1 -2	17.0/0									
	160249	TP-09	S-1	1'-2'	12.4%									
	.002 10	11 00	0 .		12.770									
	160250	TP-10	S-1	1'-2'	14.1%									
Harden Roll (Association Land														
	н	arain-Kia	1717 ASSC	ICIATES INC.		Dogg 4	of 1							Dath: C:\Lab Eilaa\2016\

Hardin-Kight Associates, Inc. Glen Burnie, MD 21061

Page 4 of 4 Lab Summary.xls Revision Date: 2/16/2012 Path: C:\Lab Files\2016\ File: 160242 to 160353 Lab Summary Final Printed: 6/9/2016 Project: Glenarden Apartments
Identification: B-37, S-4, 8.5'-10.0'
Description: Brownish yellow, fat CLAY with fine to very fine sand

Job #: 16163 Lab #: 160206 Report Date: 6/8/2016 Report Status: Final




ID: 2110704.02001 Rev: 2-6-2015

Project: Glenarden Apartments Identification: R-14, Bulk, 0'-8'

Description: Pink, very fine sandy lean CLAY

Lab #: 160205 Report Date: 6/6/2016 Report Status: Final

Job #: 16163



ID: 2110704.02001 Rev: 2-6-2015

Moisture Density Relationship

Lab #: 160205 Project: Glenarden Apartments Job #: 16163 Report Date: 6/9/2016 Identification: R-14, Bulk, 0'-8' Report Status: Preliminary Description: Pink, very fine sandy lean CLAY See Note Moisture Content: 17.0% Sample Received: 5/20/2016 Maximum Dry Density: 116.2pcf Test Method: AASHTO T99 A Optimum Moisture: 12.0% Zero Air Void Specific Gravity: 2.60 120 pcf - - Zero Air Voids ----- 80% ZAV Line **CBR Pts** 115 pcf D У 110 pcf D е n 105 pcf t У 100 pcf р С 95 pcf 90 pcf 35% 0% 5% 10% 15% 20% 25% 30% Moisture Content Gradation - Oversize Received Molded Additional testing for this sample is ongoing 0% 0% -2":+3/4" 1% 0% which may impact the results shown. -3/4":+3/8" 2% 2% 0% -3/8":+#4 2% 2% 0% -#4 95% 96% 100% Tested By: Checked By:

Form: MDR Curve


Revised: 5/2011

Project: Glenarden Apartments Identification: R-16, Bulk, 4'-5' Description: Reddish yellow, silty fine to very fine SAND

Lab #: 160357 Report Date: 6/10/2016 Report Status: Final

Job #: 16163

Received: 6/8/2016



Moisture Density Relationship


Project: Glenarden Apartments Lab #: 160357 Job #: 16163 Report Date: 6/10/2016 Identification: R-16, Bulk, 4'-5' Report Status: Preliminary Description: Reddish yellow, silty fine to very fine SAND See Note Moisture Content: 7.0% Sample Received: 6/8/2016 Maximum Dry Density: 104.0pcf Test Method: AASHTO T99 A Optimum Moisture: 13.9% Zero Air Void Specific Gravity: 2.40 120 pcf - Zero Air Voids --- 80% ZAV Line **CBR Pts** 115 pcf D У 110 pcf D е n 105 pcf t У 100 pcf р С 95 pcf 90 pcf 0% 5% 10% 15% 20% 25% 30% 35% Moisture Content - Oversize Gradation Received Molded 0% 0% Additional testing for this sample is ongoing -2":+3/4" 1% 0% which may impact the results shown. -3/4":+3/8" 2% 2% 0% -3/8":+#4 2% 2% 0% -#4 95% 96% 100% Tested By: Checked By:

Form: MDR Curve

Revised: 5/2011

Project: Glenarden Apartments Identification: TP-7, S-1, 1'-2' Description: Strong brown, silty fine to very fine SAND

Job #: 16163 Lab #: 160240 Report Date: 6/8/2016 Report Status: Final



ID: 2110704.02001 Rev: 2-6-2015

Project: Glenarden Apartments Identification: TP-7, S-2, 4'-5' Description: Strong brown, silty fine to very fine SAND

Job #: 16163 Lab #: 160241 Report Date: 6/8/2016 Report Status: Final

Received: 5/20/2016

