



Notes:

1. Remove existing grab bars if present and install new grab bars, per spec
2. Remove existing lavatory and install new lavatory
3. Install bathtub seat
4. Remove existing shower head and install new hand held shower unit
5. Shower controls to be located in this area
6. Existing tub to remain
7. Remove existing toilet tissue holder and install new toilet tissue holder
8. Remove existing toilet and install new toilet
9. Remove existing medicine cabinet and mirror; install new medicine cabinet and mirror
10. Remove existing mirror and install new mirror
11. Remove existing towel rack and install new towel rack
12. Remove existing lavatory; install new lavatory/vanity unit
13. Remove existing medicine cabinet and install new medicine cabinet
14. Remove existing porcelain surrounds at existing tub; existing tub to remain
15. Remove existing ceramic tile floor and install new ceramic tile flooring and 6x6" Tub surround
16. Existing light to remain
17. Existing towel dispenser to remain
18. Remove existing soap dispenser and install new soap dispenser
19. Install blocking in existing wall to support grab bars
20. Remove existing toothbrush/tumbler holder; install new toothbrush/tumbler holder
21. Remove existing soap dish; install new soap dish
22. Insulate all exposed pipes
23. Repair existing ceramic tile as required
24. Remove existing towel dispenser and install new towel dispenser
25. Remove existing mirror and install new tilt mirror.

Housing Authority of Prince George's County -
Marlborough Towne Renovation

1 bedroom Unit (Typical)
Bathroom Elevations

A.3